## CONTRIBUTING ZONE PLAN MODIFICATION APPLICATION

**FOR** 

# PEC LIBERTY HILL (PEDERNALES ELECTRIC COOPERATIVE SERVICE CENTER)

10625 W TX-29 Liberty Hill, Texas 78642

### Prepared For:

PEDERNALES ELECTRIC COOPERATIVE, INC 201 S. AVENUE F AUSTIN, TEXAS 78736


P.O. Box 1 Johnson City, Texas 78636 (registered mailing address)

### Prepared By:



Sandlin Services, LLC TBPELS Firm # 21356 P: (806) 679-7303

March 20, 2024





### TABLE OF CONTENTS

Edwards Aquifer Application Cover Page (TCEQ-20705)

Modification of a Previously Approved Contributing Zone Plan Form (TCEQ-10259)

Attachment A – Original Approval Letter and Approved Modification Letters

Attachment B – Narrative of Proposed Modification

Attachment C – Current Site Plan of the Approved Project

Contributing Zone Plan Application (TCEQ-10257)

Attachment A – Road Map

Attachment B – USGS Quadrangle Map

Attachment C - Project Narrative

Attachment D – Factors Affecting Surface Water Quality

Attachment E – Volume and Character of Stormwater

Attachment F – Suitability Letter from Authorized Agent (if OSSF is proposed)

Attachment G – Alternative Secondary Containment Methods (if proposed)

Attachment H – AST Containment Structure Drawing (if AST is proposed)

Attachment I – 20% or Less Impervious Cover Declaration (if applicable)

Attachment J – BMPs for Upgradient Stormwater

Attachment K – BMPs for On-site Stormwater

Attachment L – PMTs for Surface Streams

Attachment M – Construction Plans

Attachment N - Inspection, Maintenance, Repair and Retrofit Plan

Attachment O – Pilot-Scale Field Testing Plan, if BMPs not based on Complying with the Edwards

Aguifer Rules: Technical Guidance for BMPs

Attachment P – Measures for Minimizing Surface Stream Contamination

#### SWPPP or Temporary Stormwater Section (TCEQ-0602)

Attachment A – Spill Response Actions

Attachment B – Potential Sources of Contamination

Attachment C – Sequence of Major Activities

Attachment D – Temporary Best Management Practices and Measures

Attachment E – Request to Temporarily Seal a Feature, if sealing a feature

Attachment F – Structural Practices

Attachment G – Drainage Area Map

Attachment H – Temporary Sediment Pond(s) Plans and Calculations

Attachment I – Inspection and maintenance for BMPs

Attachment J – Schedule of Interim and Permanent Soil Stabilization Practices

Copy of Notice of Intent (NOI)

Agent Authorization Form (TCEQ-0599)





Application Fee Form (TCEQ-0574)

Check Payable to the "Texas Commission on Environmental Quality"

Core Data Form (TCEQ-10400)



## **Edwards Aquifer Application Cover Page** (TCEQ-20705)

### **Texas Commission on Environmental Quality**

# **Edwards Aquifer Application Cover Page**

#### **Our Review of Your Application**

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with 30 TAC 213.

#### **Administrative Review**

- Edwards Aquifer applications must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.
  - To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: <a href="http://www.tceq.texas.gov/field/eapp">http://www.tceq.texas.gov/field/eapp</a>.
- 2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
- 3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
- 4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.
  - An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.
- 5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
- 6. If the geologic assessment was completed before October 1, 2004 and the site contains "possibly sensitive" features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

#### **Technical Review**

- When an application is deemed administratively complete, the technical review period begins. The regional
  office will distribute copies of the application to the identified affected city, county, and groundwater
  conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days
  to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
- 2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

- clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.
- 3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
- 4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

#### **Mid-Review Modifications**

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a "Mid-Review Modification". Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ's Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ's San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

1. Regulated Entity N	berty Hill	2. Regulated Entity No.: 105473979			
3. Customer Name: Pedernales Electric Cooperative INC		4. Customer No.: 601327927			
5. Project Type: (Please circle/check one)	New	Modification	Extension	Exception	
6. Plan Type: (Please circle/check one)	WPAP CZP	SCS UST AST	EXP EXT	Technical Clarification	Optional Enhanced Measures
7. Land Use: (Please circle/check one)	Residential	Non-residential	8. Sit	e (acres):	6.22
9. Application Fee:	\$5,000	10. Permanent I	10. Permanent BMP(s):		hange
11. SCS (Linear Ft.):	0	12. AST/UST (No. Tanks):		1 - 10,000 gal split (7000/3000)	
13. County:	Williamson	14. Watershed:		South Fork San Gabriel River	

## **Application Distribution**

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the "Texas Groundwater Conservation Districts within the EAPP Boundaries" map found at:

http://www.tceq.texas.gov/assets/public/compliance/field\_ops/eapp/EAPP%20GWCD%20map.pdf


For more detailed boundaries, please contact the conservation district directly.

Austin Region					
County:	Hays	Travis	Williamson		
Original (1 req.)	_	_	_1_		
Region (1 req.)	_	_	_1_		
County(ies)	_		_1_		
Groundwater Conservation District(s)	Edwards Aquifer AuthorityBarton Springs/ Edwards AquiferHays TrinityPlum Creek	Barton Springs/ Edwards Aquifer	NA		
City(ies) Jurisdiction	AustinBudaDripping SpringsKyleMountain CitySan MarcosWimberleyWoodcreek	AustinBee CavePflugervilleRollingwoodRound RockSunset ValleyWest Lake Hills	AustinCedar ParkFlorenceGeorgetownJerrellLeander _1_Liberty HillPflugervilleRound Rock		

San Antonio Region					
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)	_	_		_	_
Region (1 req.)	_			_	_
County(ies)			_		
Groundwater Conservation District(s)	Edwards Aquifer Authority Trinity-Glen Rose	Edwards Aquifer Authority	Kinney	EAA Medina	EAA Uvalde
City(ies) Jurisdiction	Castle HillsFair Oaks RanchHelotesHill Country VillageHollywood ParkSan Antonio (SAWS)Shavano Park	BulverdeFair Oaks RanchGarden RidgeNew BraunfelsSchertz	NA	San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.		
Nick Sandlin, P.E. (Sandlin Services, LLC)		
Print Name of Customer/Authorized Agent		
Nive Some	3/20/2024	
Signature of Customer/Authorized Agent	Date	

**FOR TCEQ INTERNAL USE ONLY**				
Date(s)Reviewed: Date Administratively Complete:				
Received From:	Correct Number of Copies:			
Received By:	Distribution Date:			
EAPP File Number:	Complex:			
Admin. Review(s) (No.):	No. AR Rounds:			
Delinquent Fees (Y/N):	Review Time Spent:			
Lat./Long. Verified:	SOS Customer Verification:			
Agent Authorization Complete/Notarized (Y/N):	Payable to TCEQ (Y/N):			
Core Data Form Complete (Y/N):	Check: Signed (Y/N):			
Core Data Form Incomplete Nos.:	Less than 90 days old (Y/N):			





# Modification of a Previously Approved Contributing Zone Plan (TCEQ-10259)

# Modification of a Previously Approved Contributing Zone Plan

**Texas Commission on Environmental Quality** 

for Regulated Activities on the Edwards Aquifer Recharge Zone and Transition Zone and Relating to 30 TAC 213.4(j), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

### Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Modification of a Previously Approved Contributing Zone Plan** is hereby submitted for TCEQ review and executive director approval. The request was prepared by:

Print Name of Customer/Agent: Nick Sandlin, P.E. (Sandlin Services, LLC)

Date: 3/20/2024

Signature of Customer/Agent:

## **Project Information**

1. Current Regulated Entity Name: PEC Liberty Hill

Original Regulated Entity Name: Seward Junction Office And Warehouse

Assigned Regulated Entity Number(s) (RN): 105473979

Edwards Aquifer Protection Program ID Number(s): <u>11-08030503 and 11001078</u>

- The applicant has not changed and the Customer Number (CN) is: 601327927
- The applicant or Regulated Entity has changed. A new Core Data Form has been

provided.

- 2. Attachment A: Original Approval Letter and Approved Modification Letters. A copy of the original approval letter and copies of any modification approval letters are attached.
- 3. A modification of a previously approved plan is requested for (check all that apply):

3/20/2024

	Any physical or operational modification of any best management practices or structure(s), including but not limited to temporary or permanent ponds, dams, berms, silt fences, and diversionary structures;
	Any change in the nature or character of the regulated activity from that which was
	originally approved;
	<ul> <li>A change that would significantly impact the ability to prevent pollution of the</li> <li>Edwards Aquifer and hydrologically connected surface water; or</li> </ul>
	Any development of land previously identified in a contributing zone plan as undeveloped.
l.	Summary of Proposed Modifications (select plan type being modified). If the approved plan has been modified more than once, copy the appropriate table below, as necessary, and complete the information for each additional modification.

CZP Modification	Approved Project	Proposed Modification
Summary		
Acres	8.22 AC Total (2 Lots - 6.22	N/A
Type of Development	AC & 2 AC)	<u>N/A</u>
Number of Residential	Industrial	N/A
Lots	<u>0</u>	
Impervious Cover (acres)		N/A
Impervious Cover (%)	<u>5.61</u>	<u>N/A</u>
Permanent BMPs	<u>68.2</u>	<u>N/A</u>
Other	Sand Filter System	
AST Modification	Approved Project	<b>Proposed Modification</b>
Summary		
Number of ASTs	<u>0</u>	<u>1- 10,000 gal split tank</u>
Other		
UST Modification	Approved Project	<b>Proposed Modification</b>
Summary		
Number of USTs		
Other		

5.	Attachment B: Narrative of Proposed Modification. A detailed narrative description of the nature of the proposed modification is attached. It discusses what was approved, including previous modifications, and how this proposed modification will change the approved plan.
6.	Attachment C: Current Site Plan of the Approved Project. A current site plan showing the existing site development (i.e., current site layout) at the time this application for modification is attached. A site plan detailing the changes proposed in the submitted modification is required elsewhere.  The approved construction has not commenced. The original approval letter and any subsequent modification approval letters are included as Attachment A to document that the approval has not expired.  The approved construction has commenced and has been completed. Attachment C illustrates that the site was constructed as approved.  The approved construction has commenced and has been completed. Attachment C illustrates that the site was not constructed as approved.  The approved construction has commenced and has not been completed.  Attachment C illustrates that, thus far, the site was constructed as approved.  The approved construction has commenced and has not been completed.  Attachment C illustrates that, thus far, the site was not constructed as approved.
7.	Acreage has not been added to or removed from the approved plan.  Acreage has been added to or removed from the approved plan and is discussed in Attachment B: Narrative of Proposed Modification.
8.	Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.



# Modification of a Previously Approved Contributing Zone Plan (TCEQ-10259)

# Attachment A: Original Approval Letter and Approved Modification Letters

Buddy Garcia, *Chairman*Larry R. Soward, *Commissioner*Bryan W. Shaw, Ph.D., *Commissioner*Glenn Shankle, *Executive Director* 





## TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

April 16, 2008

Mr. Wayne McKee Pedernales Electric Cooperative, Inc. P.O. Box 1 Johnson City, TX 78636

Re: Edwards Aquifer, (Williamson County)

NAME OF PROJECT: Seward Junction Office and Warehouse PROJECT LOCATION: 10325 West Highway 29, Liberty Hill Request for Approval of a Contributing Zone Plan - CZP

30 Texas Administrative Code (TAC) Chapter 213 Edwards Aquifer

Edwards Aquifer Protection Program ID No.: 08030503

Dear Mr. McKee:

The Texas Commission on Environmental Quality (TCEQ) has completed its review of the CZP application for the referenced project submitted to the Austin Regional Office by Baker-Aicklen and Associates, Inc., on behalf of Pedernales Electric on March 5, 2008. Final review was completed after additional information was received on April 11, 2008. As presented to the TCEQ, the Temporary and Permanent Best Management Practices (BMPs) and construction plans were prepared by a Texas Licensed Professional Engineer and appear to be in general compliance with the requirements of 30 TAC Chapter 213. These planning materials were sealed, signed, and dated by a Texas Licensed Professional Engineer. Therefore, based on the engineer's concurrence of compliance, the planning materials for construction of the proposed project and pollution abatement measures are hereby approved subject to applicable state rules and the conditions in this letter. The applicant or a person affected may file with the chief clerk a motion for reconsideration of the executive director's final action on this Contributing Zone Plan. A motion for reconsideration must be filed no later than 23 days after the date of this approval letter. This approval expires two (2) years from the date of this letter unless, prior to the expiration date, more than 10% of the construction has commenced on the project or an extension of time has been requested.

#### PROJECT DESCRIPTION

The total site consists of 8.22 acres of undisturbed property located in the South San Gabriel stream basin. A 6.22 acre lot and a 2 acre lot will be combined to yield the total site. The project will include a customer service office, training facility, warehouse, maintenance yard, a water quality and detention pond, associated appurtenances. There will be a total of 5.61 acres of impervious cover (68.2%).

REPLY TO: REGION 11 • 2800 S. INTERSTATE HWY. 35, STE. 100 • AUSTIN, TEXAS 78704-5700 • 512-339-2929 • FAX 512-339-3795

Mr. Wayne McKee Page 2 April 16, 2008

Temporary best management practices (BMPs) consisting of silt fences, rock berms and stabilized construction entrances will be implemented to treat and control stormwater runoff during construction activities. Project wastewater will be disposed of by an on site septic system.

#### PERMANENT POLLUTION ABATEMENT MEASURES

Stormwater will be treated by a proposed sedimentation/filtration pond. The pond is designed to accept runoff from the site as well as 1.25 acres of upgradient stormwater. The water quality pond has a total volume of 34,048 cubic feet. The filtration basin has a volume of 6,656 cubic feet and the sedimentation basin has a volume of 27,393 cubic feet. The area of the filtration basin is 3,328 square feet. According to the CZP, the approved measures meet the required 80 percent removal of the increased load in total suspended solids caused by the project.

#### SPECIAL CONDITIONS

- I. Intentional discharges of sediment laden stormwater during construction are not allowed. If dewatering excavated areas and/or areas of accumulated stormwater becomes necessary, the discharge shall be filtered through appropriately selected temporary best management practices. These may include vegetative filter strips, sediment traps, rock berms, silt fence rings, etc.
- II. This approval does not authorize the installation of temporary aboveground storage tanks on this project. If the contractor desires to install a temporary aboveground storage tank for use during construction, an application to modify this approval must be submitted and approved prior to installation. The application must include information related to tank location and spill containment. Refer to Standard Condition No. 3 below.
- III. The holder of the approved Edwards Aquifer CZP must comply with all provisions of 30 TAC chapter 213 and all best management practices and measures contained in the application.

#### STANDARD CONDITIONS

1. Pursuant to Chapter 7 Subchapter C of the Texas Water Code, any violations of the requirements in 30 TAC Chapter 213 may result in administrative penalties.

#### Prior to Commencement of Construction:

- 2. All contractors conducting regulated activities at the referenced project location shall be provided a copy of this notice of approval. At least one complete copy of the approved Contributing Zone Plan and this notice of approval shall be maintained at the project until all regulated activities are completed.
- 3. Any modification to the activities described in the referenced CZP application following the date of approval may require the submittal of a plan to modify this approval, including the payment of appropriate fees and all information necessary for its review and approval prior to initiating construction of the modifications.

- 4. The applicant must provide written notification of intent to commence construction of the referenced project. Notification must be submitted to the Austin Regional Office no later than 48 hours prior to commencement of the regulated activity. Written notification must include the name of the approved plan and ID number for the regulated activity, the date on which the regulated activity will commence, and the name of the prime contractor with the name and telephone number of the contact person.
- 5. Temporary erosion and sedimentation (E&S) controls, i.e., silt fences, rock berms, stabilized construction entrances, or other controls described in the approved Storm Water Pollution Prevention Plan (SWPPP) must be installed prior to construction and maintained during construction. Temporary E&S controls may be removed when vegetation is established and the construction area is stabilized. The water quality pond shall be used as a sedimentation basin during construction. The TCEQ may monitor stormwater discharges from the site to evaluate the adequacy of temporary E&S control measures. Additional controls may be necessary if excessive solids are being discharged from the site.

#### **During Construction:**

- 6. During the course of regulated activities related to this project, the applicant or his agent shall comply with all applicable provisions of 30 TAC Chapter 213, Edwards Aquifer. The applicant shall remain responsible for the provisions and conditions of this approval until such responsibility is legally transferred to another person or entity.
- 7. If sediment escapes the construction site, the sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain). Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been significantly reduced. Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).
- 8. The following records shall be maintained and made available to the executive director upon request: the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 9. Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, and construction activities will not resume within 21 days. When the initiation of stabilization measures by the 14th day is precluded by weather conditions, stabilization measures shall be initiated as soon as practicable.

#### After Completion of Construction:

10. Upon legal transfer of this property, the new owner(s) is required to comply with all terms of the approved Contributing Zone Plan. If the new owner intends to commence any new regulated activity on the site, a new Contributing Zone Plan that specifically addresses the new activity must be submitted to the executive director. Approval of the

plan for the new regulated activity by the executive director is required prior to commencement of the new regulated activity.

- Owners of permanent BMPs and measures must insure that the BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the Austin Regional Office within 30 days of site completion.
- 12. The applicant shall be responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. The regulated entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred. A copy of the transfer of responsibility must be filed with the executive director through the Austin Regional Office within 30 days of the transfer. A copy of the transfer form (TCEQ-10263) is enclosed.
- 13. A Contributing Zone Plan approval or extension will expire and no extension will be granted if more than 50% of the total construction has not been completed within ten years from the initial approval of a plan. A new Contributing Zone Plan must be submitted to the Austin Regional Office with the appropriate fees for review and approval by the executive director prior to commencing any additional regulated activities.
- 14. At project locations where construction is initiated and abandoned, or not completed, the site shall be returned to a condition such that the aquifer is protected from potential contamination.

If you have any questions or require additional information, please contact Mr. Russ Alexander, P.G., of the Edwards Aquifer Protection Program of the Austin Regional Office at (512) 339-2929.

Sincer

Glenn Shankle

Executive Director

GS/raa

enclosure

cc: Mr. David Olson, Baker-Aicklen and Associates, Inc. Austin

Mr. Paulo C. Pinto, B.S., R.S., Director of Environmental Services, Williamson County Health District

Ms. Kathy Clark, City Secretary, City of Liberty Hill

Mr. Sam Roberts, P.E., Director of Public Works, City of Cedar Park

TCEO Central Records



# Modification of a Previously Approved Contributing Zone Plan (TCEQ-10259)

## Attachment B: Narrative of Proposed Modification

The proposed 0.15 AC development is the addition of an Excell Aboveground Storage Tank (AST) fuel island on the existing caliche-based parking/storage area. The fueling system will be backed up by one backup generator (150-gallon diesel). The proposed fuel island will include the following:

- 1. One (1) 10,000 Gallon double-walled AST split 7,000 gal Diesel/3,000 gal Gas UL 2085 Fireguard tank with rod ladder and e-vents
- 2. Two (2) 20-Gallon remote spill basins with 3" fill piping, 3" ball valves and 3" quick fill connections
- 3. Two (2) 2" X 3" overfill devices set at 90%
- 4. Two (2) DEF blue boxes with pulse output with external filters and 5-minute timers
- 5. Three (3) Centeron Cell Monitors with 500 call block
- 6. Franklin DEF nozzle and hose
- 7. One (1) Fuelmaster 6-hose FMS with network capable
- 8. One (1) 500-Gallon DEF Poly Tank


The proposed construction will not change the existing Impervious Cover (IC). Therefore, the CZP Modification request does not require additional Permanent BMPs. The existing and modified CZPs (EAPP 11-08030503 dated April 16, 2008 and EAPP 11001078 dated May 23, 2018) included a Sand Filter Basin Permanent BMP for stormwater water quality control. The proposed modification does not increase the Impervious Cover (IC) at the site. The existing sand filter basin BMP will continue to meet requirements to treat stormwater runoff at the site.




## Modification of a Previously Approved Contributing Zone Plan (TCEQ-10259)

Attachment C: Current Site Plan of the Approved Project

# FOR REFERENCE ONLY



# FOR REFERENCE ONLY





# **Contributing Zone Plan Application** (TCEQ-10257)

# **Contributing Zone Plan Application**

**Texas Commission on Environmental Quality** 

for Regulated Activities on the Contributing Zone to the Edwards Aquifer and Relating to 30 TAC §213.24(1), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

### Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Contributing Zone Plan Application** is hereby submitted for TCEQ review and Executive Director approval. The application was prepared by:

Print Name of Customer/Agent: Nick Sandlin, P.E. (Sandlin Services, LLC)

Date: <u>3/20/2024</u>

Signature of Customer/Agent:

Regulated Entity Name: PEC Liberty Hill

## **Project Information**

1. County: Williamson

2. Stream Basin: South Fork San Gabriel River

3. Groundwater Conservation District (if applicable): N/A

4. Customer (Applicant):

Contact Person: Bud Collora

Entity: Pedernales Electric Cooperative, Inc.

Mailing Address: P.O. Box 1
City, State: Johnson City, Texas
Telephone: 830-868-6056

Email Address: bud.collora@peci.com

Zip: <u>78636</u> Fax: \_\_\_\_

1 of 11

э.	Age	ent/Representative (if any):	
	Ent Ma City Tel	ntact Person: <u>Nick Sandlin, P.E.</u> ity: <u>Sandlin Services, LLC</u> iling Address: <u>9111 Jollyville Rd. Suite 212</u> y, State: <u>Austin, Texas</u> ephone: <u>806-679-7303</u> ail Address: <u>nick@sandlinservices.com</u>	Zip: <u>78759</u> Fax:
6.	Pro	eject Location:	
		The project site is located inside the city limits the project site is located outside the city limit jurisdiction) of  The project site is not located within any city's	s but inside the ETJ (extra-territorial
7.		The location of the project site is described bel provided so that the TCEQ's Regional staff can boundaries for a field investigation.	
		10625 W SH 29, Liberty Hill, TX 78642	
8.		<b>Attachment A - Road Map</b> . A road map showing project site is attached. The map clearly shows	
9.		Attachment B - USGS Quadrangle Map. A copy Quadrangle Map (Scale: 1" = 2000') is attached	
		<ul><li>✓ Project site boundaries.</li><li>✓ USGS Quadrangle Name(s).</li></ul>	
10.		<b>Attachment C - Project Narrative</b> . A detailed n project is attached. The project description is contains, at a minimum, the following details:	
		<ul> <li>Area of the site</li> <li>✓ Offsite areas</li> <li>✓ Impervious cover</li> <li>✓ Permanent BMP(s)</li> <li>✓ Proposed site use</li> <li>✓ Site history</li> <li>✓ Previous development</li> <li>✓ Area(s) to be demolished</li> </ul>	
11.	Exis	sting project site conditions are noted below:	
		Existing commercial site Existing industrial site Existing residential site	

Undeveloped (Cle	d/or unpaved roads ared) disturbed/Not cleared)		
12. The type of project is	:		
Residential: # of L Residential: # of L Commercial Industrial Other:	ots: iving Unit Equivalents: <sub>.</sub>		
13. Total project area (siz	e of site): (Lots 2 and 3	<u>) 8.22</u> Acres	
Total disturbed area:	<u>0.15</u> Acres		
14. Estimated projected	population: <u>N/A</u>		
15. The amount and type below:	of impervious cover ex	spected after construction	on is complete is shown
Table 1 - Impervious	Cover		
Impervious Cover of Proposed Project	Sq. Ft.	Sq. Ft./Acre	Acres
Structures/Rooftops	14,621	÷ 43,560 =	.34
Parking	34,897	÷ 43,560 =	.80
Other paved surfaces	194,854	÷ 43,560 =	4.47
Total Impervious Cover	244,372	÷ 43,560 =	5.61
	actors Affecting Surface affect surface water qu	e Water Quality. A deta	iled description of all licable, this includes the
construction.			
	als as defined by 30 TAC	330.2 will be used as fi	ll material.
	·	C 330.2 will be used as fi	ll material.

⊠ N/A

18. Type of project:
<ul> <li>TXDOT road project.</li> <li>County road or roads built to county specifications.</li> <li>City thoroughfare or roads to be dedicated to a municipality.</li> <li>Street or road providing access to private driveways.</li> </ul>
19. Type of pavement or road surface to be used:
Concrete Asphaltic concrete pavement Other:
20. Right of Way (R.O.W.):
Length of R.O.W.: feet. Width of R.O.W.: feet. $L \times W = Ft^2 \div 43,560 Ft^2/Acre = acres.$
21. Pavement Area:
Length of pavement area: feet.  Width of pavement area: feet.  L x W = Ft <sup>2</sup> ÷ 43,560 Ft <sup>2</sup> /Acre = acres.  Pavement area acres ÷ R.O.W. area acres x 100 = % impervious cover.
22. A rest stop will be included in this project.
A rest stop will not be included in this project.
23. Maintenance and repair of existing roadways that do not require approval from the TCEQ Executive Director. Modifications to existing roadways such as widening roads/adding shoulders totaling more than one-half (1/2) the width of one (1) existing lane require prior approval from the TCEQ.
Stormwater to be generated by the Proposed Project
24. Attachment E - Volume and Character of Stormwater. A detailed description of the volume (quantity) and character (quality) of the stormwater runoff which is expected to occur from the proposed project is attached. The estimates of stormwater runoff quality and quantity are based on area and type of impervious cover. Include the runoff coefficient of the site for both pre-construction and post-construction conditions.
Wastewater to be generated by the Proposed Project
25. Wastewater is to be discharged in the contributing zone. Requirements under 30 TAC §213.6(c) relating to Wastewater Treatment and Disposal Systems have been satisfied.  N/A

26. Wastewater will be disposed of by:
On-Site Sewage Facility (OSSF/Septic Tank):
Attachment F - Suitability Letter from Authorized Agent. An on-site sewage facility will be used to treat and dispose of the wastewater from this site. The appropriate licensing authority's (authorized agent) written approval is attached. It states that the land is suitable for the use of private sewage facilities and will meet or exceed the requirements for on-site sewage facilities as specified under 30 TAC Chapter 285 relating to On-site Sewage Facilities.  Each lot in this project/development is at least one (1) acre (43,560 square feet) in size. The system will be designed by a licensed professional engineer or registered sanitarian and installed by a licensed installer in compliance with 30 TAC Chapter 285.
<ul><li>Sewage Collection System (Sewer Lines):</li><li>The sewage collection system will convey the wastewater to the (name) Treatment</li><li>Plant. The treatment facility is:</li></ul>
Existing. Proposed.
⊠ N/A
Permanent Aboveground Storage Tanks(ASTs) ≥ 500 Gallons
Complete questions 27 - 33 if this project includes the installation of AST(s) with volume(s) greater than or equal to 500 gallons.
□N/A
27. Tanks and substance stored:

## Table 2 - Tanks and Substance Storage

AST Number	Size (Gallons)	Substance to be Stored	Tank Material
			A36 MILD CARBON STEEL (UL 2085,
1	10,000	Diesel/Gas	DOUBLE WALLED)
2			
3			
4			
5			

N/A - TANK IS DOUBLE WALLED

Total x 1.5 = <u>15,000</u> Gallons

one-half (1 one tank sy	I be placed within a 1/2) times the stora stem, the containmountained candidative storage cannot be storage.	nge capacity of the seent structure is size	system. For facilitie ed to capture one ar	s with more than
for providin	t <b>G - Alternative Sec</b> ng secondary contair for the Edwards Aqu	nment are propose		
	ons and capacity of o		ure(s):	
Length (L)(Ft.)	Width(W)(Ft.)	Height (H)(Ft.)	L x W x H = (Ft3)	Gallons
			Tr	otal: Gallons
Some of the structure.  The piping value of the structure.  The piping value of the structure.  The piping value of the structure.	will be aboveground will be underground	rs or equipment wil	Il extend outside the	e containment vious to the
substance(s	s) being stored. The	proposed containr	nent structure will t	e constructed of:
<del></del>	t <b>H - AST Containme</b> nt structure is attach		-	ing of the
Internal Tanks cle Piping c	dimensions (length, drainage to a point early labeled learly labeled er clearly labeled	· · · · · · · · · · · · · · · · · · ·		·
storage tan	oust be directed to a k facilities must be r ours of the spill.			

		<ul> <li>In the event of a spill, any spillage will be removed from the containment structure within 24 hours of the spill and disposed of properly.</li> <li>In the event of a spill, any spillage will be drained from the containment structure through a drain and valve within 24 hours of the spill and disposed of properly. The drain and valve system are shown in detail on the scaled drawing.</li> </ul>
Si	te	Plan Requirements
Ite	ms 3	34 - 46 must be included on the Site Plan.
34.		The Site Plan must have a minimum scale of 1" = 400'.
		Site Plan Scale: 1" = <u>30</u> '.
35.	100	O-year floodplain boundaries:
	The	Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled.  No part of the project site is located within the 100-year floodplain.  100-year floodplain boundaries are based on the following specific (including date of terial) sources(s): FEMA FIRM Panel # 48491C0275E (effective date 9/26/2008).
36.		The layout of the development is shown with existing and finished contours at appropriate, but not greater than ten-foot contour intervals. Lots, recreation centers, buildings, roads, etc. are shown on the site plan.
		The layout of the development is shown with existing contours at appropriate, but not greater than ten-foot contour intervals. Finished topographic contours will not differ from the existing topographic configuration and are not shown. Lots, recreation centers, buildings, roads, etc. are shown on the site plan.
37.		A drainage plan showing all paths of drainage from the site to surface streams.
38.		The drainage patterns and approximate slopes anticipated after major grading activities.
39.		Areas of soil disturbance and areas which will not be disturbed.
40.		Locations of major structural and nonstructural controls. These are the temporary and permanent best management practices.
41.	$\boxtimes$	Locations where soil stabilization practices are expected to occur.
42.		Surface waters (including wetlands).
		N/A
43.		Locations where stormwater discharges to surface water.
		There will be no discharges to surface water.
44.		Temporary aboveground storage tank facilities.

	Temporary aboveground storage tank facilities will not be located on this site.
45.	Permanent aboveground storage tank facilities.
	Permanent aboveground storage tank facilities will not be located on this site.
46.	Legal boundaries of the site are shown.
Pe	ermanent Best Management Practices (BMPs)
Pra	actices and measures that will be used during and after construction is completed.
47.	Permanent BMPs and measures must be implemented to control the discharge of pollution from regulated activities after the completion of construction.
	⊠ N/A
48.	These practices and measures have been designed, and will be constructed, operated, and maintained to insure that 80% of the incremental increase in the annual mass loading of total suspended solids (TSS) from the site caused by the regulated activity is removed. These quantities have been calculated in accordance with technical guidance prepared or accepted by the executive director.
	<ul> <li>The TCEQ Technical Guidance Manual (TGM) was used to design permanent BMPs and measures for this site.</li> <li>A technical guidance other than the TCEQ TGM was used to design permanent BMPs and measures for this site. The complete citation for the technical guidance that was used is:</li> </ul>
	N/A N/A
49.	Owners must insure that permanent BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the appropriate regional office within 30 days of site completion.
	⊠ N/A
50.	Where a site is used for low density single-family residential development and has 20 % or less impervious cover, other permanent BMPs are not required. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.
	<ul> <li>The site will be used for low density single-family residential development and has 20% or less impervious cover.</li> <li>The site will be used for low density single-family residential development but has more than 20% impervious cover.</li> </ul>

	The site will not be used for low density single-family residential development.
fa ir re ir th a	he executive director may waive the requirement for other permanent BMPs for multi- amily residential developments, schools, or small business sites where 20% or less impervious cover is used at the site. This exemption from permanent BMPs must be ecorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate egional office of these changes.
	<ul> <li>Attachment I - 20% or Less Impervious Cover Waiver. The site will be used for multi-family residential developments, schools, or small business sites and has 20% or less impervious cover. A request to waive the requirements for other permanent BMPs and measures is attached.</li> <li>□ The site will be used for multi-family residential developments, schools, or small business sites but has more than 20% impervious cover.</li> <li>□ The site will not be used for multi-family residential developments, schools, or small business sites.</li> </ul>
52.	Attachment J - BMPs for Upgradient Stormwater.
	<ul> <li>A description of the BMPs and measures that will be used to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site is attached.</li> <li>No surface water, groundwater or stormwater originates upgradient from the site and flows across the site, and an explanation is attached.</li> <li>Permanent BMPs or measures are not required to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site, and an explanation is attached.</li> </ul>
53.	Attachment K - BMPs for On-site Stormwater.
	<ul> <li>A description of the BMPs and measures that will be used to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff from the site is attached.</li> <li>Permanent BMPs or measures are not required to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff, and an explanation is attached.</li> </ul>
54.	Attachment L - BMPs for Surface Streams. A description of the BMPs and measures that prevent pollutants from entering surface streams is attached.
	☑ N/A
55.	Attachment M - Construction Plans. Construction plans and design calculations for the proposed permanent BMPs and measures have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer, and are signed, sealed, and 9 of 11

	dated. Construction plans for the proposed permanent BMPs and measures are attached and include: Design calculations, TCEQ Construction Notes, all proposed structural plans and specifications, and appropriate details.
	N/A
56.	<b>Attachment N - Inspection, Maintenance, Repair and Retrofit Plan</b> . A site and BMP specific plan for the inspection, maintenance, repair, and, if necessary, retrofit of the permanent BMPs and measures is attached. The plan fulfills all of the following:
	<ul> <li>□ Prepared and certified by the engineer designing the permanent BMPs and measures</li> <li>□ Signed by the owner or responsible party</li> <li>□ Outlines specific procedures for documenting inspections, maintenance, repairs, and, if necessary, retrofit.</li> </ul>
	Contains a discussion of record keeping procedures
	N/A
57	<b>Attachment O - Pilot-Scale Field Testing Plan</b> . Pilot studies for BMPs that are not recognized by the Executive Director require prior approval from the TCEQ. A plan for pilot-scale field testing is attached.
$\boxtimes$	N/A
58.	Attachment P - Measures for Minimizing Surface Stream Contamination. A description of the measures that will be used to avoid or minimize surface stream contamination and changes in the way in which water enters a stream as a result of the construction and development is attached. The measures address increased stream flashing, the creation of stronger flows and in-stream velocities, and other in-stream effects caused by the regulated activity, which increase erosion that result in water quality degradation.
	N/A
-	consibility for Maintenance of Permanent BMPs and sures after Construction is Complete.
59.	The applicant is responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred.
60.	A copy of the transfer of responsibility must be filed with the executive director at the appropriate regional office within 30 days of the transfer if the site is for use as a

multiple single-family residential development, a multi-family residential development, or a non-residential development such as commercial, industrial, institutional, schools, and other sites where regulated activities occur.

### **Administrative Information**

	Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions.
62. 🔀	Any modification of this Contributing Zone Plan may require TCEQ review and Executive Director approval prior to construction, and may require submission of a revised application, with appropriate fees.
	The site description, controls, maintenance, and inspection requirements for the storm water pollution prevention plan (SWPPP) developed under the EPA NPDES general permits for stormwater discharges have been submitted to fulfill paragraphs 30 TAC §213.24(1-5) of the technical report. All requirements of 30 TAC §213.24(1-5) have been met by the SWPPP document.
	The Temporary Stormwater Section (TCEQ-0602) is included with the application.



## Contributing Zone Plan Application (TCEQ-10257)

## Attachment A: Road Map



Source: Google Earth Pro accessed 3/12/2024



## Contributing Zone Plan Application (TCEQ-10257)


## Attachment B: USGS Quadrangle Map FEMA FIRM Map Edwards Aquifer Recharge Zone Map



Source: Portion of USGS Quadrangle Map (TX\_Leander\_NE\_20220808\_TM\_geo)



#### FEMA FIRM MAP PANEL



Source: Portion of FEMA FIRMette Panel 48491C0275E (effective 9/26/2008)






Source: Portion of FEMA FIRM Map Panel 48491C0275E (effective 9/26/2008)



#### **EDWARDS AQUIFER ZONE MAP**

PEC Liberty Hill 10625 W SH 29 Liberty Hill, Texas 78642 Source: TCEQ Edwards Aquifer Viewer Prepared: March 12, 2024







# Attachment C: Project Narrative

#### Proposed Development

The project site is located at 10625 W SH 29, Liberty Hill, Texas and is composed of two lots (6.22 AC & 2 AC) totaling 8.22 AC. The property is within the City limits of Liberty Hill, Texas, in Williamson County.

The proposed development is the addition of an Excell Aboveground Storage Tank (AST) fuel island on the existing caliche-based parking/storage area and one backup generator (150-gallon diesel). The fuel island will include the following:

- 1. One (1) 10,000 Gallon double-walled AST split 7,000 gal Diesel/3,000 gal Gas UL 2085 Fireguard tank with rod ladder and e-vents
- 2. Two (2) 20-Gallon remote spill basins with 3" fill piping, 3" ball valves and 3" quick fill connections
- 3. Two (2) 2" X 3" overfill devices set at 90%
- 4. Two (2) DEF blue boxes with pulse output with external filters and 5-minute timers
- 5. Three (3) Centeron Cell Monitors with 500 call block
- 6. Franklin DEF nozzle and hose
- 7. One (1) Fuelmaster 6-hose FMS with network capable
- 8. One (1) 500-Gallon DEF Poly Tank

The fueling system will be backed up by a 150 gal. diesel generator.

The property is within the Edwards Aquifer Contributing Zone. The existing Contributing Zone Plan (CZP) (EAPP 11-08030503 approval letter dated 4/16/2008) and approved CZP Modification (EAPP 11001078 approval letter dated 5/23/2018) includes a sand filter basin Permanent BMP for stormwater water quality control located on Lot 3 (1.3069 AC) adjacent and south of Lot 2. The sand filter basin BMP was designed to meet the required 80% removal of the increased load in total suspended solids of the original project in 2008 (EAPP 11-08030503). The requested project modification does not increase the Impervious Cover (IC) at the site. The existing sand filter basin Permanent BMP continues to treat stormwater runoff at the site.

#### Site Description and History

The previously developed property is owned by Pedernales Electric Cooperative, Inc. (WCOPR Document # 2003039417). The legal descriptions are S8162 - Seward Junction Commercial Park, Lot 2, ACRES 6.22 (WCAD Parcel No. R431148). The facility y currently serves as an operations center for the Pedernales





Electric Cooperative, including customer service and bill payment, storage of power poles, transformers, other utility construction and maintenance materials, and equipment.

The project site is on land with 0% - 15% slopes. Elevation at the project site is approximately between 975 FT and 985 FT. There is no vegetation at the project site, as the proposed construction is located on an existing parking lot area.

Access

Proposed access to the site is at 10625 W SH 29 in Liberty Hill, TX.

Impervious Cover (IC)

The impervious cover (IC) percentage on-site will not increase post-development. No change is proposed to the existing permanent BMP at the site.

Watershed and FEMA Floodplain Information

The project site is within the South Fork San Gabriel River Watershed, which drains to the Brazos River Basin. No surface streams run across the property. Drainage is generally to the southwest to an unnamed tributary that drains directly to the South Fork San Gabriel River, approximately 2.0 miles south of the project site.

The 6.22 AC property and 0.15 AC project site is in Zone X of FEMA FIRM Map No. 48491C0275E (effective 9/26/2008).

Temporary Best Management Practices (BMPs)

Construction practices shall disturb the minimal amount of existing ground cover as required for land clearing, grading, and construction activity for the shortest amount of time possible to minimize the potential of erosion and sedimentation from the site.

Prior to soil disturbing construction activity, temporary BMPs will be installed. Silt fencing will be installed along the down-gradient sides of the property to intercept and detain waterborne sediment from unprotected areas. The silt fence shall remain in place until the disturbed area is permanently stabilized.

Permanent Best Management Practices (BMPs)

No increased runoff or TSS will result from this fuel island and tank construction. The existing approved sand filter basin BMP for stormwater drainage and water quality at the developed site will continue to provide the required 80% reduction in stormwater sediments and be maintained according to the approved CZP (EAPP 11-08030503, dated April 16, 2008) and CZP Modification (EAPP 11001078, dated May 23, 2018). Total impervious cover (IC) at the property will not change as a result of the proposed construction of an AST and fueling island in the existing parking/storage area.





Offsite Areas

No offsite areas are anticipated to be affected by pre and post construction activities at the site. Temporary BMPs will minimize any anticipated effects of the proposed construction activities. The proposed development will not change the IC at the site. The existing permanent BMP currently addresses the impervious cover as shown within the construction plans.



## Attachment D: Factors Affecting Surface Water Quality

No surface water quality impacts are expected.



## Attachment E: Volume and Character of Stormwater

The proposed AST fueling site includes a double-walled AST fuel tank for secondary containment, and the fueling island is covered by a permanent constructed canopy. No change in the volume and character of stormwater at the site is expected.



Attachment F: Suitability Letter from Authorized Agent (if OSSF is proposed) **NOT APPLICABLE** 



## Attachment G: Alternative Secondary Containment Methods (if AST with an alternative method of secondary containment is proposed)


The 10,000-gallon AST is a double-walled, split 10/3 UL 2085 Fireguard tank with rod ladder and e-vents. The double-walled tank construction provides the required secondary containment.




Attachment H: **AST Containment Structure Drawings** 

#### Table of contents:

- 1.) Site plan, TCEQ Notifications & tank schematic
- 2.) Gasboy Dispenser & Containment
- 3.) Hanging hardware and hose retractor
- 4.) Red Jacket submersible pump
- 5.) Diesel exhaust fluid equipment
- 6.) Emergency valves
- 7.) Remote fill connection and basin
- 8.) Product piping and flex connector
- 9.) FuelMaster fuel management unit
- 10.) NFPA Placards
- 11.) Emergency Stop button





IF DRAWING BAR DOES NOT MEASURE 2" THIS PRINT IS NOT TO SCALE

1. THIS PROJECT IS SUBMITTED WITHOUT PHASING. 2.ALL EXISTING IMPERVIOUS COVER AND DRAINAGE PATTERNS WILL REMAIN UNCHANGED POST-DEVELOPMENT.

3.CONTRACTOR TO CUT AND REMOVE CONCRETE AS NECESSARY TO REMOVE ALL EXISTING PIPING. REFER TO PLANS BY OTHERS FOR EXACT LOCATION OF DISPENSERS AND PIPING.

4.ALL REQUIRED NOTICES AND PERMITS MUST BE PLACED IN A HIGHLY VISIBLE LOCATION ONSITE BEFORE THE COMMENCEMENT OF

5.ALL EROSION AND SEDIMENTATION CONTROLS (ESC) MUST BE INSTALLED PRIOR TO ANY DISTURBANCE TO THE PROJECT SITE.

6.ALL ESC USED ONSITE MUST BE REGULARLY MONITORED AND MAINTAINED AS NEEDED.

7.THE STABILIZED CONSTRUCTION ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT PREVENTS TRACKING ONTO THE PUBLIC ROADWAY ON AN ONGOING/REGULAR BASIS. MUD AND OR DIRT TRACKÉD INTO THE ROADWAY MUST BE IMMEDIATELY REMOVED UPON DISCOVERY.

8.INLET PROTECTION SHALL BE INSTALLED IMMEDIATELY UPON INLET INSTALLATION.

9.INITIATE TEMPORARY STABILIZATION WHEN CONSTRUCTION CEASES IN A DISTURBED AREA

10. INITIATE PERMANENT STABILIZATION IMMEDIATELY ONCE WORK HAS CEASED AND FINAL GRADE HAS BEEN ACHIEVED.

11. ALL DISTURBED/BARE AREAS WILL REQUIRE PERMANENT STABILIZATION BEFORE FINAL ACCEPTANCE CAN BE ACHIEVED. AVOID DISTURBING AREAS OF THE PROJECT THAT ARE NOT NECESSARY FOR CONSTRUCTION.


12. TEMPORARY ESC'S SHALL REMAIN IN PLACE IN ALL DISTURBED AREAS UNTIL ADEQUATE STABILIZATION HAS BEEN ACHIEVED.

13. THE TECHNICAL SPECS OF ESC DEVICES AND BEST MANAGEMENT PRACTICES (BMP) MEET OR EXCEED THE CITY OF AUSTIN ENVIRONMENTAL

14. PER PLANS BY OTHERS, EXISTING WATER QUALITY AND DETENTION POND HAS CAPACITY FOR AND WILL TREAT RUNOFF DURING CONSTRUCTION AND IN THE PROPOSED

15.NO INCREASED RUNOFF OR TSS WILL RESULT FROM THIS FUEL ISLAND AND TANK

16. IMPERVIOUS COVER PERCENTAGE ON-SITE WILL NOT INCREASE POST-DEVELOPMENT.




#### LEGEND

PROPOSED PROPERTY/ PROJECT BOUNDARY LINE EXISTING R.O.W./PROPERTY LINE EXISTING EASEMENT LINE PROPOSED CURB & GUTTER —LOC—LOC—LOC— LIMITS OF CONSTRUCTION .00000000 FIBER ROLL (MULCH) STAGING & TEMPORARY SPOILS AREA STABILIZED CONSTRUCTION **ENTRANCE** 



CONCRETE WASHOUT

NOTE: ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED BY INSPECTOR AT TIME OF CONSTRUCTION.





EROSION CONTROL AND DRAINAGE PLAN


SHEET 8 OF 10


P.E.C. LIBERTY HILL EAPP

**EXCELL FUELING SYSTEMS** 


TBPELS FIRM #21356 9111 JOLLVILLE RD., STE. 212 AUSTIN, TX 78759

SANDLIN






#### PROPERTY KEY MAP



IF DRAWING BAR DOES NOT MEASURE 2" THIS PRINT IS NOT TO SCALE




AST TANK LAYOUT PLAN SHEET 9 OF 10

P.E.C. LIBERTY HILL EAPP

**EXCELL FUELING SYSTEMS** 

**SANDLIN** 

TBPELS FIRM #21356 9111 JOLLVILLE RD., STE. 212 AUSTIN, TX 78759





# FLEET & COMMERCIAL

FUELING



#### CONTENTS

Gasboy Overview				
9853 Electronic High Flow.				
9850 Electronic Ultra-Hi .				4
9216 Satellite				(
9862 Electronic DEF				(
9872 Electronic E85			. 1	(
Atlas PRIME			. 1	
9153 Mechanical High Flow			. 1	
9823 ASTRA Electronic AST			. 1	
Model List			. 1	
Features and Options			. 2	(

# ATLAS SERIES

## FUELING EQUIPMENT

Gasboy has been producing refueling equipment since the 1920's. The Atlas Series is the latest generation in a long line of fleet-fueling equipment and is the workhorse for the tough Fleet and Commercial environment. It's compatible with the Gasboy PLUS Fuel Management System or a wide range of third-party controllers.

#### The Atlas Platform Offers:

- A wide range of models and flow rates
- Sophisticated electronics or simple mechanical registers which cover all requirements
- Use in Underground Tanks (UST) or Aboveground Tanks (AST) applications

#### Common Features in the Atlas Platform Include:

- Rugged and welded G90 galvanized-steel frame
- Structural foam bezel with a clear polycarbonate window, and a backscreen polycarbonate dialface
- Field-wiring junction box for easy installation
- Replaceable sheathing painted or optional 304 embossed stainless steel
- Standard hydraulics compatible with traditional motor fuels such as Biodiesel (up to B20) and Ethanol (up to E15); custom models are available for E85, B100 or DEF
- Safety listed and with NTEP CoC for W&M sealing for fuel resale application
- Optional High Retrievers and Catlow's hanging hardware to complete your fleet fueling equipment



# ATLAS 9853K

ELECTRONIC HIGH FLOW

# **Basic High Flow**

The 9853K Series Basic High Flow Atlas has electronic displays. Available in a complete range of pump or dispenser style models. Versatile for most high-flow fleet fueling applications.

EASY USE	Large 1" LCD display with LED backlight and capacitor back up. LED lighting to identify fuel grade and illuminate the front panel.
FAST	High-flow rated at 22 gpm with side load or optional front load nozzle positions.
INTEGRATED	RS485 or Pulse Output interface for connectivity to Gasboy PLUS or other third-party site controllers.
DURABLE	Four-piston CFT meter with flow-through center chamber for harsh fuels. Large 1" internal piping for high flow rates in a variety of site conditions. Steel internal tubing on most models. 10-vane suction pump with 1-HP motor.
OPTIONS	Satellite piping option can turn your Atlas into a master / satellite fueling position.



•

# ATLAS MODELS

G A S B O Y M O D E L S

Model Number	Description	Туре	Hoses	Products	Register	Flow Rating
9153K						
9153K	Hi-flow Single Pump	Pump	1	1	Mech	22 gpm
9152KTW1	Std-flow Twin 1 Pump	Pump	2	1	Mech	15 gpm
9153KTW1M	Hi-flow Twin 1 Pump	Pump	2	1	Mech	22 gpm
9153KTW2	Hi-flow Twin 2 Pump	Pump	2	2	Mech	22 gpm
9153KX	Hi-flow Single Dispenser	Dispenser	1		Mech	22 gpm
9153KXTW1	Hi-flow Twin 1 Dispenser	Dispenser	2	1	Mech	22 gpm
9153KXTW2	Hi-flow Twin 2 Dispenser	Dispenser	2	2	Mech	22 gpm
9853K						
9853K	Hi-flow Single Pump	Pump	1	1	Elec	22 gpm
9852KTW1	Std-flow Twin 1 Pump	Pump	2	1	Elec	15 gpm
9853KTW1M	Hi-flow Twin 1 Pump	Pump	2	1	Elec	22 gpm
9853KTW2	Hi-flow Twin 2 Pump	Pump	2	2	Elec	22 gpm
9853KX	Hi-flow Single Dispenser	Dispenser	1	1	Elec	22 gpm
9853KXTW1	Hi-flow Twin 1 Dispenser	Disnenser	2	1	Flec	22 anm
9853KXTW2	Hi-flow Twin 2 Dispenser	Dispenser	2	2	Elec	22 gpm
9040K						
9840K	Super-hi Single Pump	Pump	1	1	Elec	40 gpm
9840KX	Super-hi Single Dispenser	Dispenser	1	1	Elec	40 gpm

Model Number	odel Number Description Type		Hoses	Products	Register	Flow Rating
9850K						
9850K	Ultra-hi Flow Single Pump	Pump	1	1	Elec	50 gpm
9850KTW3	Ultra-hi Flow Combo Pump	Pump Combo	2	1	Elec	50 gpm
9850KX	Ultra-hi Flow Single Disp	Dispenser	1	1	Elec	50 gpm
9850KXTW1	Ultra-hix-Flow Twin 1 Disp	Dispenser	2	1	Elec	50 gpm
9850KXTW2	Ultra-hi Flow Iwin 2 Disp	Dispenser	2	2	Elec	50 gpm
9850KXTW3	Ultra-hi Flow Combo Disp	Disp Combo	2	1	Elec	50 gpm
9862K						
9862KX—Z	DEF — Cold Weather	Dispenser	1	1	Elec	
9862KX—WW	DEF — Warm Weather	Dispenser	1	1	Elec	
9862KX—ZWW	DEF — Warm Weather	Dispenser	1	1	Elec	
9872K						
9872KX	E85 — Single	Dispenser	1	1	Elec	15 gpm
9872KXTW1	E85 — Twin 1	Dispenser	2	1	Elec	15 gpm
9823K						
9823K	ASTRA Split AST Pump	Pump	1	1	Elec	21 gpm
9216K						
9216K	Satellite	Satellite	1	1	None	
9216KTW	Satellite	Satellite	2	1	None	

# ATLAS FEATURES

G A S B O Y M O D E L S

Feature	Short Description	9853	9840	9850	9823	9872	9862 CW	9862 WW	9153	9216
	Safety: UL and cUL Listed	S	S	S	S	S	MET	MET	S	S
Approvals	W&M: NCWM, Measurement Canada (MC)	S	S	S	S	S	S	S	S	S
Working Pressure	50 psi maximum	S	S	S	S	S	S	S	S	S
Operating Temp	-30°C to +55°C	S	S	S	S	S	S	-11°C	S	S
Unit of Measure	Gallons (liters optional)	S	S	S	S	S	S	S	S	_
	Gilbarco 4 piston PD CFT Meter	S	S	_	S	S	_	_	S	_
Meter	Liquid controls 6 step rotary PD Meter	_	_	S	_	_	_	_	_	_
	Coriolis Mass Flow Meter	_	_	_	_	_	S	S	_	_
	1 HP CD — 115V/60Hz (230V/50Hz optional)	S	S	_	S	_	-	-	S	_
Motors/Voltages	1½ HP CD — 115V/60Hz (230V/50Hz optional)	_	_	S	_	_	_	_	_	_
	3/4 HP CD 380V/50Hz/3-phase	0	0	_	0	_	_	_	0	_
	10 vane rotary w/air separator	S	S	_	S	_	_	_	S	_
Pump Models	High speed rotary vane w/air separator	_	_	S	_	_	_	_	_	_
Solenoid Valve	2-stage valve for Preset Operation (PP)	]"	1½"	1½"	]"	]"	3/4"	3/4"	]"	1½"
Filters	Internal spin-on style (F)	S	S	Strainer	S	S	Strainer	Strainer	S	_
1111612	External Canister Type	0	0	0	0	_	_	_	0	0
Piping	Internal Fuel Piping	1"	1½"	1½"	1"	1"	3/4"	3/4"	1"	1½"
Discharge	Hose Connection — NPT	1"	11/4"	11/4"	1"	3/4"	1" BSPP	1" BSPP	1"	11/4"
Satellite Piping	Satellite piping connection (S) — disp only	0	0	0	_	_	-	-	0	_
Inlet	Island Connection — NPT	1½"	2"	2"	1½"	1½"	1" BSPP	1" BSPP	1½"	1½"
Junction Box	Field Wiring Junction Box	S	S	S	S	S	S	S	S	S
Housing	G90 Galvanized Steel	13 GA	13 GA	13 GA	11 GA	13 GA	13 GA	13 GA	13 GA	13 GA
Panels	Lockable removable — Painted Galvanized Steel (std) — gauge	20	20	20	16	20	20	20	20	20
i uilGis	Lockable removable — Kooline Stainless Steel — 22 gauge	0	0	0	_	0	_	0	0	0
Sheathing	Replaceable — Painted G60 Galvanized Steel (std) — gauge	20	20	20	16	20	20	20	20	20
Juganing	Replaceable — Kooline Stainless Steel — 22 gauge	0	0	0	_	0	0	0	0	0

Feature	Short Description	9853	9840	9850	9823	9872	9862 CW	9862 WW	9153	9216
Computer/Register	Electronic Register — Volume only display	S	S	S	S	S	S	S	-	_
Component Register	Mechanical Register — VR10 volume only	_	_	_	_	_	_	_	S	_
Electronic Display	1" LCD w/LED Backlight & Capacitor Backup	S	S	S	S	S	S	S	-	_
	Pulser — 10:1 or 100:1 volume (CC or CX)	_	-	_	-	-	_	-	0	_
Interface Options	RS-485 — Gasboy CFN, Islander, or TopKat	0	0	0	0	0	0	0	_	_
illieriace opiiolis	Pulse Output I/F	0	0	0	0	0	0	0	_	_
	DC conduit and junction box (D)	S	S	S	_	S	S	S	_	_
	Keytrol (EK)	_	_	_	_	_	_	_	0	_
TopKAT PLUS	TopKAT PLUS with Ethernet conduit (factory install)	0	0	0	_	0	0	0	_	_
Brand Panel Lighting	LED Lighted brand panel (L)	0	0	0	_	0	0	0	0	_
	Electronic	S	S	S	S	S	S	S	_	_
Totalizers	Non-resettable Electro-mechanical	0	0	_	_	0	0	0	_	_
	Non-resettable mechanical	_	_	0	0	_	_	_	S	_
Namela Dante	Side load	S	S	S	_	S	_	S	S	_
Nozzle Position	Front load (Z)	0	0	0	S	0	S	0	_	S
	Internal hose retractor (I)	0	0	_	_	_	_	_	0	_
Hose Retractors	Internal hose reel	_	_	_	_	_	S	_	_	_
	High hose retractor — external post mounted	0	0	0	0	0	_	0	0	0
ACT A . P ·	Pressure Regulating Valve Model 52A — suction pumps only	0	_	_	0	_	_	_	0	_
AST Applications	9850 Above Ground Tank Kit — suction pumps only	_	_	0	_	_	_	_	_	_
W	12 month — Parts and labor	S	S	S	S	S	S	S	S	S
Warranty	Extended — 2, 3, 4 or 5 years	0	0	0	0	0	_	_	0	0
	ATC (Canada only)	0	0	0	_	_	_	_	_	_
	Hand crank (K)	_	_	_	_	_	-	_	0	_
	Power reset	_	_	_	_	_	-	_	S	_
II	Display power fail backup	S	S	S	S	S	S	S	_	_
Miscellaneous	Internal cabinet heater (DEF only)	_	_	_	_	_	S	_	_	_
	Balanced vapor recovery	0	_	_	0	_	_	_	0	_
	Healy Universal Kit compatible	0	_	_	_	_	_	_	0	_
	Hose, nozzle, swivel, breakaway	0	0	0	0	0	0	0	0	0

S = Standard; 0 = Optional; -= not available

21



www.gasboy.com

P-7080 | 022217 | Gilbarco Veeder-Root | 7300 W. Friendly Ave., Greensboro, NC 27410

# Model 434 Dispenser Pedestal

#### SPECIFICATION SHEET

#### **Application**

Dispenser pedestals serve as a raised platform for piping and installing dispensers/pumps in aboveground fueling systems.

#### **Features and Details**

- · Provides containment for small leaks in dispenser piping
- AST pedestal sold with a dispenser specific mounting platform
- Dispenser pedestal less entry penetrations for desired placement in the field
- · Pre-drilled anchor holes
- Dispenser mounting platform overhangs the pedestal base minimizing the ability for water penetration
- · Stabilizer bar kits included
- · Connection boots available
- Water tested liquid tight to the 6" level (18 gallon capacity)

#### **Materials of Construction**

#### 434

12 gauge steel, powder coated black

#### 434S

• 12 gauge 304 stainless steel

#### **Certifications and Listings**

Florida DEP EQ-823







434CB-0075 1B (3/4") through 434CB-02001B (2")



Specific item numbers and model details on next page.







Item Number	Description	Single (S) or Dual (D) Products	Opening Size (L x W)	Dispenser/Pedestal selection quide	Weight (lbs)
43412001 AK	AST pedestal base, platform, & 1 stabilizer bar kit	S	14½" x 10"	Gasboy 215/216A	140.0
43412002 AK	AST pedestal base, platform, & 2 stabilizer bar kits	D	14½" x 10"	Gasboy 215/216A	140.0
43414001 AK	AST pedestal base, platform, & 1 stabilizer bar kit	S	22¼" x 12"	Gasboy Atlas 8700K, 8800K, 9100K, 9800K; Bennett Big Squirt/Big Fueler 3000 series (Pre August 2017)	125.70
43414002 AK	AST pedestal base, platform, & 2 stabilizer bar kits	D	22¼" x 12"	Gasboy Atlas 8700K, 8800K, 9100K, 9800K; Bennett Big Squirt/Big Fueler 3000 series (Pre August 2017)	134.87
43417001 AK	AST pedestal base, platform, & 1 stabilizer bar kit	S	28" x 15"	Wayne Century 3/G2200, Reliance G5200 and G6200, Select 3/G7200	122.20
43417002 AK	AST pedestal base, platform, & 2 stabilizer bar kits	D	28" x 15"	Wayne Century 3/G2200, Reliance G5200 and G6200, Select 3/G7200	131.37
434S-14001 AK	SS AST pedestal base, platform, & 1 stabilizer bar kit	S	22¼" x 12"	Gasboy Atlas 8700K, 8800K, 9100K, 9800K; Bennett Big Squirt/Big Fueler 3000 series (Pre August 2017)	125.7
434S-14002 AK	SS AST pedestal base, platform, & 2 stabilizer bar kits	D	22¼" x 12"	Gasboy Atlas 8700K, 8800K, 9100K, 9800K; Bennett Big Squirt/Big Fueler 3000 series (Pre August 2017)	134.87
434S-17001 AK	SS AST pedestal base, platform, & 1 stabilizer bar kit	S	28" x 15"	Wayne Century 3/G2200, Reliance G5200 and G6200, Select 3/G7200	122.2
434S-17002 AK	SS AST pedestal base, platform, & 2 stabilizer bar kits	D	28" x 15"	Wayne Century 3/G2200, Reliance G5200 and G6200, Select 3/G7200	131.37

#### **Accessories**

	Item Number	Size	Description	Weight (lbs)	
	434CB-0075 1B	3/,"	Connection boot	0.22	A
	434CB-0100 1B	1"	Connection boot	0.22	
	434CB-0150 1B	1½"	Connection boot	0.61	
	434CB-0200 1B	2"	Connection boot	0.62	1
	434CBB0001 1B		Bonder, connection bond*		
	434CBBA001 1A		Bond applicator, connection boot		
	434SB-0100 AK		AST pedestal stabilizer bar kit		
	434SSB0100 AK		AST pedestal stabilizer bar kit; stainless steel		
_	434VB-0100 AK		Valve mounting bracket for Tok-52 / F- 664 valve		

\*One tube of bonder will cover three (3) connection boots.



# **Product Catalog**



Magnetic Breakaway





# **CATLOW**

#### www.catlow.com

This series of automatic nozzles establishes a new standard for vehicle refueling. The lightweight construction produces a smooth working, rugged nozzle designed for endurance.

The Elite Prepay is specifically designed for self-service or card-lock systems. The no-pressure/no-flow feature enables the station operator to control the dispensing of fuel while the customer has the convenience of a one hand hold-open mechanism for effortless dispensing.

#### **FEATURES and BENEFITS:**

- \*UL/ULC Listed
- \*Automatic shut off
- \*Splash shield included with each new nozzle
- \*Mates with all standard 5/8" & 3/4" hoses
- \*BSPT and BSPP threads available upon request
- \*Available in self serve upon request (S)
- \*Available with an Attitude Device at an additional charge
- \*Full cover provided for added protection
- \*Spout assembly easily replaced
- \*Completely rebuildable
- \* Custom logo available upon request
- \* 1 year warranty

#### **MATERIALS:**

- \*3/4" Single body, sand cast aluminum
- \*Lever & handguard is Super-Tuff Glass Filled Nylon
- \*O-rings and Seals are Viton
- \*Unleaded Spout Assembly 13/16" OD
- \*Leaded Spout Assembly 15/16" OD
- \*Weight 2.2 lbs.

CATLOW
2750 US RT 40
TIPP CITY, OHIO 45371 USA
Phone (800) 222-8569 Fax (937) 898-8631
www.catlow.com



#### **ORDERING SPECIFICATIONS**

PART NUMBER	DESCRIPTION
NENL	NEW, UNLEADED
NEL	NEW, LEADED
NEPNL	NEW, PREPAY UNLEADED
NEPL	NEW, PREPAY LEADED
RENL	REBUILT, UNLEADED
REL	REBUILT, LEADED
REPNL	REBUILT, PREPAY UNLEADED
REPL	REBUILT, PREPAY LEADED

#### Accessories

PART NUMBER	DESCRIPTION
PART NUIVIDER	DESCRIPTION
CNLS	ELITE UNLEADED SPOUT ASSEMBLY
CLS	ELITE LEADED SPOUT ASSEMBLY
CNLSP	PREPAY UNLEADED SPOUT ASSEMBLY
CLSP	PREPAY LEADED SPOUT ASSEMBLY
CFCxx	ELITE COVER xx
C11Bxx	ELITE PREPAY COVER xx
C376xx	ROUND SPLASH SHIELD XX



## **CAM TWIST MAGNETIC**

In-Line Breakaway



#### www.catlow.com

The CAM TWIST Breakaway is the only breakaway that gives you the option to easily disconnect, inspect and reconnect while installed. With a twist the breakaway can be taken apart and inspected for damage, corrosion, and wear without removing the breakaway from service.

Designed to be installed between the dispenser and the nozzle. It is simple to inspect the unit. Our unique design seals the internal components before a separation is complete, thus reducing any exposure to product and any environmental impact. With the CAM TWIST alignment and reconnection is easy. Align the two halves together & let the magnets do the work while pushing the unit back together. It's that easy!

#### CATLOW'S CAM TWIST MAGNETIC IN-LINE DESIGN IS THE FUTURE OF BREAKAWAY TECHNOLOGY!

As a cost saving feature, Catlow has designed a replacement lower half unit so in the event of a drive off, you only have to replace the lower half!

#### **FEATURES and BENEFITS:**

- \*Inspectable, No "Remove-By" date
- \* Patented Magnetic Snap-back Technology
- \* Resists "Hydraulic Hammer" problems
- \* UL/ULC Listed, CARB Certified, Meets NFPA 30A Codes
- \*BSPP & BSPT threads available upon request
- \* Separation force designed at 230 or 300 lbs.
- \* Durable plastic cover prevents damage during a driveoff
- \* Replacement "Lower" half of Breakaway available
- \* Reduces Environmental Impact. No need to drain assemblies to change nozzle
- \* One year warranty

#### **MATERIALS:**

- \* Body is Aluminum
- \* O-ring & Seals are Viton
- \* Cover is Nylon

**CATLOW** 2750 US RT 40 TIPP CITY, OHIO 45371 USA Phone (800) 222-8569 Fax (937) 898-8631 www.catlow.com



#### **ORDERING SPECIFICATIONS**

PART NUMBER	DESCRIPTION
CTM75	3/4" NPT (230 LBS PULL FORCE)
CTM100	1" NPT (300 LBS PULL FORCE)
CTMVA	VAC-ASSIST M34 X 1.5 (230 LBS PULL FORCE)
CTM75-HD	3/4" NPT (300 LBS PULL FORCE)
CTM75-L	3/4" LOWER UNIT
CTM75HD-L	3/4" LOWER UNIT, HEAVY DUTY
CTM100-L	1" LOWER UNIT
CTMVA-L	VAC-ASSIST LOWER UNIT

#### Accessories

PART NUMBER	DESCRIPTION
A13-SW	8" WHIP HOSE FOR CTM75 or HD
B9-SW	12" WHIP HOSE FOR CTM100
V1012-1-SW	12" WHIP HOSE FOR CTMVA
2976	O'RING KIT CTM75
2978	O'RING KIT CTM75-HD/CTM100
2977	O'RING KIT CTMVA





#### www.catlow.com

The Twister Swivel from Catlow raises the level of swivel flexibility with two (2) high flow 360 degree rotating swivel ends. Special seals protect this heavy duty swivel from extreme cold weather conditions and is designed for blended fuels.

Its high tech engineering, durable construction and economical price will not only "Twist & Turn" your hoses, but your profits as well.

#### **FEATURES and BENEFITS:**

- \*Lightweight and maintenance free
- \*UL/ULC listed
- \*360 degree swivel rotation in middle joint & male end
- \*Mates with all standard and diesel hoses
- \*Fluorosilicone seals perform to -40 degree F
- \*Does not affect existing hose length
- \*BSPP & BSPT threads available upon request
- \*Minimal flow restriction
- \*Both swivel joints have double o-rings
- \* 1 year warranty

#### **MATERIALS:**

- \*Swivel elbow Cast Aluminum
- \*Swivel body Cast ZA-12 Zamak
- \*Bearing is Acetal

**CATLOW** 

\*Seals are Viton and Fluorosilicone

# C720-3/4 SWIVEL



C720


#### **Twister Swivels**



#### **ORDERING SPECIFICATIONS**

	PART NUMBER	DESCRIPTION			
	C720 3/4	3/4"M x 3/4"F			
	C720 1x3/4	1"M x 3/4"F			
>	C720 1x1	1"M x 1"F			
	C720 1X1B100	1"M X 1"F 100% BIO DIESEL FUEL			
	C720 1X1BP	1"M X 1"F BRITISH THREAD			
	C720 3/4BP	3/4"M X 3/4"F BRITISH THREAD			
	C720 3/4E85	3/4"M X 3/4"F E85 FUEL			
	C720 1X1E85	1"M X 1"F E85 FUEL			

#### C720-1 SWIVEL



2750 US RT 40 TIPP CITY, OHIO 45371 USA Phone (800) 222-8569 Fax (937) 898-8631 www.catlow.com





#### www.catlow.com

The MAX 1 Hi-flow diesel nozzle is designed for durability. This heavy-duty nozzle can be used in high volume truckstop applications as well as high volume service stations.


Available as a standard or prepay (no pressure/no flow) nozzle. The prepay nozzle is specifically designed for unattended self service and cardlock refueling locations. The prepay feature enables the station operator to control the dispensing of fuel.

#### **FEATURES and BENEFITS:**

- \*Available as full serve or self serve
- \*Rugged heavy duty design
- \*Automatic shut-off
- \*UL/ULC Listed
- \*Custom logo available upon request
- \*BSPP and BSPT threads available upon request
- \*Attitude Device available upon request (AD)
- \*Spout assembly easily replaced
- \*Full Cover provided for added protection
- \*Longer spout with Anchor Bushing available upon request (AR)
- \*One-hand, hold open mechanism for effortless operation
- \*Mates with all standard hardwall or softwall 1" hoses
- \*Completely rebuildable
- \* One year warranty

#### **MATERIALS:**

- \* Body is Sand cast Aluminum
- \*Lever/Handguard Super-Tuff glass filled Nylon
- \*Seals are Viton
- \*Spout is 1-3/16" OD Aluminum Spout
- \*Weight 4 lbs.



**CATLOW** 2750 US RT 40 TIPP CITY, OHIO 45371 USA Phone (800) 222-8569 Fax (937) 898-8631 www.catlow.com



MAX1

#### ORDERING SPECIFICATIONS

PART NUMBER	DESCRIPTION
NM1	NEW, DIESEL
NM1P	NEW, DIESEL PREPAY
NM1S	NEW, DIESEL SELF SERVE
NM1PS	NEW, DIESEL SELF SERVE, PREPAY
RM1	REBUILT, DIESEL
RM1P	REBUILT, DIESEL PREPAY

#### Accessories

PART NUMBER	DESCRIPTION				
BS	DIESEL SPOUT ASSEMBLY				
BS-P	DIESEL SPOUT ASSEMBLY PREPAY				
C180 xx	COVER xx identifies color i.e. BK Black				
C076 xx	SPLASH SHIELD xx identifies color i.e. BK				





### TERMS AND WARRANTY

#### Rebuilt Nozzles:

Rebuilt Nozzles are invoiced at exchange price, and terms: Net 30 Days from invoice date. A separate invoice will be issued for core charges. Nozzle cores may be returned within sixty (60) days from invoice date to receive full credit against the core charge invoice.

#### Terms and Service Charge:

The terms for approved accounts: Net 30 Days on all orders. Terms for core charges: 60 Days Net. A service charge of 1 1/2% per month - 18% annual rate - will be added to all past due accounts.

#### Freight:

Freight is prepaid when net order to one destination is greater than: \$2,500 All shipments within the continental USA \$3,000 All International & Canadian shipments

Minimum Purchase: (Repair parts are an exception)

\$100.00 per order: All shipments within the continental USA \$500.00 per order: All International & Canadian shipments

#### Remittance Address:

Please use this address for Remittance ONLY

VEEDER ROOT COMPANY P.O. Box 99502 Chicago, IL 60693-9502

#### Limited Warranty:

CATLOW expressly warrants that its products shall be free from defects in materials and workmanship for a period of one year from the date of manufacture. This warranty is limited to repair or replacement by CATLOW upon return of the product to the CATLOW factory. This warranty does not apply in the event of any misuse or neglect of the product. The foregoing warranty is the exclusive remedy of purchasers of CATLOW products. CATLOW expressly disclaims any warranties, other than the foregoing express warranty, including the implied warranties of merchantability and fitness for a particular purpose, and disclaims any and all liability for consequential damages resulting from the use of its products.

#### Warranty Procedure:

All nozzles returned under warranty within 60 days, will be replaced with a new product. If the nozzle is dated beyond 60 days, it will be replaced with a rebuilt nozzle that carries the same warranty. The only exceptions are vapor recovery nozzles. If the nozzle returned to us was originally purchased as a new or rebuilt, that is what will be sent as a replacement.

Vapor recovery nozzles must have the "Nozzle Warranty Tag" completed and returned with the nozzle for the warranty to be honored. VERY IMPORTANT .... You must include the replacement serial number on the tag for the warranty to be honored. Without the tag, the warranty will not be honored. In addition to this, the vapor recovery nozzle replacement serial number will replace the serial number of the nozzle sent to us under warranty. We will be prorating the remaining warranty on the replacement nozzle.

#### Returned Goods:

Resalable material of standard manufacture must not be returned without first receiving a Return Goods Authorization number. Products accepted for return must be in first class condition, resalable as new and shipping charges prepaid. Minimum handling charge is 20% deducted from the price paid by the customer, or current price, whichever is lower.

All items shipped to Catlow must have a Returned Goods Authorization number (RGA).



C

# OSE RETRIEVER

# **HOSE RETRACTOR - COUNTERWEIGHT**

#### **Application** -

Keeping conventional and Stage II vapor recovery coaxial hoses raised to prevent traps in the vapor line. Potential accidents are reduced. Hose life is greatly extended.

#### **Part Number - 880/882**





Only from Universal! - Our better looking profile blends in with today's modern dispensers.

Α

#### Features -

- ✓ Easy to install and maintain
- Adaptable to most dispensers
- ✓ Corrosion resistant construction
- ✓ Plastic bushing minimizes cable wear
- ✓ Compatible with E-85

#### **Construction** -

- Aluminum Post (2"x2")
- Cast iron counterweight
- Plastic bushings
- Black polyester cable
- · Includes both side and bottom mounting brackets

Model	Weight (lbs.)	A	В	С	Counter Weight
880	29	78-3/4"	5-1/2"	2-1/4	20lbs
882	38	92"	5-1/2"	2-1/4"	27lbs

#### **Replacement Parts**

Part Numbers	Description		<u>† [·]</u>
880-5	Cover Pulley	880-MBC	Square Bracket
880-8	Bushing	880-WA	Weight Assembly (1-1/2" x 1-1/2")
880-8A	Black Nylon Rope	880-WA-2	Weight Assembly (882) (1-3/4" x 1-3/4")
880-A	Body	880-AC	Body Assembly
880-B	Base	880-CA	Cover Assembly
880-C	Cover		

<sup>\*</sup>Custom heights and counterweights available. Call for options.

Notice: Universal Valve Co., products must be used in compliance with applicable federal, state, and local laws and regulations. Product selection should be based on physical specifications and limitations and compatibility with the environment and material to be handled. Universal Valve Co., makes no warranty of fitness for a particular use. All illustrations and specifications in this literature are based on the latest production information available at the time of publication. Prices, materials, and specification are subject to change at any time, and models may be discontinued at any time, in either case, without notice or obligation.













# The Red Jacket Submersible Turbine Pump

# **Key Features:**

- Industry's newest motor design
- Track record of unsurpassed reliability
- Designed to maximize safety and ease installation

**The cornerstone of your fueling infrastructure.** The Red Jacket series submersible turbine pump is the foundation model that sets the standard for high throughput, high reliability fueling applications.

# **Specifications:**

#### **Fuel Compatibility**

- 100% Diesel
- 100% Gasoline
- Methanol concentrations up to 20%
- Ethanol concentrations up to 20%
- MTBE, ETBE, or TAME concentrations up to 20%

#### **Designed for Hazardous Locations**

• Class 1, Group D atmospheres

#### Fits installations from 3 $\frac{1}{2}$ to 19' in depth

#### 4 Motor Sizes Available:

- ¾ HP, 60 Hz, 1 phase
- 1 ½ HP, 60 Hz, 1 phase
- X3 1  $\frac{1}{2}$  HP, 60 Hz, 1 phase, high pressure
- 2 HP, 60 Hz, 1 phase

All models available with floating suction adapter

Automatic electrical disconnect plus fuel drain to assist in safe servicing

#### **Siphon Ports:**

- 2 available, 1/4" NPT
- Vacuums generated up to 25 in Hg.

#### Compatible with check valve housing models:

- Standard VR ready check valve for PLLD (410152-001)
- High pressure check valve for high pressure applications (410152-002)

Line Pressure Port: 1 Available, 1/4" NPT

Vent Port: 1 Available, 1/4"NPT

#### **UL** Listings:

- 100% Diesel
- 100% Gasoline
- Gasoline and up to: 10% Ethanol, 15% Methanol, 20% MTBE, 20% ETBE, 20% TAME

#### Other Agency Listings: cUL

Optional stainless steel trapper intake screen blocks corroded tank debris from clogging dispenser filters



## Quick Set Final Assemblies (Adjustable)

Horsepower	KW	Length	Floating Suction Adapter	Model Number	Part Number
0.75	0 56	72" - 102"		P75111 R11	410140-001
0.75	0.56	102" - 162"		P75U1 RJ2	410140-002
0.75	U.36	107 - 777		P75UT KJ3	410140-003
0.75	0.56	74.3" - 104.3" *	•	P75U1 RJ1 FSA	410140-004
0.75	0.56	104.3" - 164.3" *	•	P75U1 RJ2 FSA	410140-005
0.75	0.56	164.3" - 224.3" *	•	P75U1 RJ3 FSA	410140-006
1.5	1.13	74.5" - 105"		P150U1 RJ1	410141-001
1.5	1.13	104.5" - 165"		P150U1 RJ2	410141-002
1.5	1.13	164.5" - 225"		P150U1 RJ3	410141-003
1.5	1.13	76.8" - 107.3"	•	P150U1 RJ1 FSA	410141-004
1.5	1.13	106.8" - 167.3"	•	P150U1 RJ2 FSA	410141-005
1.5	1.13	166.8" - 227.3"	•	P150U1 RJ3 FSA	410141-006
1.5	1.13	75.5" - 105.5"		X3P150U1 RJ1	410143-001
1.5 볼	1.13	105.5" - 165.5"		X3P150U1 RJ2	410143-002
1.5	1.13	165.5" - 225.5"		X3P150U1 RJ3	410143-003
1.5 HS 1.	1.13	77.8" - 107.8"	•	X3P150U1 RJ1 FSA	410143-004
1.5 🖺	1.13	107.8" - 167.8"	•	X3P150U1 RJ2 FSA	410143-005
1.5	1.13	167.8" - 227.8"	•	X3P150U1 RJ3 FSA	410143-006
2	1.5	78.5" - 108.5"		P200U1-3 RJ1	410142-001
2	1.5	108.5" - 168.5"		P200U2-3 RJ1	410142-002
2	1.5	168.5" - 228.5"		P200U3-3 RJ1	410142-003
2	1.5	80.8" - 110.8"	•	P200U1-3 RJ1 FSA	410142-004
2	1.5	110.8" - 170.8"	•	P200U1-3 RJ2 FSA	410142-005
2	1.5	170.8" - 230.8"	•	P200U1-3 RJ3 FSA	410142-006

Fixed-Speed, single phase STP assemblies. Length measured from the top of the eyebolt to the bottom of the motor inlet. All 208/230 Volts.

#### Fixed Length Final Assemblies (Non-Adjustable)

Horsepower	KW	Length	Floating Suction Adapter	Model Number	Part Number
0.75	0.56	42" - 132"		P75U1 RJ	410166-001
0.75	0.56	133" - 168"		P75U2 RJ	410166-002
0.75	0.56	169" - 222"		P75U3 RJ	410166-003
0.75	0.56	44.3" - 134.3"	•	P75U1 RJ FSA	410166-019
0.75	0.56	135.3" - 168.2"	•	P75U1 RJ FSA	410166-020
0.75	0.56	171.3" - 224.3"	•	P75U1 RJ FSA	410166-021
1.5	1.13	45" - 135"		P150U1 RJ	410173-001
1.5	1.13	136" - 171"		P150U1 RJ	410173-002
1.5	1.13	172" - 225"		P150U1 RJ	410173-003
1.5	1.13	47.3" - 137.3"	•	P150U1 RJ FSA	410173-019
1.5	1.13	138.3" - 173.3"	•	P150U1 RJ FSA	410173-020
1.5	1.13	174.3" - 227.3"	•	P150U1 RJ FSA	410173-021
1.5	1.13	46" - 135"		X3P150U1 RJ	410175-001
1.5 불	1.13	136" - 171"		X3P150U1 RJ	410175-002
1.5 1.5 LESS C.1 1	1.13	172" - 225"		X3P150U1 RJ	410175-003
1.5 =	1.13	48.3" - 137.3"	•	X3P150U1 RJ FSA	410175-019
1.5 ≌	1.13	138.3" - 173.3."	•	X3P150U1 RJ FSA	410175-020
1.5	1.13	174.3" - 227.3"	•	X3P150U1 RJ FSA	410175-021
2	1.5	49" - 138"		P200U1-3 RJ	410174-001
2	1.5	139" - 174"		P200U1-3 RJ	410174-002
2	1.5	175" - 228"		P200U1-3 RJ	410174-003
2	1.5	51.3" - 140.3"	•	P200U1-3 RJ FSA	410174-019
2	1.5	141.3" - 176.3"	•	P200U1-3 RJ FSA	410174-020
2	1.5	177.3" - 230.3"	•	P200U1-3 RJ FSA	410174-021

Fixed length pumps may not be returned to stock.



To learn more, contact us at 888.561.7942 or visit www.redjacket.com













METERED NOZZLES



DEF BLUE BOX PEDESTAL

#### **FEATURES**

- EASY TO INSTALL
- READY TO USE
- · BUILT-IN LOCK

The PIUSI DEF Blue Box Pedestal is specifically designed for wall or tank installation, or can be mounted atop an optional pedestal. It is covered by a lockable metal container which protects the pump when not in use.

#### PERFORMANCE


9 GPM

FLOW RATE

AC V./Hz
120/60
VOLTAGE
POWER

**± 1%** 

20 MIN





DEF BLUE BOX PEDESTAL (FULLY ASSEMBLED)

PACKAGING (BLUE BOX)								
PART#	WE	GHT	PACKAGING					
PARI#	KG	LBS	мм	INCH	PCS/BOX			
R1611800A	25	55.1	575X32OX6O7	22.6X23.9	1			



































# SUZZARABLUE AC 10.6 7.93 00 2.64 2.64 2.725 14.5 21.7 29

P = TOTAL PRESSURE (PSI)

#### **VARIOUS COMPONENTS**

- BLUE BOX (R1611800A)
- · SB PRO KIT (PAGE 20)
- MOUNTING PLATE (F20300000)
- PEDESTAL (OPTIONAL) (F1270800)

#### **DETAILS**








**TEMPERATURE** 

TYPE OF FLUID WATER

68 °F





#### **MATERIALS**

• PUMP:

SUZZARABLUE PUMP AC

PG. 28

• METER:

K24 METER

PG. 46

· NOZZLE:

SUZZARABLUE A6O PG. 64

TECHNIC	TECHNICAL DATA										
PART #	DESCRIPTION	FLUIDS TYPE	FLOW RATE		VOLTAGE			METER	NOZZLE	HOSE	
PARI#	DESCRIPTION	FLUIDS I YPE	L/MIN	GPM	AC V./HZ DC VOLT	POWER WATT	AMP. MAX.	MOD.	TYPE	LENGTH	
DEFPEDESTAL	DEF BLUE BOX PEDESTAL TANK KIT	(D) W	34	9	120/60	400	1.95	K24	SUZZARABLUE NOZZLE A6O	20 FT	
R1611800A	KIT COMPLETE BOX FOR SUZZARABLUE BOX	-	-	-	-	-	-	-	-	-	



#### DURADEFT NOZZLE

For DEF/AdBlue®

The FLEX-ING™ brand DuraDEF™ nozzle features a specially encapsulated aluminium casting that makes it lightweight yet completely compatible with DEF (Diesel Exhaust Fluid)/ AdBlue®. This nozzle provides the performance and construction specifications required for DEF/AdBlue® delivery with a lightweight, more user-friendly design.

#### **HIGHLIGHTS**

- High strength aluminium body and stainless steel spout.
- Protective vinyl scuff guard available in green, yellow, red, blue, black and light blue to match station branding.
- Available with or without hold-open clip.
- Internal components are manufactured from stainless steel or plastic for full DEF/AdBlue® compatibility.
- Sealed in a plastic bag to ensure no contamination.
- Meets all required specifications set by ISO 22241 for DEF/AdBlue® delivery.

#### **SPECIFICATIONS**

• Inlet: ¾" BSPP

Spout: 19mm stainless steelSeals and poppet disc: Viton® A

• Packing: PTFE

• Weight / length / height: 2.5 Lbs. / 13.5" / 9"

Body casting: Coated aluminiumHandguard and vac cap: Nylon

• Lever: Electroless nickel plated steel & nylon

Scuff guard: VinylBody cap: Coated zinc

#### ORDERING INFORMATION

#### FLDEF A B C D - E - F

- FLDEF = DEF/AdBlue® Hose
- B = Hose Diameter
- $02 = \frac{3}{4}$ "
- C = Hose Length Feet
- Use three-digit format
- D = Hose Length Inches
- Use two-digit format
- E & F = End Fitting Options
- 2N = ¾" NPT
- 2P = 34" BSPP
- 3P = 1" BSPP

Model	Description
DURADEF-LB	Light Blue DuraDEF nozzle with locking clip
DURADEF-LB-O	Light Blue DuraDEF nozzle without locking clip



# HOSE For DEF/AdBlue®

FLEX-ING<sup>TM</sup> brand diesel exhaust fluid hose features a specially formulated low-extraction EPDM rubber tube making it completely compatible with DEF/AdBlue®. The flexible softwall construction provides superior handling for both standard and reel applications. Each curb hose length features dual anit-kink sleeves at each end to protect the hose from accelerated wear and kinking. The anti-kink sleeves are factory installed over the end fitting ferrule to ensure maximum wear protection.

#### **HIGHLIGHTS**

- Peroxide cured tube provides superior extraction levels and significantly reduces contamination.
- Premium polyester braided construction reduces volumetric expansion.
- Integrated static wire.
- All curb hoses over 2' in length are outfitted with factory installed anti-kink sleeves on both ends.
- BSPP outlets include a fluoroelastomer flat seal to ensure compression tightness.

#### **SPECIFICATIONS**

- Tube: Specially formulated low-extraction EPDM rubber, peroxide cured
- Reinforcement: Polyester braid
- Cover: Specially formulated EPDM
- Temperature: -40 °F to 257 °F (-40 °C to 125 °C)

#### **Approvals**

 Meets ISO 22241 standard ensuring desirable characteristics of AUS 32 (DEF) are met, such as quality, safety, reliability and contamination.

#### ORDERING INFORMATION

#### FLDEF A B C - D - E

- FLDEF = DEF/AdBlue® Hose
- A = Hose Diameter
- 2 = <sup>3</sup>/<sub>4</sub>"
- B = Hose Length Feet
- · Use three-digit format
- C = Hose Length Inches
- Use two-digit format
- D & E = End Fitting Options
- 2N = ¾" NPT
- 2P = 3/4" BSPP
- 3P = 1" BSPP
- 3PF = 1" BSPP Female Swivel

Example: FLDEF200906-2N-2N = Def/Adblue® hose, %" diameter, 9 feet 6 inches length, %" NPT fitting on both ends.











#### SWIVEL BREAK AWAY

For DFF/AdRlue®

FLEX-ING<sup>TM</sup> brand diesel exhaust fluid swivel break aways provide in-line protection for hanging hardware in the event of a drive off. These break aways feature a stainless steel body that makes them extremely durable and completely compatible with DEF/AdBlue®. The break away design ensures proper drive-off protection and allows for easy installation directly between the nozzle and hose. The integrated swivel action provides easy nozzle rotation during vehicle filling while also helping to reduce hose wear and kinking.

#### **HIGHLIGHTS**

- High strength stainless steel body with internal components that are completely compatible with DEF/ AdBlue®.
- Break away valves separate with axial or up to 30° angular force.
- Fluid release limited to less than 10 ml upon break away valve separation.
- Atmospheric inner seal protects from corrosion.
- Integrated swivel action provides easy nozzle rotation during vehicle filling while also helping to reduce hose wear and kinking.
- Available with either ¾" NPT and ¾" BSPP nozzle outlet and standard 1" BSPP female inlet.
- BSPP nozzle outlet includes a fluoroelastomer flat seal to ensure compression tightness between the break away and the nozzle inlet.

#### **SPECIFICATIONS**

- Body: Stainless steel
- Separation force: Between 180 Lbs. and 340 Lbs. force (800 N and 1,500 N force)
- Temperature rating: -22 °F to 131 °F (-30 °C to 55 °C)
- Internal pressure: Factory tested to 76.8 PSI (5.3 bar)
- Electric conductivity: Factory tested to < 100k Ohm
- Nozzle flow rate compatibility: Up to 21 gpm (80 lpm)
- Working pressures compatibility: 0.5 bar up to 3.5 bar

# ORDERING INFORMATION Model Description OMNIDEF1X34N %" NPT nozzle outlet, 1" BSPP female inlet DEF swivel break away OMNIDEF1X34P %" BSPP nozzle outlet, 1" BSPP female inlet DEF swivel break away OMNIDEF1PXM34 M34 (metric) nozzle outlet, 1" BSPP female inlet DEF swivel break away

#### Model 9095AA 3" Overfill Prevention Valve

**NEW PRODUCT ANNOUNCEMENT** 

#### **Application**

The 9095AA series overfill prevention valve is designed to prevent the overfilling of liquid storage tanks by providing a positive shut-off during a pressurized fill.

#### **Features and Details**

- Installs on tank top by threading onto a 6" male NPT riser
- Direct fill adaptor has 3" male quick disconnect
- Remote adaptor has 3" female NPT inlet threads for piping to remote fill point
- · Full flow until shut-off point
- · 1.23" of float height adjustment
- · Integral pressure relief
- · Integral anti-siphon function
- Optional test mechanism
- Drop tube adaptor accepts 3" drop fill tubes (Morrison 419)

#### **Materials of Construction**

- · Direct fill adaptor... passivated aluminum
- Remote adaptor... ductile iron, powder coated
- Body... passivated aluminum
- Shaft, linkage, and hardware... stainless steel
- · Lower pipe... e-coated steel
- · Drop tube adaptor... passivated aluminum

#### **Operational Criteria**

- Minimum 5 PSI flow requirements
- Maximum operating pressure is 100 PSI
- Maximum viscosity of 300 centistokes
- A tight fill connection is required for the valve to operate
- The estimated flow rate is 560 GPM at 10 PSI pressure drop (See flow curve)

#### **Code Compliance**

ULC-S661-10 listed, NFPA 30, 30A, UFC, IFC, PEI/ RP200, PEI/RP 600, and Florida DEP EQ-851. California EVR models available



For use on clean liquids only.


Item numbers and flow curve on next page.





EVR EVR

Item Number	Size	Description	Weight (lbs)	List Price
9095AA0300 AV	3"	AST overfill prevention valve, aluminum body, with 3" male quick disconnect x 6" female threads	21	\$1,277.92
9095AA3300AVEVR	3"	AST overfill prevention valve, aluminum body with 3" female threaded x 6" Female threaded connections; CARB EVR approved	30	\$1,277.92
9095AA9300AVEVR	3"	AST overfill prevention valve, aluminum body, less top connection; CARB EVR approved	14.4	\$1,174.65
9095ATM0100 AM	2" & 3"	Mechanical test mechanism kit	1	\$114.31







### A0060 Shear Valve

 Beefier Castings for Rugged Reliability ATEX & UL Approved\*

Mounting Bolts Included






Stainless Steel Versions for E85, DEF, Ultra Low Sulfur Diesel & Biodiesel Blends up to B100


#### **EMCO WHEATON RETAIL CORPORATION**

2300 Industrial Park Drive • Wilson, North Carolina 27893 252-243-0150 • 252-243-4603 (fax) • www.emcoretail.com



## A0060 **Emergency Shear Valve**





#### **Materials**

Body: Cast Iron or Stainless Steel

Spring: Stainless Steel Viton® Seal:

Viton® is a registered trademark of The Chemours Company

<u>Approvals</u>

ATEX FTZÚ14ATEX0204





**Guide Specification:** Emergency shut off valve for installation under gasoline dispensing units. Incorporates a replaceable shear section and a heat sensitive fusible link assembly. Valve can be manually operated to facilitate dispenser maintenance and incorporates a 3/8" test port. Closing poppet assembly is positioned out of the fuel flow path to minimize pressure drop. The A0060 utilizes a standard three boss mounting arrangement. Available in single poppet and double poppet configurations. Cast iron versions are powdered coated.

Model No. Cast Iron	Model No. Stainless Steel	Description	Inlet	Outlet	Cast Iron   Lbs.	SST Lbs.	Α	В
A0060-002	A0060-002S	I <sup>1</sup> /2" Single Poppet	Female	Male	5.7	6.4	6.9"	2.2"
A0060-003	A0000-0033	1 1/2 Single Poppet	remaie	remaie	5.6	6.3	0./	1./
A0060-015	A0060-015S	I 1/2" Single Poppet	Female BSPT	Male BSPT	5.7	6.4	7.9"	3.2"
A0060-016	A0060-016S	I 1/2" Single Poppet	Female BSPT	Female BSPT	5.6	6.3	6.9"	2.2"
A0060-022	A0060-022S	I <sup>1</sup> /2" Double Poppet	Female	Male	5.8	6.7	7.9"	3.2"
A0060-023	A0060-023S	I 1/2" Double Poppet	Female	Female	5.7	6.4	6.9"	2.2"
A0060-025	A0060-025S	I 1/2" Double Poppet	Female BSPT	Male BSPT	5.8	6.7	7.9"	3.2"
A0060-026	A0060-026S	I 1/2" Double Poppet	Female BSPT	Female BSPT	5.7	6.4	6.9"	2.2"

#### **Replacement Parts**

•							
Part No.	For	Part No.	For	I	l	Cast Iron	SST
Cast Iron	Use On	Stainless Steel	Use on	Description	Outlet	Lbs.	Lbs.
492938	A0060-002	492938S	A0060-002S	<sup> </sup> / <sub>2</sub> " Replacement Top;   Poppet	Male	2.2	2.5
492939	A0060-003	492939S	A0060-003S	/2" Replacement Top;   Poppet	Female	2.3	2.6
493885	A0060-016	493885S	A0060-016S	I <sup>1</sup> /2" Replacement Top; I Poppet	Female BSPT	1.4	1.6
493886	A0060-015	493886S	A0060-015S	I <sup>1</sup> /2" Replacement Top; I Poppet	Male BSPT	1.6	1.8
493887	A0060-022	493887S	A0060-022S		Male	2.7	3.0
493888	A0060-023	493888S	A0060-023S		Female	2.7	3.0
493889	A0060-025	493889S	A0060-025S		Male BSPT	1.6	1.8
493890	A0060-026	493890S	A0060-026S		Female BSPT	1.6	1.8
492963K				Fusible Link Kit		0.2	
564036				Control Arm			
A0065-001				A0060 Stabilizer Bar Mounted Kit		3.8	



#### **Emco Wheaton Retail Corporation**

2300 Industrial Park Drive • Wilson, North Carolina 27893 252-243-0150 • 252-243-4603 (fax) • www.emcoretail.com

© 2020 Emco Wheaton Retail Corporation V-1000



#### Model 76DI & 78DI Expansion Relief Valves

SPECIFICATION SHEET

#### **Application**

Expansion Relief Valves are used on AST piping for relief of excess pressure caused by thermal expansion of liquid. The Valve allows product to return back to the storage tank.

**076DI**...Specify 25 or 50 PSI. Primarily for use with line leak detection systems. Use Fig. 76DI anytime you need to maintain precise pressures in the piping system.

**078DI**...Specify 25, 40 or 100 PSI. Pressure settings are approximate.

#### **Materials of Construction**

#### 076DI

- · Body... Ductile iron
- · Cap... Stainless steel
- · Relief fitting... Stainless steel with FKM

#### 078DI


- · Body... Ductile iron
- Cap... Stainless steel
- Spring... Stainless steel
- Ball... Stainless steel



Item Number	Α	В	С	D	E	F	G	Weight	
076DI-0100 AV	1/2"	25	DI	SS	SS/P	NA	NA	0.75	
076DI-0200 AV	1/2"	50	DI	SS	SS/P	NA	NA	0.75	
078DI-0100 AV	1/2"	25	DI	SS	NA	SS	SS	0.75	
078DI-0200 AV	1/2"	40	DI	SS	NA	SS	SS	0.75	
078DI-0300 AV	1/2	100	DI	55	NA	55	55	0.75	

#### **SPECIFICATION OPTIONS:**

- A—Size (inches)
- **B**—PSI setting
- **C—**Body material: DI (Ductile Iron)
- D—Cap material: SS (Stainless Steel)
- E—Expansion relief Valve Material: SS/TF (Stainless Steel/PTFE), NA (Not Applicable)
- F—Spring material: SS (Stainless Steel), NA (Not Applicable)
- G—Check ball material: SS (Stainless Steel), NA (Not Applicable)
- Weight—Shipping weight (lbs)



570 E. 7th Street, P.O. Box 238 | Dubuque, IA 52004-0238 t. 563.583.5701 | 800.553.4840 | f. 563.583.5028

www.morbros.com

#### Model 710 Solenoid Valve (Normally Closed)

#### **Application**

Normally closed solenoid valves are used to help prevent the accidental siphoning of a product from a tank in the event of a leak downstream below the liquid level. They are generally installed on the dispensing side of a fuel system pipeline. The valve opens upon the receipt of an electronic signal such as when a dispenser or pump is switched to the 'on' position.

#### **Features and Details**

- · Normally closed, hung piston design
- Operates at 120 volts AC (24, 208, 220, 240, & 480 volts AC, and 12, 24, and 48 volts DC also available)
- Minimum operating temperature is -40°F
- Includes a continuous duty Class H standard coil. Other options are available
- Install in a horizontal pipeline in the upright vertical position
- · Zero pressure differential
- Integral thermal relief allows the valve to relieve expansion pressure in the opposite direction of flow
- Enclosure is watertight and rated for hazardous locations—NEMA 3, 4X, 7 and 9; groups C and D
- Several optional coil voltages available
- Recommended for use with liquids having a maximum viscosity of 60 centistokes
- A strainer with a 100 mesh screen is recommended at the valve inlet
- 710 has a cast bronze body
- 710MO has manual override feature. Available in sizes ranging from ¾" to 2" for operation during a power outage
- 710SS has a stainless steel body

#### **Materials of Construction**

 Solenoid housed in an integral, watertight, explosion-proof shell


#### **Certifications and Listings**

CSA listed (File No. 108921, Model Z1314); Class I, Groups C and D; Class II, Groups E, F and G; Class III; T3C










Item numbers, dimensions, and water flow vs. pressure drop chart on next page.





#### SPECIFICATION SHEET

Item Number	Size (NPT)	Seal Material	Orifice Size (inches)	cv	Diffe	Pressure rential (P.S.I) Max	Fluid Temp. (Max) (Deg. F.)	Power Consumption (Watt)	Ship Weight (lbs)	A	Gen. Dim (inch B		D
710-0075 1V	3/4"	FKM	3/4"	7	0	105	302	30	11.0	4.0"	5.90"	1.5"	4.38"
710-0100 1V	1"	FKM	1"	12	0	105	302	30	13.0	4.8"	6.25"	1.75"	4.38"
710-0150 1V	1½"	FKM	11/4"	17	0	105	302	30	16.0	5.40"	6.90"	2.0"	4.38"
710-0200 1V	2"	FKM	1½"	27	0	105	302	30	21.0	5.90"	7.0"	2.25"	4.38"
710-0300 1V	3"	FKM	3"	94	0	45	302	48	44.0	8.80"	9.50"	4.50"	4.38"
710MO-0075 1V	3/4"	FKM	3/4"	7	0	105	302	30	12.0	4.0"	5.90"	1.50"	4.38"
710MO-0100 1V	1"	FKM	1"	12	0	105	302	30	14.0	4.80"	6.25"	1.75"	4.38"
710MO-0150 1V	1½"	FKM	11/4"	17	0	105	302	30	17.0	5.40"	6.90"	2.00"	4.38"
710MO-0200 1V	2"	FKM	1½"	27	0	105	302	30	22.0	5.90"	7.0"	2.25"	4.38"
710SS-2075 1V	3/4"	PTFE	3/4"	7	0	105	356	30	13.0	4"	5.90"	1.50"	4.38"
710SS-2100 1V	1"	PTFE	1"	12	0	105	356	30	15.0	4.80"	6.25"	1.75"	4.38"
710SS-2150 1V	1½"	PTFE	11/4"	17	0	105	356	30	16.0	5.40"	6.90"	2.0"	4.38"
710SS-2200 1V	2"	PTFE	1½"	26	0	105	356	30	21.0	5.90"	7.0"	2.25"	4.38"
710SS-3300 1V	3"	PTFE	3"	93.60	0	45	356	48	44.0	8.80"	9.50"	4.50"	4.38"
710SS-0300 1V	3"	PTFE	3"	93.60	0	45	302	48	44.0	8.80"	9.50"	4.50"	4.38"





570 E. 7th Street, P.O. Box 238 | Dubuque, IA 52004-0238 t. 563.583.5701 | 800.553.4840 | f. 563.583.5028 www.morbros.com



SPECIFICATION SHEET

#### **Application**

Pressure vacuum vents are installed on the top of underground and low volume aboveground storage tank vent pipes. Vent allows tank to "breathe" during filling and discharging operations. Pressure and vacuum poppets seal vapors in tank when pressure is equalized. Settings are approximate.

The 749T provides the same functions as the 749 and is designed for use on underground and low volume aboveground tanks storing Diesel Exhaust Fluid (DEF) and other products requiring PTFE and stainless construction.

#### **Features and Details**

- Screen protects the tank from debris and insects
- Integrated internal drain port channels water away from the tank
- Vent vapors up and outward per NFPA 30
- · Conserves fuel
- Certified SCFH ratings

#### **Materials of Construction**

- Body and hood... anodized aluminum (749T—is PTFE coated aluminum)
- Pressure poppet... anodized aluminum (749T—is HDPE)
- Vacuum poppet... brass vacuum (749T—is stainless steel)
- Body seal... Buna-N (749T—is FKM)
- Screen... 40 mesh stainless steel
- · Springs... stainless steel
- Set screws... Zinc-plated steel (749T—is Nylon)
   \*HDPE = High density polyethelene

#### **Certifications and Listings**

CARB 95-14 (749CRB0500 model); CARB 95-15 (749CRB0600 model); CARB 96-19 (749CRBS0600 model); 749CRB Pressure Vacuum Vents (models 749CRB0600 AV, 749CRB1600 AV, 749CRBS0600 AV and 749CRBS1600 AV), meet the requirements of EPA 40 CFR part 63 for Gasoline Dispensing Facilities



#### **WARNING**

749T

Fig. 749 P/V vent must only be used in conjunction with motor fueling and/or low capacity flow. Fluid handling in lines larger than that used for retail service stations can cause tank to rupture or implode.

WARNING: DO NOT FILL OR UNLOAD FUEL FROM A STORAGE TANK UNLESS IT IS CERTAIN THAT THE TANK VENTS WILL OPERATE PROPERLY. Morrison tank vents are designed only for use on shop fabricated atmospheric tanks which have been built and tested in accordance with UL 142, NFPA 30 & 30A, and API 650 and in accordance with all applicable local, state, and federal laws. In normal operation, dust and debris can accumulate in vent openings and block air passages. Certain atmospheric conditions such as a sudden drop in temperature, below freezing temperatures, and freezing rain can cause moisture to enter the vent and freeze which can restrict internal movement of vent mechanisms and block air passages. All storage tank vent air passages must be completely free of restriction and all vent mechanisms must have free movement in order to insure proper operation. Any restriction of airflow can cause excessive pressure or vacuum to build up in the storage tank, which can result in structural damage to the tank, fuel spillage, property damage, fire, injury, and death. Monthly inspection, and immediate inspection during freezing conditions, by someone familiar with the proper operation of storage tank vents, is required to insure venting devices are functioning properly before filling or unloading a tank.





Item Number	Α	В	С	D	E	SCFH	Height	Weight
7490100 AV	2N	8.0 oz	0.50 oz	М	N	6200 @ 20oz./in.sq.	4.33	1.0
7490200 AV	2N	12.0 oz	0.50 oz	М	N	7500 @ 25oz./in.sq.	4.33	1.0
7491100 AV	3N	8.0 oz	0.50 oz	М	N	6200 @ 20oz./in.sq.	5.91	1.55
7491200 AV	3N	12.0 oz	0.50 oz	М	N	7500 @ 25oz./in.sq.	5.91	1.55
749S0100 AV	2S	8.0 oz	0.50 oz	М	N	6200 @ 20oz./in.sq.	4.33	1.0
749S0200 AV	2S	12.0 oz	0.50 oz	М	N	7500 @ 25oz./in.sq.	4.33	1.0
749S1100 AV	3S	8.0 oz	0.50 oz	М	N	6200 @ 20oz./in.sq.	6.28	1.65
749S1200 AV	3S	12.0 oz	0.50 oz	М	N	7500 @ 25oz./in.sq.	6.28	1.65
749CRB0500 AV	2N	8.0 oz	5.0 oz	V	Υ	6200 @ 20oz./in.sq.	4.33	1.45
749CRB0600 AV	2N	3" W.C.	8" W.C.	V	Υ	3800 @ 8.2" H2O	4.33	1.95
749CRB1500 AV	3N	8.0 oz	5.0 oz	V	N	6200 @ 20oz./in.sq.	5.91	1.65
749CRB1600 AV	3N	3" W.C.	8" W.C.	V	N	3800 @ 8.2" H2O	5.91	1.65
749CRBS600 AV	2S	3" W.C.	8" W.C.	V	N	3800 @ 8.2" H2O	4.33	1.45
749CRBS1600 AV	3S	3" W.C.	8" W.C.	V	N	3800 @ 8.2" H2O	6.28	1.95
749BSP0100 AV	2B	8.0 oz	0.50 oz	М	N	6200 @ 20oz./in.sq.	4.33	1.0
749BSP0200 AV	2B	12.0 oz	0.50 oz	М	N	7500 @ 25oz./in.sq.	4.33	1.0
749T0200 AV	28	8.0 oz	0.50 oz	V	N	7500 @ 25oz./in.sq.	4.33	1.0

#### **SPECIFICATION OPTIONS:**

A— Body connection: 2" NPSM (2N), 2" Slip-on style (2S), 2" BSP (2B), 3" NPSM (3N), or 3" Slip-on style (3S)

**B**—Pressure setting: oz = oz/sq inch, wc = water column

**C—**Vacuum setting: oz = oz/sq inch, wc = water column

**D**—Pressure seal: metal-to-metal seat (M) or metal/FKM o-ring seat (V)

**E—**C.A.R.B. approval: yes or no (Y/N) **Height**—Dimension from base to top of vent

Weight—Shipping weight (lbs)

SPECIFICATION SHEET

#### **Application**

Atmospheric updraft vents are installed on the top of storage tank vent pipes on underground and aboveground fuel storage tanks.

#### **Features and Details**

- Directs vapors outward and upward in accordance with NFPA 30
- Protects the vent line from debris and insects
- · Water-resistant rain cap sheds water away from the vent line
- Slip-on design with set screws for easy installation
- Internal drain channels water penetration out through weep hole
- 354T is compatible with DEF

#### **Materials of Construction**

#### 354

- Body and cap... aluminum die cast
- · Screen... 40 mesh stainless steel

#### 354T

- Body and cap... PTFE coated black aluminum
- · Screen... 40 mesh stainless steel

#### **Certifications and Listings**

CARB 89-12 (1½" and 2" 354 models)

Item Number	Size (slip-on)	Weight (lbs)	Venting Capacity (SCFH) (@ 2.5 PSI)
3540100 AV	1½"	0.75	27,650
3540200 AV	2"	0.75	27,650
3540300 AV	3"	1.50	59,000
3540400 AV	4"	2.25	116,900
0547 0000 414	0,4	0.75	07.050
354T0200 AV	2"	0.75	27,650
354T0300 AV	3"	1.50	59,000





NOTE

Open vents will allow unrestricted evaporation of product.

WARNING: DO NOT FILL OR UNLOAD FUEL FROM A STORAGE TANK UNLESS IT IS CERTAIN THAT THE TANK VENTS WILL OPERATE PROPERLY. Morrison tank vents are designed only for use on shop fabricated atmospheric tanks which have been built and tested in accordance with UL 142, NFPA 30 & 30A, and API 650 and in accordance with all applicable local, state and federal laws. In normal operation, dust and debris can accumulate in vent openings and block air passages. Certain atmospheric conditions such as a sudden drop in temperature, below freezing temperatures, and freezing rain can cause moisture to enter the vent and freeze which can restrict internal movement of vent mechanisms and block air passages. All storage tank vent air passages must be completely free of restriction and all vent mechanisms must have free movement in order to insure proper operation. Any restriction of airflow can cause excessive pressure or vacuum to build up in the storage tank, which can result in structural damage to the tank, fuel spillage, property damage, fire, injury, and death. Monthly inspection, and immediate inspection during freezing conditions, by someone familiar with the proper operation of storage tank vents, is required to insure venting devices are functioning properly before filling or unloading a tank. Normal vents such as pressure vacuum and updraft vents for aboveground storage tanks should be sized according to NFPA 30 (2008) 21.4.3

MORRISON BROS. CO.

570 E. 7th Street, P.O. Box 238 | Dubuque, IA 52004-0238 t. 563.583.5701 | 800.553.4840 | f. 563.583.5028 www.morbros.com

#### 1519 Mechanical Tank Top Gauge with Relay Output

SPECIFICATION SHEET

#### **Application**

Designed for installation on top of horizontal and vertical tanks up to 25' in height, the 1519 mechanical tank gauge provides a readout in feet and inches and includes a single liquid level set point to activate an external alarm box.

#### **Features and Details**

- Viewable up to 25' in tank height
- · Readout in feet and inches
- Easy to read from wide viewing angle
- · Easy to install and calibrate
- Installs through 2" schedule 40 pipe or 2" tank bung (drop tube float models require a 4" tank opening)
- Vapor tight to allow for standard tank pressure testing and sealing up to 5 PSI
- Vapor is contained from viewing area to prevent lens fogging
- 1519M...metric versions available to mount on top of horizontal and vertical tanks up to 7 meters (23') in height, providing readouts in centimeters

#### Gauge with Relay Output

- Desired alarm level is set within gauge head
- Alarm level setting can be verified
- The level alarm relay output wiring from the gauge has to be connected to an external alarm box (sold separately). Options include the 918 series and 918AC series alarm boxes.

#### **Battery Power Module**

- Can be installed in any convenient location
- One 3.6 volt lithium AA replaceable battery
- Anticipated battery life is 4 years
- Low battery light indicator

#### Alpha Wire 77112 (required cable for connecting gauge to Battery Power Module)\*

- 5 Conductors
- 22 AWG (7/30 Stranded) tinned copper
- · Foil shield with drain wire
- Temperature range: -50 to 150C

\*Wire needs to be purchased to connect a 1519 gauge to the Battery Power Module.

Separate wire is required from the gauge to external alarm. See external alarm specifications for wire requirements.









#### 1519 Mechanical Tank Top Gauge with Relay Output (continued)

#### **Materials of Construction**

- Body... Cast aluminum
- · Gears and gear cogs... Acetal
- Hardware (including captive screws on front cover)... Stainless steel
- Float... Stainless steel
- · Cable... Stainless steel
- Spring... 301 stainless steel
- Shaft bushing... Stainless steel
- O-ring... FKM
- Lens cover... Acrylic
- · Power module enclosure... Polyester fiberglass


#### **Code Compliance**

UL/cUL 913

Item Number	Description	Float	Length
15192500 AG	Mechanical tank top gauge with alarm relay, angled face	Standard	0-25'
15192550 AG	Mechanical tank top gauge with alarm relay, vertical face	Standard	0-25'
15192510 AG	Mechanical tank top gauge with alarm relay, angled face	Drop Tube	0-25'
15192515 AG	Mechanical tank top gauge with alarm relay output, vertical face	Drop Tube	0-25'
1519M-7000 AG	Metric mechanical tank top gauge with alarm relay, angled face	Standard	0-700 CM
1519M-7050 AG	Metric mechanical tank top gauge with alarm relay, vertical face	Standard	0-700 CM
1519M-7010 AG	Metric mechanical tank top gauge with alarm relay, angled face	Drop Tube	0-700 CM
1519M-7015 AG	Metric mechanical tank top gauge with alarm relay, vertical face	Drop Tube	0-700 CM

#### Alpha Wire 77112 (required cable)

Item Number	Description	Length
15190015 CC	Five-conductor shielded cable	15'
15190025 CC	Five-conductor shielded cable	25'
15190050 CC	Five-conductor shielded cable	50' (spool)
15190100 CC	Five-conductor shielded cable	100' (spool)
15190200 CC	Five-conductor shielded cable	200' (spool)





570 E. 7th Street, P.O. Box 238 | Dubuque, IA 52004-0238 t. 563.583.5701 | 800.553.4840 | f. 563.583.5028 www.morbros.com

The Morrison 715 Series remote fill box is a simple 10-gallon capacity cabinet that provides containment of small spills during tank filling operations. Each unit is supplied with tank mount brackets for easy installation on storage tanks.

#### **Features**

- 10-gallon (37.85 liter) capacity
- 2" or 3" male NPT threaded or 150# raised face flange top connection
- Vented and weatherproof
- · Hinged door is lockable with a padlock
- Bottom sloped (right to left) toward drain and pump mounting location; drains on left side
- Vapor recovery mounting bracket integrated into the cabinet exterior
- · Vapor recovery adaptor, cap, and u-bolt kits are available
- Available with hand pump assembly, ball valve, quick disconnect check valve coupler/adaptor, dry disconnect adaptor, and dust cap/ plug in 2" or 3" configuration
- All connection assemblies are factory installed and tested prior to shipping
- DEF, Aviation, and E-85 models are available
- Post mount kits and four-leg stands are available in powder coated steel
- · Four-leg stands are also available in stainless steel

#### **Construction Details**

- Box and door are 14-gauge steel, powder coated white, or 304 stainless steel
- Ball valve is Morrison 691 series brass or 691BSS series stainless steel
- Quick disconnect coupler and plug are aluminum, anodized aluminum, or stainless steel
- Quick disconnect adaptor and cap are anodized aluminum
- · Dry disconnect adaptor and cap are aluminum, anodized aluminum, or stainless steel

#### Vapor recovery kit

- Vapor recovery adaptor is aluminum with FKM
- · Vapor recovery cap is aluminum, powder coated orange
- Hand pump is steel construction, PTFE seals with FKM o-rings, or stainless steel with PTFE and FKM

#### **Box dimensions**

Width = 24.38"

Height = 28.88" (34.8" including flange)

Depth = 19.19''

#### **Approvals**

CAN-ULC-S663-11; Florida DEP EQ-787







#### SPECIFICATION SHEET


Item Number	Size	Description	Weight			
715T00-0000-0	3″—10 gal.	Top connection w/ no outlets				
715-TT3-0000-0	3"—10 gal.	Top connection w/ no internal components				
715TT3-000B-0	3"—10 gal.	Top connection w/ hand pump				
715TT3-2QBB-0	3"—10 gal.	Top connection w/2" AL female QD coupler, BR ball valve, hand pump				
715-TT3-2MBB-0	3"—10 gal.	Top connection w/2" AL male QD adaptor, BR ball valve, hand pump	141 lbs			
715-TT3-3QBB-0	3"—10 gal.	Top connection w/3" AL female QD coupler, BR ball valve, hand pump	144 lbs			
715TT3-3QBB-0	3'—10 gal.	Top connection w/3" AL remaie QD coupler, BK ball valve, hand pump	144 lbs			
			143 lbs			
715TT3-2DBB-0	3"—10 gal.	Top connection w/2" AL dry disc adaptor, BR ball valve, hand pump	158 lbs			
715TT3-3DBB-0	3"—10 gal.	Top connection w/3" AL dry disc adaptor, BR ball valve, hand pump	100 IDS			
715TT3-2MB0-0	3"—10 gal.	Top connection w/2" AL male QD adaptor, BR ball valve				
715TT3-3MB0-0	3"—10 gal.	Top connection w/3" AL male QD adaptor, BR ball valve				
715TT3-2QB0-0	3"—10 gal.	Top connection w/2" AL female QD coupler, BR ball valve				
715TT3-2DS0-0	3"—10 gal.	Top connection w/2" AL dry disc adaptor, SS ball valve				
715TT3-2DSE-0	3"—10 gal.	Top connection w/2" AL dry disc adaptor, SS ball valve, E85 hand pump				
715S-TT3-0000-0	3"—10 gal.	SS top connection w/ no internal components	135 lbs			
715S-TT3-2QBB-0	3″—10 gal.	SS top connection w/2" AL female QD coupler, BR ball valve, hand pump	132 lbs			
715S-TT3-2MBB-0	3"—10 gal.	SS top connection w/2" AL male QD adaptor, BR ball valve, hand pump	132 lbs			
715S-TT3-3QBB-0	3″—10 gal.	SS top connection w/3" AL female QD coupler, BR ball valve, hand pump	144 lbs			
715S-TT3-3MBB-0	3″—10 gal.	SS top connection w/3" AL male QD adaptor, BR ball valve, hand pump	144 lbs			
715S-TT3-2DBB-0	3″—10 gal.	SS top connection w/2" AL dry disc adaptor, BR ball valve, hand pump				
715S-TT3-3DBB-0	3″—10 gal.	SS top connection w/3" AL dry disc adaptor, BR ball valve, hand pump				
715S-TT3-2DS0-0	3"—10 gal.	SS top connection w/2" AL dry disc adaptor, SS ball valve				
715S-TT3-3DS0-0	3"—10 gal.	SS top connection w/3" AL dry disc adaptor, SS ball valve				
715S-TT3-2DSE-0	3"—10 gal.	SS top connection w/2" AL dry disc adaptor, SS ball valve, E85 hand pump				
715S-TT3-2MBE-0	3″—10 gal.	SS top connection w/2" AL male QD adaptor, BR ball valve, E85 hand pump				
715S-TT3-3DSE-0	3"—10 gal.	SS top connection w/3" AL dry disc adaptor, SS ball valve, E85 hand pump				
715S-TT3-2ES0-0	3"—10 gal.	SS top connection w/2" SS dry disc adaptor, SS ball valve				
715S-TT3-2ESS-0	3″—10 gal.	SS top connection w/2" SS dry disc adaptor, SS ball valve, SS hand pump				
715S-TT3-2SS0-0	3"—10 gal.	SS top connection w/2" SS female QD coupler, SS ball valve				
715S-TT3-2SSS-0	3"—10 gal.	SS top connection w/2" SS female QD coupler, SS ball valve, SS hand pump				
715S-TT3-3SS0-0	3"—10 gal.	SS top connection w/3" SS female QD coupler, SS ball valve				
715S-TT3-3SSE-0	3"—10 gal.	SS top connection w/3" SS female QD coupler, SS ball valve, E85 hand pump				
715TF4-0000-0	2"—10 gal.	Flanged top connection w/ no outlets				
715S-TF4-0000-0	2"—10 gal.	SS flanged top connection w/ no outlets				
715TF5-0000-0	3"—10 gal.	Flanged top connection w/ no outlets				
715S-TF5-0000-0	3"—10 gal.	SS flanged top connection w/ no outlets				
715VR30 AK		3" Vapor recovery kit				
715VR40 AK		4" Vapor recovery kit				
715P060 AK		Post mount kit - 3" x 60" post with clamps and base				
715S400 AS		Four-leg stand for 715 fill box, powder coated steel				
715SS400 AS		Four-leg stand for 715 fill box, stainless steel				
7150373 AK		Mounting plate assembly kit				
		5 ;				


<sup>\*</sup>Please consult Price List for additional options.



570 E. 7th Street, P.O. Box 238 | Dubuque, IA 52004-0238 t. 563.583.5701 | 800.553.4840 | f. 563.583.5028 www.morbros.com








#### 715 Part Numbering System

#### How to "Build-a-Box"

To order, simply select desired option from each category and insert the corresponding letter or number in the appropriate space below.



S

M

dust cap

#### Additional Options:

- 60" Post mount kit: 715---P060 AK
- Mounting Plate: 715---0373 2PPW (not compatible with in-wall models)
- Stand: 715---S400 AS (4-leg stand, powder coated steel)
- Stand: 715S--S400 AS (4-leg stand, stainless steel)
- Vapor recovery kits: 715---VR30 AK (3") and 715---VR40 AK (4")



For a complete listing of 715 item numbers, please refer to the Morrison Price List.

90° quick disconnect stainless steel coupler with check

stainless steel check valve, FKM seals, and aluminum

90° quick disconnect aluminum male adaptor with

valve, FKM seals, and aluminum dust plug

570 E. 7th Street, P.O. Box 238 | Dubuque, IA 52004-0238 t. 563.583.5701 | 800.553.4840 | f. 563.583.5028

www.morbros.com

MORRISON BROS. CO.



#### Model 73590CA Check Valve Adaptor

#### **Application**

The 73590CA cam and groove adaptor with check valve is used in specialized applications where it is necessary and/or convenient to be able to connect and disconnect tank filling components quickly and cleanly.

#### **Features and Details**

- Male quick connect adaptor mates with traditional quick disconnect fill couplers
- Integrated check valve and fill adaptor reduces product loss at disconnect
- Space saving 90° design saving design fits into small spaces such as Morrison model 715 remote fill boxes

#### **Materials of Construction**

- Hard coated aluminum body
- Stainless steel plunger
- Viton® disc

Item Number	Size	Description	Weight (lbs)
73590CA0200 AV	2"	90° check valve; male adaptor; female threads	2.0
73590CA0300 AV	3"	90° check valve; male adaptor; female threads	5.0

#### Optional dust caps:



,	Item Number	Size	Description
	735DCA2000ACEVR	2"	Anodized aluminum dust cap; EVR approved
	735DCA3000ACEVR	3"	Anodized aluminum dust cap: EVR approved





570 E. 7th Street, P.O. Box 238 | Dubuque, IA 52004-0238 t. 563.583.5701 | 800.553.4840 | f. 563.583.5028 www.morbros.com

#### Model 927/928/735DC Series

#### **Application**

The Morrison 927 dry disconnect adaptor is installed at the fill point in the fill line of a fuel storage tank system. The internal spring loaded poppet assembly remains closed providing a liquid-tight seal when not connected to a dry disconnect coupler.

The Morrison 928 dry disconnect coupler is installed on the end of delivery vehicle hose. When coupled, the 927 and 928 provide a liquid-tight connection enabling a dry connection and a dry disconnection.

The 735DC dust cap serves as a protective cover for the 927 adaptor when not in use.

927 models mate with PT Maxi-Dry® and OPW Kamvalok® couplers.

#### **Code Compliance**

EVR

EVR

735DC models meet California EVR VR-402 and US Military CID A-A-59326D; some 927 and 928 models meet CARB Phase 1 EVR VR-402

Item Number	Size	Description	A	В	С	D	E	Cap Size	Weight (lbs)
9270150 1A	1½"	Dry disconnect adaptor	1N	2"	Α	F	N	2"	1.63
9270200AAEVR	2"	Dry disconnect adaptor	2N	21/2"	А	F	Υ	2½"	1.98
9270300AAEVR	3"	Dry disconnect adaptor	3N	4"	А	F	Υ	4"	3.50
9270400AAEVR	4"	Dry disconnect adaptor	4N	4"	Α	F	Υ	4"	3.50
9095A5201AAEVR	4" x 2"	Dry disconnect adaptor	4N	2½"	Α	F	Υ	2½"	2.50
927B0200 AA	2"	Dry disconnect adaptor	2N	21/2"	В	F	N	2½"	3.05
927S0150 1A	1½"	Dry disconnect adaptor	1N	2"	SS	F	N	2"	3.80
927S0200 1A	2"	Dry disconnect adaptor	2N	21/2"	SS	F	N	2½"	5.90
927S0300 1A	3"	Dry disconnect adaptor	3N	4"	SS	F	N	4"	18.25
9280150 1C	1½"	Dry disconnect coupler	1N	2"	А	F	N	N/A	4.40
9280150ACEVR	1½"	Dry disconnect coupler	1N	2"	Α	F	Υ	N/A	4.40
9280200 1C	2"	Dry disconnect coupler	2N	21/2"	Α	F	N	N/A	6.0
9280200ACEVR	2"	Dry disconnect coupler	2N	2½"	Α	F	Υ	N/A	6.0
9280300 1C	3"	Dry disconnect coupler	3N	4"	Α	F	N	N/A	12.60
9280300ACEVR	3"	Dry disconnect coupler	3N	4"	Α	F	Υ	N/A	12.60
928S0150 1C	1½"	Dry disconnect coupler	1N	2"	SS	F	N	N/A	
928S0200 1C	2"	Dry disconnect coupler	2N	21/2"	SS	F	N	N/A	
928S0300 1C	3"	Dry disconnect coupler	3N	4"	SS	F	N	N/A	
735DC-2000ACEVR	2"	Dust cap, use w/ 1½" 927 adaptors	N/A	N/A	Α	В	Υ	N/A	1.0
735DCA2000ACEVR	2"	Dust cap, use w/ 1½" 927 adaptors	N/A	N/A	AA	В	Υ	N/A	1.0
735DC-2500ACEVR	21/2"	Dust cap, use w/ 2" 927 adaptors	N/A	N/A	Α	В	Υ	N/A	1.25
735DCA2500ACEVR	21/2"	Dust cap, use w/ 2" 927 adaptors	N/A	N/A	AA	В	Υ	N/A	1.25
735DC-3000ACEVR	3"	Dust cap, use w/ 3" adaptors	N/A	N/A	Α	В	Υ	N/A	1.50
735DCA3000ACEVR	3"	Dust cap, use w/ 3" adaptors	N/A	N/A	AA	В	Υ	N/A	1.50
735DC-4000ACEVR	4"	Dust cap, use w/ 3" & 4" 927 adaptors	N/A	N/A	Α	В	Υ	N/A	2.50
735DCA4000ACEVR	4"	Dust cap, use w/ 3" & 4" 927 adaptors	N/A	N/A	AA	В	Υ	N/A	2.50

SPECIFICATION SHEET





#### **SPECIFICATION OPTIONS:**

A—Female threads: 1½" NPT (1N); 2" NPT (2N); 2" NPS (2S); 3" NPT (3N); 4" NPT (4N)

**B**—Coupler size

C—Body: Hard coated aluminum (A); Anodized aluminum (AA); Brass (B); Stainless steel (SS)

**D**—Seals: FKM (F); Buna-N (B) **E**—EVR: Yes (Y); No (N)

Cap size—In inches
Weight—Shipping weight



570 E. 7th Street, P.O. Box 238 | Dubuque, IA 52004-0238 t. 563.583.5701 | 800.553.4840 | f. 563.583.5028



Southland is a leader in precision-made steel, red brass and malleable iron pipe, nipples, fittings and related products. Manufactured in our North American facilities and threaded to industry specifications to provide a secure and trusted fit, Southland products are the trusted choice for plumbing, OEM, oil, gas and steam applications. Durable and highly resistant to rust and corrosion, every Southland pipe, nipple and fitting is 100% inspected and quality tested.



Piping will be 1-1/2" piping and 3" black piping.

#### Steel Pipe & Ready Cut Pipe

Our extensive line of welded black steel and galvanized steel pipe meets rigid industry standards and is backed by one of the most trusted names in the industry. Available in 1/4" to 4" diameters and offered in various lengths including 10-foot or 21 foot cut lengths, our steel pipes offer a choice of plain, threaded or coupled ends.

#### **Product Highlights:**

- · Available from 1/8" 4" Diameters
- · Available in Black & Galvanized
- · Available in Ready Cut Pipe Assortments
- . Pipes supplied in lengths from 10ft to 21ft
- Produced by Electric Resistance Welded (ERW) process

#### Specifications:

- Welded steel pipe schedule 40 (1/2) through 6") and 80 (1/2" to 2") complies with:
- -Galvan zed P pe ASTM A-53 standard
- -Black Pipe ASTM A-53 and API 5L standards
- -Threads ASME ANSI B1 20/1 standard

- ·Produced in a stretched-reduced mill to ensure full body normalized pipe
- · Hot dip galvanizing process according to ASTM standards
- · Galvanized Products meet Californ a Lead Plumbing Law
- Seamless steel pipe schedule 40, 80, 160 in diameters from 1/8" to 4"complies with:
- Black pipe ASTM A-106 grade B
- Threads ASME /ANS! B1:20:1 standard
- Welded Steel Ready Cut Pipe
- Schedule 40 and 80 in sizes from 1/2" to 4"
  - \*Galvanized Steel ASTM A-53
  - \*Black Steel ASTM A-53 / API 5L



#### Steel Nipples

We manufacture both black and gal vanized welded steel nipples in 11 diameters from 1 "to 4" and in 14 different length s ranging up to 12 ". Available individually or in pre-packaged assortments, we also offer a full selection of pre-cut welded steel pipes in the same diameters and lengths.

#### **Product Highlights:**

- · Ava lab le from 1 8 " -4" Diameters
- •Ava lab e in Lengths from C bsed 12 "
- Ava lab e in Black & Ga van zed Schedu e 40 and 80 Pipe Nipples
- Ava lab e in Black & Ga van zed Schedu e 4 Q 80, 160 & XXHvy Seamless Nipples
- NAFTA approved

#### Specifications:

- · Welded Steel Pipe Nipples Black and Ga van zed Schedules 40 and 80 in sizes from 1/8" through 6"
  - ASTM A-733 , ASM EANSI B1 20 1 and ASTM A-53
- •We also have available Merchant Couplings, Chrome Plated Nipples, Stainless Steel
- Nipples & Conduit Nipples
- Color coded product labels
- \*Preferred industry pack quantities
- Galvanized Products meet California Lead Plumbing Law
- Seamless Steel Pipe Nipples
- Schedule 40 and 80 in sizes from 1/8" to 4"
- Black Steel ASTM A-733, ASME/ANSI B1.20.1 and A-106 grade B







Fittings will 1-1/2" and 3" black steel fittings as needed.

#### Malleable Iron Fittings


We offer one of the most extensive selections of black and galvanized malleable iron fittings in the industry. Available in 13 diameters from 1/8" to 6", every fitting is produced to exact specifications. All galvanized products are zinc-coated for water applications and meet all low-lead requirements. In addition, all of our iron fittings undergo our rigorous testing and quality inspection.

#### **Product Highlights:**

- . Stocked in most figures from 1/8" to 6"
- · Available in Black finish for oil and gas fluid applications
- · Available in Galvanized finish for water, air and steam installations
- Available for servicing 150 psi and 300 psi applications
- Hot dip galvanizing process according to ASTM A-153 standard
- · Galvanized Products meet California Lead Plumbing Law

#### Specifications:

- Threaded ends meeting with ANSI/ASME B1.20.1 standard
- Material meeting with ASTM A-197 standard
- Dimensions meet the following:
- Threaded Fittings with ASME B16.3 standard
- Unions with ASME B16.39 standard
- Bushing Reducer and Plugs with ASME B16.14 standard



#### Red Brass Fittings & Nipples

Our Red Brass Fittings and Nipples are carefully produced and threaded to industry specifications to provide a secure and trusted fit. While primarily developed for carrying water in commercial plumbing and OEM applications, they are also used in oil, gas and steam applications. Durable and highly resistant to rust and corrosion, every red brass fitting and nipple is 100% inspected and quality tested.

#### **Product Highlights:**

- · Made with Class 125lb Red Brass
- Nipples Available in Lengths from Close to 12\*
- · Available in Schedule 40 diameters from 1/8" to 4"

#### Specifications:

- Red Brass Nipples meets ASTM B43-96 specifications
- · All threads meet ASME/ANSI B1.20.1 standards
- . Meets ASTM B-687 standards





# FIREFLEX FLEXIBLE CONNECTORS

Since their introduction in 1995, FLEX-ING™ FIREFLEX Flexible Connectors have quickly become the industry standard and benchmark for quality as a means to easily connect one pipework system to other systems' components such as submersible pumps or shear valves. The benefit of their use is undeniable. They have quickly become an integral part of any installation. Installers love their ease of installation while station owners have come to depend on their durability and how easy they make regular maintenance. With tons of available options, Franklin Fueling Systems has the right connector to fit any application.



#### Highlights

- The corrugated fuel contact layers feature a 25% thicker metal construction and gain flexibility from having more corrugations per foot rather than thinner walls.
- Enclosing the corrugated fuel contact layer is a stainless steel braid that is manufactured from only high-grade stainless steel.
- Available in a multitude of end connections to ensure the right fit for any application - including tees, elbows, and FRP transitions
- The EZ FIT union style coupling system is specifically designed to make connections in confined spaces simple and tight.
- Each EZ FIT union style coupling comes complete with couplers and gaskets.


#### **Specifications**

- USA NFPA 30-A fire rated
- All metal construction means one flexible connector for both above and below ground applications
- An 18-8 alloy outer shell, 321 Stainless Steel inner core provides a long service life
- Thick, schedule 80 hex end fittings protect against deformation of the ends
- 100% pressure tested to assure quality
- UL 2039 approved for 50 psi working pressure
- EZ FIT clamp and gasket are included with each assembly

#### Approvals

 UL 2039 listed for above and below ground installation for use with gasoline, gas alcohol blends (up to E85), diesel, and biodiesel.





#### Ordering Information

Use these diagrams below along with the Ordering Guide at the bottom of the page to help you build your flexible connector model numbers.

#### **Ordering Options Diagram**

Use the options and descriptions in the Ordering Guide along with this diagram to assist in building your

model numbers.



#### **End Fitting Options**

Use the options and descriptions in the Ordering Guide along with the diagrams below to select your end fitting types (two total).



#### **Ordering Guide**

#### ABXCDXE

#### A = Product Type

FF = If either of the end connections are any type of swivel, this option must be selected.

FFUL = If both end connections are fixed (non-swivel), this option must be selected.

#### B = Hose Diameter

07 = 3/4"

10 = 1"

15 = 1½"

20 = 2"

30 = 3"

40 = 4"

#### C = Overall Length in Inches

Use two-digit format

#### D & E = End Fitting Options

EZ = EZ FIT flange only

EZM = EZ FIT male NPT (Each EZ FIT union style coupling comes complete with couplers and gaskets)

EZF = EZ FIT female NPT (Each EZ FIT union style coupling comes complete with couplers and gaskets)

EZFG = EZ FIT fiberglass glue pipe (Each EZ FIT union style coupling comes complete with couplers and gaskets)

M346 = Male swivel NPT

F346 = Female swivel NPT

HM = Hex male fixed NPT

HF = Hex female fixed NPT

BT = Hex male fixed BSPT

BTS = Male swivel BSPT

MS90 = 90° with male swivel NPT

Example: FF20X18M346XHM = FIREFLEX flexible connector with swivel end fitting(s), 2" hose diameter, 18" overall length, with one male swivel end fitting and one fixed hex male end fitting.

#### Flexible Connectors with Differing Hose and End Fitting Diameters

All end fittings are, by default, the same diameter as the hose. If you require a flexible connector where the end fitting diameter does not match the hose diameter, the size must be indicated numerically in front of the corresponding fitting as in the following example.

Example: FFUL15X18HMX2HM = FIREFLEX flexible connector with fixed end fittings, 1½" hose diameter, 18" overall length, with one 1½" hex male fixed end fitting, and one 2" hex male fixed end fitting.

#### Rules:

- 1) End fitting diameters can not be smaller than hose diameters.
- 2) Only one hose fitting per flexible connector can be of a different diameter than the hose diameter.
- 3) End fitting diameter must only be one size larger than hose (1" hose could use 1½" fitting, 1½" hose could use 2" fitting, etc.)



# MASTER YOUR



# MANAGEMENT

**AUTOMATE YOUR FUELING PROCESS** 

#### FMU-2500 & 3505 SERIES

- Built to military specifications
- Modular design and backward capability
- Ease of maintenance
- World class support



"FUELMAS"





#### FMU-2500 & 3505 SERIES

#### CUSTOMIZE YOUR FUEL MANAGEMENT NEEDS

The FMU-2500Plus and FMU-3505Plus are the industry leaders in commercial fleet and retail fueling automation. The passive fueling automation of the 3505 Series compliments the interactive automation of the 2500 Series using our state of the art patented RFID 2.4 technology.

Note: All FMU-2500Plus units can be easily upgraded to include passive automated features found in the 3505 Series at the fuel island.

#### **FEATURES & BENEFITS**

- Handles up to 8 hoses
- Communicates with up to 8 satellite FMU, each handling 8 hoses, for a total of 72 hoses per master FMU
- Fueling process initiated by keypad; PROKEE®; smartcard; proximity card; or AIM module
- FMU can be equipped to read fleet, aviation, and standard credit cards. Contact us for a current list
  of available networks
- · Works with mechanical and electronic dispensers, both retail and commercial
- Windows based software and operates on a SQL platform
- · Transactional data can be exported to most fleet maintenance or accounting programs
- · Communicates with a Tank Monitor Unit/Tank Gauge interface from a variety of manufacturers
- Supports Automatic/Manual Operation
- 24/7 Live customer support call center
- Customer Training provided at no cost
- All product research and development completed within our on-site Engineering Department







CONTACT US TO LEARN MORE

#### 800.888.9136 850.878.2558

www.MyFuelMaster.com Marketing@MyFuelMaster.com Syntech Systems, Inc. 100 Four Points Way, Tallahassee, FL 32305

# 



#### **Labeling Guidelines for:**

#### NFPA 704 PLACARDS AND LABELS

#### The NFPA 704 Placard

The NFPA 704 Diamond ("NFPA Diamond" or "fire diamond") is a standard placard that identifies the level of chemical hazard at fixed locations, such as production facilities, warehouses, storage tanks, and storage sheds. It is required by the California Fire Code and meets requirements under the Hazard Communication Act ("Right to Know")

The NFPA 704 diamond (shown at right) is divided into four colored quadrants. Each quadrant provides information about the materials inside:

- Blue represents health hazard.
- **Red** represents flammability.
- Yellow represents reactivity.
- White provides information about special precautions.


Fire Hazard Health Reactivity Hazard Hazard Specia Hazard

Within each quadrant is a number from 0 to 4 indicating the degree of risk associated with the material. The higher the number, the higher the risk. For some materials, the white

quadrant contains symbols indicating special hazards. (See NFPA Indicator Key, page 2)

#### Proper Hazard indicators (numbers) can be found on the product MSDS.

If more than one chemical is present at a facility, the NFPA diamond indicates overall hazard at that location, *not* the hazard posed by a particular chemical. It shows the highest of each of the four hazards present. For example, it may be that one chemical poses the highest health hazard while another poses the highest fire hazard.



**INSIDE BUILDING, CONTENTS** 

**OUTSIDE PLACARD** 

Labels meeting NFPA 704 standards and the "Right to Know" can very in format but consistently are the same in content.



RTK Label



NFPA Label

To meet Hazcom "Right to Know" act, labels must include:

- Manufacture
- Chemical name
- Common name
- Hazards

#### **NFPA INDICATOR KEY**

HEALTH HAZARD	FLAMMABILITY	REACTIVITY	SPECIAL		
4 - Materials which on very short exposure could cause death or major residual injury even through prompt medical treatment were given.	4 - Materials which will rapidly or completely vaporize at atmospheric pressure and normal ambient temperature, and which will burn.  FLASH POINT < 73	4 - Materials which are readily capable of detonation or of explosive decomposition or reaction at normal temperatures and pressures.	Specific chemical hazards, special information and personal protective equipment will be noted in this section. Specific hazards and their symbols are as follows:		
3 - Materials which on short exposure could cause serious temporary or residual injury even though prompt medical treatment were given.	3 - Liquids and solids that can be ignited under almost all ambient temperature conditions.  FLASH POINT< 100	3 -Materials that can detonate or explode but require a strong initiating source, or must be heated under confinement before initiation, or react explosively with water.	OX- Oxidizer  ACID - Acid  ALK - Alkali  COR- Corrosive  -W- No Water  Radioactive		
2 -Materials which on intense exposure could cause possible residual injury unless prompt medical treatment is given.	2 -Materials that must be moderately heated or exposed to relatively high ambient temperatures before igniting. FLASH > 100 < 200	2 -Materials that are normally unstable and readily undergo violent chemical changes but do not detonate; also materials that may react violently with water.	HMIS  A=Safety glasses B=Safety glasses, Gloves C=Glasses, gloves Protective apron D=Face shield, Gloves, apron E=Glasses, gloves		
1 -Materials which on exposure would cause irritation but only minor residual injury even if no treatment is given.	1 -Materials that must be preheated before ignition can occur. FLASH POINT > 200	1 -Materials that are normally stable, but can become unstable at high temp. and pressures, or may react with water with some release of energy.	Dust respirator F=glasses, gloves Respirator, apron G=Glasses, gloves Vapor respirator H=Goggles, gloves Apron, respirator I =glasses, gloves APR		
<b>0</b> -Materials which on exposure under fire conditions would offer no hazard beyond that of ordinary combustibles.	<b>0</b> -Materials that will not burn.	<b>0</b> -Materials that are normally stable even under fire explosive conditions, and that are not reactive with water.	K=supplied air, Mask or hood Suit and boots Or symbols may be used		

# 

### **Emergency Stop Solutions for Fueling Sites**

Emergency Stop Controls are required by the National Electrical Code at <u>ALL</u> fueling facilities. Power Integrity offers a full line of emergency stop operators to meet your site requirements.





IA-ESOCA Emergency Stop Operator with Cover & Alarm

#### **Emergency Stop Operators**

- Available in momentary, twist-to-reset, key-to-reset, and break glass configurations
- Clear tamperproof cover protects against accidental activation, damage, and vandalism
- Optional alarm protects against nuisance activation
- Standard operator includes (1) NO and (1) NC contact
- Custom labeling available

### **Cashier Control Stations**

- Allow employees to activate emergency stop system without leaving the cashier area
- Standard configuration includes
  - Emergency stop pushbutton
  - Emergency stop system reset pushbutton
- Available with optional lighting bypass switch
- Custom configurations available including
  - Product status lights
  - o Timed lighting override
  - Individual dispenser shut-down




IA-ESORS
Cashier Control Station with
Protective Shroud




Power • Control • Protect



### **Typical Emergency Stop Installation**





### **Attaching to Recessed Junction Box**

**Attaching to Surface Mount Junction Box** 

<b>Emergency Stop</b>	Operators - Outdoor Rated	
IA-ESOC	Emergency stop operator with lift-up clear cover	
IA-ESOCA	Emergency stop operator with lift-up clear cover and alarm	
IA-ESOC/T	Emergency stop operator, twist to release with lift-up clear cover	
IA-ESOCA/T	Emergency stop operator, twist to release with lift-up clear cover and alarm	
IA-ESOCK	SOCK Emergency stop operator, keyed reset with lift-up clear cover	
IA-ESOG	Emergency stop operator with "Break Glass", hammer, and (5) replacement discs	
<b>Emergency Stop</b>	Operator Accessories	
IA-ESPLATE	Emergency stop operator mounting plate with "emergency fuel shutoff" nameplate	
IA-BREAKTAB	KTAB Locking mechanism block with (5) one-time use breakaway seals	
<b>Cashier Control</b>	Stations - Indoor Rated	
	Cashier control with emergency stop button with shroud to prevent accidental	
IA-ESORS	pressing, and reset button	
	Cashier control with emergency stop button with shroud to prevent accidental	
IA-ESORLS	pressing, reset button, and light control bypass switch	
<b>Emergency Stop</b>	Operator Lift-Up Covers	
IA-PBCOVSA	Small lift-up clear cover with alarm for e-stop operators, 5.5"W x 7.0"H (Yellow)	
IA-PBCOVS	Small lift-up clear cover for e-stop operators, 5.5"W x 7.0"H (Yellow)	
IA-PBCOVLAR	Large lift-up clear cover with alarm for e-stop operators 7.0"W x 9.0"H (Red)	

### www.powerintegritycorp.com





### Attachment I:

20% or Less Impervious Cover Declaration (if project is multifamily residential, a school, or a small business and 20% or less impervious cover is proposed for the site) (NOT APPLICABLE)



### Attachment J: **BMPs** for Upgradient Stormwater

Existing on-site sand filter basin Permanent BMP continues to address any upgradient stormwater. The proposed project does not increase the IC at the site.



### Attachment K: **BMPs** for On-Site Stormwater

The proposed project will not increase impervious cover (IC) and the volume of potential on-site stormwater. The existing and approved sand filter basin permanent BMP was designed to capture and will continue to mitigate potential onsite stormwater flows.

Runoff from the developed site and proposed fueling island will convey to the existing approved sand filter basin permanent BMP that is designed to capture and detain the required water quality volume. For additional information, see the original approved calculations.



### Attachment L: **BMPs for Surface Streams** (NOT APPLICABLE)

No surface streams flow across the property.



Attachment M: **Construction Plans** 

#### PROJECT CONTACTS

OWNER:

**ENGINEER:** 

9115 CIRCLE DR. AUSTIN, TX 78736 SANDLIN SERVICES, LLC 9111 JOLLYVILLE RD, SUITE 212 AUSTIN, TEXAS 78759

806-679-7303

CONTACT: NICHOLAS SANDLIN, P.E.

CONTRACTOR: EXCELL FUELING SYSTEMS, INC 549 S LOOP 4 BUDA, TEXAS 78610 (512)280-5230 CONTRIBUTING ZONE & ABOVE GROUND STORAGE TANK PLANS

ADDRESS: 10625 W STATE HWY 29, LIBERTY HILL, TX 76527

PEDERNALES ELECTRIC COOP

DATE OF SUBMITTAL: 3/20/24

**APPROVALS:** 

-----

#### SURVEY AND BENCHMARK

ALL ELEVATIONS SHOWN HEREON ARE BASED ON THE FOLLOWING BENCHMARKS AND INFORMATION.

CONTRACTOR TO PROVIDE FIELD SURVEY AND BENCHMARK

BEARINGS ARE BASED ON THE TEXAS STATE PLAN COORDINATE SYSTEM OF 1983, TEXAS CENTRAL ZONE (NAD 83)

#### LEGAL DESCRIPTION

S8162 - SEWARD JUNCTION COMMERCIAL PARK, LOT 2, ACRES 6.22

#### ZONING AND USE

JURISDICTION:

ZONING:
EXISTING LAND USE:
PROPOSED LAND USE:
UNCHANGED

LIBERTY HILL (FULL PURPOSE)

C3 — GENERAL COMMERCIAL/RETAIL

ELECTRIC SERVICE PROVIDER

UNCHANGED

**WATERSHED** 

WATERSHED: SOUTH FORK SAN GABRIEL RIVER

#### EDWARDS AQUIFER


THIS PROJECT LIES WITHIN THE EDWARDS AQUIFER CONTRIBUTING ZONE AS DEFINED BY THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ)

#### FLOODPLAIN NOTE

THE 100-YEAR FLOODPLAIN AS DEFINED BY THE CITY REGULATION, IS CONTAINED WITHIN THE DRAINAGE EASEMENT(S) SHOWN HEREON, NO PORTION OF THIS TRACT IS WITHIN THE BOUNDARIES OF THE 100-YEAR FLOODPLAIN OF ANY WATERWAY THAT IS WITHIN THE LIMITS OF THE STUDY OF THE FEDERAL INSURANCE ADMINISTRATION FIRM PANEL #48491C0275E, AND INCORPORATED AREAS EFFECTIVE DATE 9/26/2008 FOR WILLIAMSON COUNTY, TEXAS.

REVISION RECORD

	SHEET LIST
NUMBER	TITLE
1	COVER PAGE
2	GENERAL NOTES (1 OF 4)
3	GENERAL NOTES (2 OF 4)
4	GENERAL NOTES (3 OF 4)
5	GENERAL NOTES (4 OF 4)
6	FINAL PLAT (1 OF 2)
7	FINAL PLAT (2 OF 2)
8	EROSION CONTROL AND DRAINAGE PLAN
9	AST TANK LAYOUT PLAN
10	EROSION CONTROL DETAILS



PROJECT LOCATION MAP N.T.S.



#### **CONTRACTOR GENERAL NOTES**

- 1. THE CONTRACTOR SHALL OBTAIN A "NOTICE OF PROPOSED INSTALLATION OF UTILITY LINE" PERMIT FROM THE COUNTY FOR ANY WORK PERFORMED IN THE EXISTING COUNTY RIGHT-OF-WAY (DRIVEWAY APRON, WATER MAIN TIE-IN, ETC.) THIS PERMIT APPLICATION WILL REQUIRE A LIABILITY AGREEMENT, A CONSTRUCTION COST ESTIMATE FOR WORK WITHIN THE RIGHT-OF-WAY INCLUDING PAVEMENT REPAIR (IF NEEDED), A PERFORMANCE BOND, CONSTRUCTION PLANS AND, IF NECESSARY, A TRAFFIC CONTROL PLAN. AN INSPECTION FEE, AND A PRE-CONSTRUCTION MEETING MAY ALSO BE REQUIRED, DEPENDING ON THE SCOPE OF WORK. THE PERMIT WILL BE REVIEWED AND APPROVED BY THE COUNTY ENGINEER, AND MUST ALSO BE APPROVED BY THE COUNTY COMMISSIONERS COURT IF ANY ROAD CLOSURE IS INVOLVED.
- 2. BY THE ACT OF SUBMITTING A BID FOR THIS PROPOSED CONTRACT, THE BIDDER WARRANTS THAT THE BIDDER, AND ALL SUBCONTRACTORS AND MATERIAL SUPPLIERS HE INTENDS TO USE, HAVE CAREFULLY AND THOROUGHLY REVIEWED THE DRAWINGS, SPECIFICATIONS AND ALL OTHER CONTRACT DOCUMENTS AND HAVE FOUND THEM COMPLETE AND FREE FROM ANY AMBIGUITIES AND SUFFICIENT FOR THE PURPOSE INTENDED. THE BIDDER FURTHER WARRANTS THAT TO THE BEST OF HIS OR HIS SUBCONTRACTORS' AND MATERIAL SUPPLIERS' KNOWLEDGE, ALL MATERIALS AND PRODUCTS SPECIFIED OR INDICATED HEREIN ARE ACCEPTABLE FOR ALL APPLICABLE CODES AND AUTHORITIES.
- 3. THE LOCATION OF ALL EXISTING UTILITIES SHOWN ON THESE PLANS HAS BEEN BASED UPON RECORD INFORMATION ONLY AND MAY NOT MATCH LOCATIONS AND/OR DEPTHS AS CONSTRUCTED. THE CONTRACTOR SHALL CONTACT THE AUSTIN AREA "ONE CALL" SYSTEM 1-800-245-4545, OR THE OWNER OF EACH INDIVIDUAL UTILITY, FOR ASSISTANCE IN DETERMINING EXISTING UTILITY LOCATIONS AND DEPTHS PRIOR TO BEGINNING ANY CONSTRUCTION. CONTRACTOR SHALL FIELD VERIFY LOCATIONS OF ALL UTILITY CROSSINGS PRIOR TO BEGINNING ANY CONSTRUCTION.
- 4. THE CONTRACTOR OR SURVEYOR WILL OBTAIN A DIGITAL COPY OF THE CAD FILES THAT REPRESENT THESE IMPROVEMENTS; SANDLIN SERVICES, LLC AND IT'S ASSOCIATES TAKE NO RESPONSIBILITY FOR THE LOCATION OF THESE IMPROVEMENTS IN ANY COORDINATE SYSTEM. DIGITAL FILES USED TO PRODUCE THESE PLANS WERE PARTIALLY CREATED BY PARTIES OTHER THAN SANDLIN SERVICES, LLC AND ARE NOT INTENDED FOR USE IN CONSTRUCTION STAKING. VERTICAL AND HORIZONTAL DATA SHALL BE INDEPENDENTLY VERIFIED BY CONTRACTOR'S R.P.L.S.
- 5. SANDLIN SERVICES, LLC HAS ENDEAVORED TO DESIGN THESE PLANS COMPLIANT WITH ADA/TDLR AND OTHER ACCESSIBILITY REQUIREMENTS. HOWEVER, THE CONTRACTOR SHALL NOT BE RELIEVED OF ANY RESPONSIBILITY FOR CONSTRUCTING THESE IMPROVEMENTS COMPLIANT WITH ALL APPLICABLE ACCESSIBILITY STANDARDS. IF THE CONTRACTOR NOTICES ANY DISCREPANCIES BETWEEN THESE PLANS AND ACCESSIBILITY LAWS/RULES, HE IS TO STOP WORK IN THE AREA OF CONFLICT AND NOTIFY THE ENGINEER IMMEDIATELY FOR A RESOLUTION AND/OR REVISION TO THESE PLANS. SANDLIN SERVICES, LLC SHALL NOT BE HELD RESPONSIBLE FOR CONSTRUCTING THIS SITE COMPLIANT WITH ACCESSIBILITY LAWS/RULES REGARDLESS OF WHAT IS SHOWN IN THESE PLANS.

COVER PAGE

SHEET 1 OF 10

P.E.C. LIBERTY HILL EAPP

EXCELL FUELING SYSTEMS

SANDLIN SERVICES, LLC

TBPELS FIRM #21356 9111 JOLLVILLE RD., STE. 212 AUSTIN, TX 78759

- GENERAL NOTES AND REQUIREMENTS:
  1. ALL CONTRACTORS MUST CONFINE THEIR ACTIVITIES TO THE WORK AREA. NO ENCROACHMENTS OUTSIDE OF THE WORK AREA WILL BE ALLOWED. ANY DAMAGE RESULTING THEREFROM SHALL BE CONTRACTOR'S SOLE RESPONSIBILITY TO REPAIR.
- THE CONTRACTOR SHALL PROTECT ALL EXISTING STRUCTURES, UTILITIES, MANHOLES, POLES, GUY WIRES, VALVE COVERS, VAULT LIDS, FIRE HYDRANTS, COMMUNICATION BOXES/PEDESTALS, AND OTHER FACILITIES TO REMAIN, AND SHALL REPAIR ANY DAMAGES AT NO COST TO THE OWNER.
- THE CONTRACTOR SHALL IMMEDIATELY REPAIR OR REPLACE ANY PHYSICAL DAMAGE TO PRIVATE PROPERTY OR PUBLIC IMPROVEMENTS, INCLUDING BUT NOT LIMITED TO: FENCES, WALLS, SIGNS, PAVEMENT, CURBS, UTILITIES, SIDEWALKS, GRASS, TREES, LANDSCAPING, AND IRRIGATION SYSTEMS, ETC .... TO ORIGINAL CONDITION OR BETTER AT NO COST TO THE OWNER.
- ALL AREAS IN EXISTING RIGHT-OF-WAY DISTURBED BY SITE CONSTRUCTION SHALL BE REPAIRED TO ORIGINAL CONDITION OR BETTER, INCLUDING AS NECESSARY, GRADING, LANDSCAPING, CULVERTS, AND
- THE CONTRACTOR SHALL SALVAGE ALL EXISTING POWER POLES, SIGNS, WATER VALVES, FIRE HYDRANTS, METERS, ETC... THAT ARE TO BE RELOCATED DURING CONSTRUCTION
- CONTRACTOR SHALL MAINTAIN ADEQUATE SITE DRAINAGE DURING ALL PHASES OF CONSTRUCTION, INCLUDING MAINTAINING EXISTING DITCHES OR CULVERTS FREE OF OBSTRUCTIONS AT ALL TIMES.
- SITE SAFETY IS SOLELY THE RESPONSIBILITY OF THE CONTRACTOR.
- THESE PLANS DO NOT EXTEND TO OR INCLUDE DESIGNS OR SYSTEMS PERTAINING TO THE SAFETY OF THE CONTRACTOR OR ITS EMPLOYEES, AGENTS, OR REPRESENTATIVES IN THE PERFORMANCE OF THE WORK. THE ENGINEER'S SEAL HEREON DOES NOT EXTEND TO ANY SUCH SAFETY SYSTEM. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL REQUIRED SAFETY PROCEDURES AND PROGRAMS. SIGNS RELATED TO SITE OPERATION OR SAFETY ARE NOT INCLUDED IN THESE PLANS.
- 10. CONTRACTOR OFFICE AND STAGING AREA SHALL BE AGREED ON BY THE OWNER AND CONTRACTOR PRIOR TO BEGINNING OF CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR ALL PERMITTING
- REQUIREMENTS FOR THE CONSTRUCTION OFFICE, TRAILER, STORAGE, AND STAGING OPERATIONS AND LOCATIONS.

  11. LIGHT POLES, SIGNS, AND OTHER OBSTRUCTIONS SHALL NOT BE PLACED IN ACCESSIBLE ROUTES.

  12. TOP RIM ELEVATIONS OF ALL EXISTING AND PROPOSED MANHOLES SHALL BE COORDINATED WITH TOP OF PAVEMENT OR FINISHED GRADE AND SHALL BE ADJUSTED TO BE FLUSH WITH THE ACTUAL FINISHED GRADE AT THE TIME OF PAVING.
- 13. CONTRACTOR SHALL ADJUST ALL EXISTING AND PROPOSED VALVES, FIRE HYDRANTS, AND OTHER UTILITY APPURTENANCES TO MATCH ACTUAL FINISHED GRADES AT THE TIME OF PAVING.
  14. THE CONTRACTOR IS RESPONSIBLE FOR CONSTRUCTION SEQUENCING AND PHASING AND SHALL CONTACT THE APPROPRIATE CITY OFFICIALS, INCLUDING BUILDING OFFICIAL, ENGINEERING INSPECTOR, AND FIRE MARSHALL TO LEARN OF ANY REQUIREMENTS.
- 15. CONTRACTOR IS RESPONSIBLE FOR PREPARATION, SUBMITTAL, AND APPROVAL BY THE CITY OF A TRAFFIC CONTROL PLAN PRIOR TO THE START OF CONSTRUCTION, AND THEN THE IMPLEMENTATION OF THE PLAN.
- 16. THE CONTRACTOR SHALL VISIT THE SITE PRIOR TO BIDDING TO DETERMINE EXISTING CONDITIONS.
- 17. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING AS-BUILT PLANS TO THE ENGINEER AND CITY IDENTIFYING ALL DEVIATIONS AND VARIATIONS FROM THESE PLANS MADE DURING CONSTRUCTION.
- 18. THE CONTRACTOR SHALL COMPLY WITH ALL LOCAL, STATE, AND FEDERAL EROSION CONTROL AND WATER QUALITY REQUIREMENTS.

  19. PRIOR TO COMMENCEMENT OF CONSTRUCTION, THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS AFFECTING THEIR WORK WITH THE ACTUAL CONDITION AT THE PROJECT SITE. IN ADDITION, THE CONTRACTOR MUST VERIFY THE ENGINEER'S LINE AND GRADE STAKES. IF THERE ARE ANY DISCREPANCIES FROM WHAT IS SHOWN ON THE CONSTRUCTION PLANS, THE CONTRACTOR MUST IMMEDIATELY PROVIDE THE INFORMATION TO THE ENGINEER BEFORE DOING ANY WORK, OTHERWISE, THE CONTRACTOR ASSUMES FULL RESPONSIBILITY. IN THE EVENT OF A DISAGREEMENT BETWEEN THE CONSTRUCTION PLANS, STANDARD SPECIFICATIONS, AND/OR DETAILS. THE CONTRACTOR SHALL SECURE WRITTEN INSTRUCTIONS FROM THE ENGINEER PRIOR TO PROCEEDING WITH ANY PART OF THE WORK AFFECTED BY OMISSIONS OR DISCREPANCIES. IF THE CONTRACTOR FAILS TO SECURE WRITTEN INSTRUCTIONS FROM THE ENGINEER, THE CONTRACTOR WILL BE CONSIDERED TO HAVE PROCEEDED AT THEIR OWN RISK AND EXPENSE. IN THE EVENT OF ANY DOUBT OR QUESTION ARISING WITH RESPECT TO SPECIFICATIONS, THE DECISION OF THE ENGINEER SHALL BE FINAL.
- 20. THE CONTRACTOR SHALL COMPLY WITH JURISDICTIONAL "GENERAL NOTES" FOR CONSTRUCTION, JURISDICTIONAL NOTES SHALL SUPERCEDE ANY CONFLICT WITH THE SANDLIN SERVICES, LLC. NOTES.
- 21.IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT THE VARIOUS UTILITY COMPANIES WHICH MAY HAVE BURIED OR AERIAL UTILITIES WITH OR NEAR THE CONSTRUCTION AREA BEFORE COMMENCING WORK TO HAVE THEM LOCATE THEIR EXISTING UTILITIES PRIOR TO CONSTRUCTION. CONTRACTOR SHALL USE EXTREME CAUTION AS THE SITE CONTAINS VARIOUS KNOWN AND UNKNOWN PUBLIC AND PRIVATE UTILITIES.
- COORDINATE ALL UTILITY LINE CROSSINGS TO ENSURE ALL PIPES MAINTAIN MINIMUM COVER, MINIMUM CLEARANCES, AND PROPER SEPARATION.
- 23. THE LOCATIONS, ELEVATIONS, DEPTH, AND DIMENSIONS OF EXISTING UTILITIES SHOWN ON THE PLANS WERE OBTAINED FROM AVAILABLE UTILITY COMPANY MAPS AND PLANS, AND ARE CONSIDERED APPROXIMATE. THE ENGINEER SHALL BE NOTIFIED WHEN A PROPOSED IMPROVEMENT CONFLICTS WITH AN EXISTING UTILITY.
- 24. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING ANY ADJUSTMENTS AND RELOCATIONS OF EXISTING UTILITIES THAT CONFLICT WITH THE PROPOSED IMPROVEMENTS THAT MAY BE ENCOUNTERED THAT ARE UNKNOWN AT THIS TIME AND NOT SHOWN ON THESE PLANS. CONTRACTOR SHALL ARRANGE FOR OR PROVIDE, ALL GAS, TELECOMMUNICATIONS, CABLE, OVERHEAD AND UNDERGROUND POWER LINE, AND UTILITY POLE ADJUSTMENTS NEEDED. CONTRACTOR IS RESPONSIBLE FOR COORDINATING INSTALLATION OF FRANCHISE UTILITIES THAT ARE NECESSARY FOR ON-SITE AND OFF-SITE CONSTRUCTION, AND SERVICE TO THE PROPOSED DEVELOPMENT.
- 25. THE IMPLIED PRESENCE OR ABSENCE OF UTILITIES IS NOT TO BE CONSTRUED BY THE OWNER, ENGINEER, CONTRACTOR, OR SUBCONTRACTORS TO BE AN ACCURATE AND COMPLETE REPRESENTATION OF UTILITIES THAT MAY OR MAY NOT EXIST ON THE CONSTRUCTION SITE. BURIED AND ABOVE GROUND UTILITY LOCATION, IDENTIFICATION AND MARKING IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. REROUTING, DISCONNECTION, PROTECTION, ETC. OF ANY UTILITIES MUST BE COORDINATED BETWEEN THE CONTRACTOR, UTILITY COMPANY, AND OWNER. SITE SAFETY, INCLUDING THE AVOIDANCE OF HAZARDS ASSOCIATED WITH BURIED AND ABOVE GROUND UTILITIES, REMAINS THE SOLE RESPONSIBILITY OF THE THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS.
- 26. THE CONTRACTOR TO FIELD VERIFY LOCATION AND ELEVATION OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION.
- 27. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR ALL DAMAGES DUE TO THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ALL UTILITIES. THE OWNER OR ENGINEER WILL ASSUME NOT LIABILITY FOR ANY DAMAGES SUSTAINED OR COST INCURRED BECAUSE OF THE OPERATIONS IN THE VICINITY OF EXISTING UTILITIES OR STRUCTURES.
- 21. ALL SHOP DRAWINGS AND OTHER DOCUMENTS THAT REQUIRE ENGINEER REVIEW SHALL BE SUBMITTED BY THE CONTRACTOR SUFFICIENTLY IN ADVANCE OF CONSTRUCTION OF THAT ITEM, SO THAT NO LESS THAN 10 BUSINESS DAYS FOR REVIEW AND RESPONSE IS AVAILABLE.
- 22. ALL NECESSARY INSPECTIONS AND/OR CERTIFICATIONS REQUIRED BY CODES, JURISDICTIONAL AGENCIES, AND/OR UTILITY SERVICE COMPANIES SHALL BE PERFORMED PRIOR TO USE OF THE FACILITY AND THE FINAL CONNECTION OF SERVICES.
- 23. CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS.
- 24. CONTRACTOR'S BID PRICE SHALL INCLUDE ALL INSPECTION FEE.
- 25. ALL SYMBOLS SHOWN ON THESE PLANS ARE FOR PRESENTATION PURPOSES ONLY AND ARE NOT TO SCALE. CONTRACTOR SHALL COORDINATE FINAL SIZES AND LOCATIONS WITH APPROPRIATE CITY INSPECTOR.REFER TO ARCHITECTURAL AND STRUCTURAL PLANS FOR ALL FINAL BUILDING DIMENSIONS.
- 26. COMPLIANCE WITH COMMERCIAL AND MULTI-FAMILY RECYCLING ORDINANCE IS MANDATORY FOR MULTI-FAMILY COMPLEXES WITH 100 OR MORE UNITS AND BUSINESSES WITH 100 OR MORE EMPLOYEES.
- 27. CONTRACTOR PARKING AND LAYDOWN AREAS SHALL BE COORDINATED WITH THE OWNER.
- 27. CONTINACION FANNING AND LATDOWN AREAS SHALL BE COURDINATED WITH THE UWNER.
  28. THE CONTRACTOR SHALL PROVIDE ANY FINANCIAL SURETIES REQUIRED AS PART OF ANY PERMIT.
  29. CONTRACTOR SHALL BE RESPONSIBLE FOR PREPARING AND SUBMITTING ELECTRONIC AS—BUILT DRAWINGS FOR UTILITIES AND DETENTION AREAS TO THE OWNER AND ENGINEER FOR REVIEW AND APPROVAL PRIOR TO PROJECT ACCEPTANCE.
- 30. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS FOR ALL ITEMS INCORPORATED INTO THE WORK FOR ENGINEER REVIEW AND APPROVAL OF MINIMUM OF 4 WEEKS PRIOR TO ORDERING
- 31. REFERENCES TO "INSPECTION" OR "INSPECTOR" IN THE SPECIFICATIONS SHALL NOT CREATE, IMPOSE, OR GIVE RISE TO ANY DUTY OWED BY THE OWNER OR ENGINEER TO THE CONTRACTOR, ANY SUBCONTRACTOR, OR ANY SUPPLIER. ALL IMPROVEMENTS SHALL BE SUBJECT TO INSPECTION BY A DULY AUTHORIZED AND QUALIFIED OWNER'S REPRESENTATIVE BOTH DURING THE COURSE OF CONSTRUCTION AND AFTER CONSTRUCTION IS COMPLETE. THE INSPECTOR SHALL HAVE AUTHORITY OVER MATERIALS OF CONSTRUCTION, METHODS OF CONSTRUCTION, AND WORKMANSHIP, TO ENSURE COMPLIANCE WITH WORKING DRAWINGS AND SPECIFICATIONS. THE CONTRACTOR SHALL PROVIDE FOR REASONABLE TESTS AND PROOF OF QUALITY OF MATERIALS AS REQUESTED BY THE INSPECTOR. UPON DUE CAUSE, WHICH SHALL INCLUDE WEATHER CONDITION, WORKMANSHIP OR NON-ADHERENCE TO THE APPROVED PLANS AND SPECIFICATIONS, THE INSPECTOR SHALL HAVE THE AUTHORITY TO STOP CONSTRUCTION.
- 32. WHERE SECTION, SUB—SECTION, SUBDIVISION, OR PROPERTY MONUMENTS ARE ENCOUNTERED, THE OWNER'S REPRESENTATIVE SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND PRESERVE ALL PROPERTY MARKERS UNTIL AN OWNER OR AUTHORIZED SURVEYOR HAS WITNESSED OR REFERENCED THEIR LOCATION.
- 33. CONTRACTOR SHALL NOTIFY THE APPROPRIATE AGENCY A MINIMUM OF 48 HOURS PRIOR TO CONNECTING TO OR INSTALLING ANY PUBLIC SEWER OR WATER MAINS.

GENERAL NOTES (1 OF 4)

SHEET 2 OF 10

P.E.C. LIBERTY HILL EAPP


NICHOLAS R. SANDLIN

124404

CENSED IN

**EXCELL FUELING SYSTEMS** 





#### <u>TEXAS COMMISSION ON ENVIRONMENTAL QUALITY CON</u>TRIBUTING ZONE PLAN GENERAL CONSTRUCTION NOTES

- A WRITTEN NOTICE OF CONSTRUCTION MUST BE SUBMITTED TO THE TCEQ REGIONAL OFFICE AT LEAST 48 HOURS PRIOR TO THE START OF ANY GROUND DISTURBANCE OR CONSTRUCTION ACTIVITIES. THIS NOTICE MUST INCLUDE:
  - THE NAME OF THE APPROVED PROJECT;
  - THE ACTIVITY START DATE; AND
  - THE CONTACT INFORMATION OF THE PRIME CONTRACTOR.
- 2. ALL CONTRACTORS CONDUCTING REGULATED ACTIVITIES ASSOCIATED WITH THIS PROJECT SHOULD BE PROVIDED WITH COMPLETE COPIES OF THE APPROVED CONTRIBUTING ZONE PLAN (CZP) AND THE TCEO LETTER INDICATING THE SPECIFIC CONDITIONS OF ITS APPROVAL. DURING THE COURSE OF THESE REGULATED ACTIVITIES, THE CONTRACTOR(S) SHOULD KEEP COPIES OF THE APPROVED PLAN AND APPROVAL LETTER ONSITE.
- NO HAZARDOUS SUBSTANCE STORAGE TANK SHALL BE INSTALLED WITHIN 150 FEET OF A WATER SUPPLY SOURCE, DISTRIBUTION SYSTEM, WELL, OR SENSITIVE FEATURE.
- PRIOR TO BEGINNING ANY CONSTRUCTION ACTIVITY, ALL TEMPORARY EROSION AND SEDIMENTATION (E&S) CONTROL MEASURES MUST BE PROPERLY INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE MANUFACTURERS SPECIFICATIONS. IF INSPECTIONS INDICATE A CONTROL HAS BEEN USED INAPPROPRIATELY, OR INCORRECTLY, THE APPLICANT MUST REPLACE OR MODIFY THE CONTROL FOR SITE SITUATIONS. THESE CONTROLS MUST REMAIN IN PLACE UNTIL THE DISTURBED AREAS HAVE BEEN PERMANENTLY STABILIZED.
- ANY SEDIMENT THAT ESCAPES THE CONSTRUCTION SITE MUST BE COLLECTED AND PROPERLY DISPOSED OF BEFORE THE NEXT RAIN EVENT TO ENSURE IT IS NOT WASHED INTO SURFACE STREAMS, SENSITIVE FEATURES, ETC.
- SEDIMENT MUST BE REMOVED FROM THE SEDIMENT TRAPS OR SEDIMENTATION BASINS WHEN IT OCCUPIES 50% OF THE BASIN'S DESIGN CAPACITY.
- LITTER, CONSTRUCTION DEBRIS, AND CONSTRUCTION CHEMICALS EXPOSED TO STORMWATER SHALL BE PREVENTED FROM BEING DISCHARGED OFFSITE.
- ALL EXCAVATED MATERIAL THAT WILL BE STORED ON-SITE MUST HAVE PROPER E&S CONTROLS.
- IF PORTIONS OF THE SITE WILL HAVE A CEASE IN CONSTRUCTION ACTIVITY LASTING LONGER THAN 14 DAYS, SOIL STABILIZATION IN THOSE AREAS SHALL BE INITIATED AS SOON AS POSSIBLE PRIOR TO THE 14TH DAY OF INACTIVITY. IF ACTIVITY WILL RESUME PRIOR TO THE 21ST DAY. STABILIZATION MEASURES ARE NOT REQUIRED. IF DROUGHT CONDITIONS OR INCLEMENT WEATHER PREVENT ACTION BY THE 14TH DAY, STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS POSSIBLE.
- 10. THE FOLLOWING RECORDS SHOULD BE MAINTAINED AND MADE AVAILABLE TO THE TCEQ UPON REQUEST:
  - THE DATES WHEN MAJOR GRADING ACTIVITIES OCCUR:
- THE DATES WHEN CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE ON A PORTION OF THE SITE; AND
  - THE DATES WHEN STABILIZATION MEASURES ARE INITIATED.
- 11. THE HOLDER OF ANY APPROVED CZP MUST NOTIFY THE APPROPRIATE REGIONAL OFFICE IN WRITING AND OBTAIN APPROVAL FROM THE EXECUTIVE DIRECTOR PRIOR TO INITIATING ANY OF THE FOLLOWING:
  - A. ANY PHYSICAL OR OPERATIONAL MODIFICATION OF ANY BEST MANAGEMENT PRACTICES (BMPS) OR STRUCTURE(S), INCLUDING BUT NOT LIMITED TO TEMPORARY OR PERMANENT PONDS, DAMS, BERMS. SILT FENCES, AND DIVERSIONARY STRUCTURES;
  - B. ANY CHANGE IN THE NATURE OR CHARACTER OF THE REGULATED ACTIVITY FROM THAT WHICH WAS ORIGINALLY APPROVED;
  - C. ANY CHANGE THAT WOULD SIGNIFICANTLY IMPACT THE ABILITY TO PREVENT POLLUTION OF THE EDWARDS AQUIFER; OR
- D. ANY DEVELOPMENT OF LAND PREVIOUSLY IDENTIFIED AS UNDEVELOPED IN THE APPROVED CONTRIBUTING ZONE PLAN.

AUSTIN REGIONAL OFFICE 12100 PARK 35 CIRCLE, BUILDING A AUSTIN, TEXAS 78753-1808 PHONE (512) 339-2929 FAX (512) 339-3795

SAN ANTONIO REGIONAL OFFICE 14250 JUDSON ROAD SAN ANTONIO, TEXAS 78233-4480 PHONE (210) 490-3096 FAX (210) 545-4329

REVISION RECORD

NOTICE: ALTERATION OF A SEALED DRAWING WITHOUT PROPER NOTIFICATION TO THE ENGINEER OF RECORD IS A VIOLATION OF THE TEXAS ENGINEERING PRACTICES ACT

- 1. CONTRACTOR SHALL USE ALL NECESSARY SAFETY PRECAUTIONS TO AVOID CONTACT WITH OVERHEAD AND UNDERGROUND POWER LINES. CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE LOCAL, STATE, FEDERAL, AND UTILITY OWNER REGULATIONS PERTAINING TO WORK SETBACKS FROM POWER LINES.
- 2. ESTABLISH FIRE ZONES AS SHOWN ON SITE BY PAINTING CURB RED. STENCIL THE WORDS, "FIRE ZONE/TOW-AWAY ZONE", IN WHITE LETTERS AT LEAST 3 INCHES HIGH AT 35-FOOT INTERVALS ALONG THE CURB. ALSO, SIGNS SHALL BE POSTED AT BOTH ENDS OF A FIRE ZONE. ALTERNATE MARKING OF THE FIRE LANES MY BE APPROVED BY THE FIRE CHIEF PROVIDED THE FIRE LANES ARE CLEARLY IDENTIFIED AT BOTH ENDS AND AT INTERVALS NOT TO
- 3. WARNING ARE REQUIRED TO BE PLACED UNDER THE OVERHEAD ELECTRIC LINES TO MAKE ALL PERSONNEL AWARE OF THE ELECTRIC HAZARD.
- 4. ALL FDC'S TO BE TWO 2  $\frac{1}{2}$  INCH SIAMESE CONNECTIONS. 5. THE CONTRACTOR SHALL FURNISH, ERECT, AND MAINTAIN MARKINGS AND ASSOCIATED HAZARD WARNING LIGHTS, DELINEATOR FENCE, AND OTHER ASSOCIATED FACILITIES AS REQUIRED FOR OPEN TRENCHES, EXCAVATIONS, TEMPORARY STOCK PILES, AND PARKED CONSTRUCTION EQUIPMENT THAT MAY POSE A POTENTIAL HAZARD AS PART OF THE DAILY OPERATIONS AT THIS SITE. CONTRACTOR IS SOLELY RESPONSIBLE FOR SITE SAFETY.


CONSTRUCTION MEANS, METHODS, & SAFETY PROTECTION NOTES: THE CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLIANCE WITH ALL FEDERAL, STATE, AND LOCAL LAWS, INCLUDING OSHA STANDARDS AND WITH ANY OTHER APPLICABLE LAWS, ORDINANCES, RULES, REGULATIONS AND ORDERS OF ANY PUBLIC BODY HAVING JURISDICTION FOR THE SAFETY OF PERSONS OR PROPERTY OR TO PROTECT THEM FROM DAMAGE, INJURY OR LOSS. THE CONTRACTOR SHALL PROVIDE ALL SAFEGUARDS, SAFETY DEVICES, AND PROTECTIVE EQUIPMENT AND SHALL BE RESPONSIBLE FOR INITIATING. MAINTAINING, AND SUPERVISING ALL SAFETY PRECAUTIONS AND PROGRAMS UTILIZED BY THE CONTRACTOR AND HIS SUB-CONTRACTORS IN THE PERFORMANCE OF THEIR WORK AND SHALL TAKE ANY OTHER ACTIONS NECESSARY TO PROTECT THE LIFE AND HEALTH OF EMPLOYEES ON THE JOB AND THE SAFETY OF THE PUBLIC AND TO PROTECT PROPERTY IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES OR PROCEDURES, EQUIPMENT, AND FOR SAFETY PRECAUTIONS OR PROGRAMS, UNLESS SUCH MEANS AND EQUIPMENT ARE SPECIFIED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL COMPLY WITH SECTION 108.06 LABOR, METHODS, AND EQUIPMENT OF THE "STANDARD

#### STORM WATER DISCHARGE AUTHORIZATION

SPECIFICATIONS".

THE CONTRACTOR AND WHERE APPLICABLE SUBCONTRACTORS ARE RESPONSIBLE FOR:

- COMPLIANCE WITH ALL TCEQ AND EPA STORM WATER POLLUTION PREVENTION 1. REQUIREMENTS.
- 2. ENSURING THAT ALL PRIMARY OPERATORS SUBMIT A NOI TO TCEQ AT LEAST 7 DAYS PRIOR CONSTRUCTION. AND THEY PROVIDE A COPY OF ALL SIGNED NOI'S TO THE OPERATOR OF ANY MS4 RECEIVING DISCHARGE FROM THE SITE.
- 3. IMPLEMENTATION OF THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP), IF IT APPLIES, IE. POST SITE NOTICE, INSPECTIONS. DOCUMENTATION AND SUBMISSION OF ANY INFORMATION, SUCH AS NOI, REQUIRED BY TCEQ AND EPA.
- 4. SIGNING THE REQUIRED CERTIFICATION STATEMENT ACKNOWLEDGING THEIR RESPONSIBILITIES AS STATED IN THE SWPPP IF PROVIDING SERVICES RELATED TO SWPPP.
- SUBMITTING TO THE CITY, AND RETAINING ON SITE DURING CONSTRUCTION, A COPY OF THE SWPPP INCLUDING NOI, SITE NOTICE, CONTRACTOR CERTIFICATION. AND ANY REVISIONS.
- PRIMARY OPERATOR IS RESPONSIBLE FOR SUBMITTING A NOTICE OF TERMINATION (NOT) TO TCEQ WITH 30 DAYS AFTER ALL SOIL DISTURBING ACTIVITIES HAVE BÉEN COMPLETED AND A VEGETATIVE COVER HAS BEEN ESTABLISHED ON ALL UNPAVED AREA AND ALL AREAS NOT COVERED BY STRUCTURES, A TRANSFER OF OPERATIONAL CONTROL HAS OCCURRED, OR THE OPERATOR HAS AN ALTERNATIVE AUTHORIZATION UNDER A DIFFERENT PERMIT. A COPY OF THE NOT SHALL BE PROVIDED TO THE OPERATOR OF ANY MS4 RECEIVING DISCHARGE FROM THE SITE.



#### PRE-CONSTRUCTION NOTES:

- 1. PRIOR TO SCHEDULING THE PRE-CONSTRUCTION MEETING ENSURE THAT ALL REQUIRED NOTICES AND PERMITS ARE POSTED AND THE CERTIFIED INSPECTOR FOR YOUR SITE HAS UPLOADED A SWP3 INSPECTION REPORT TO YOUR ACCOUNT THAT CONFIRMS THAT THE FIRST PHASE OF TEMPORARY ESC HAVE BEEN INSTALLED PER PLANS AND SPECIFICATIONS.
- 2. FAILURE TO FOLLOW THE PRE-CONSTRUCTION MEETING REQUIREMENTS MAY RESULT IN WORK STOPPAGE AND ADDITIONAL PERMIT FEES.
- 3. PROVIDE 48 HR. MINIMUM NOTICE TO SCHEDULE THE PRE-CONSTRUCTION MEETING.
- 4. PROVIDE A 1/2 SIZE SET OF PLANS FOR THE INSPECTOR AT THE PRE-CONSTRUCTION.
- 5. PROVIDE AN ANTICIPATED CONSTRUCTION SCHEDULE AT THE PRE-CONSTRUCTION.
- 6. BRING YOUR SWP3 FOR COMPLETENESS CHECK AT THE PRE-CONSTRUCTION.
- 7. ALL DEVELOPMENT SHALL BE IN ACCORDANCE WITH THE PLANS APPROVED BY TRAVIS COUNTY.
- 8. SCHEDULE YOUR PROJECTS PRE-CONSTRUCTION MEETING THROUGH THE MYPERMITNOW.ORG ACCOUNT AFTER THE INITIAL 3RD PARTY SWP3 INSPECTION REPORT HAS BEEN UPLOADED AND ALL PERMITS AND NOTICES HAVE BEEN POSTED, THEN FOLLOW UP WITH EMAILS TO THE ENVIRONMENTAL INSPECTOR AT ENV-INSPECTION@TRAVISCOUNTYTX.GOV

GENERAL NOTES (2 OF 4)

SHEET 3 OF 10

P.E.C. LIBERTY HILL EAPP

**EXCELL FUELING SYSTEMS** 



#### **ACCESSIBLE PARKING NOTE:**

- 1. BEFORE PLACING PAVEMENT, CONTRACTOR SHALL VERIFY THAT SUITABLE HANDICAPPED ROUTES (PER ADA) EXIST TO AND FROM DESIGNATED DOORS. IN NO CASE SHALL HANDICAP RAMP SLOPES EXCEED 1 VERTICAL TO 12 HORIZONTAL. IN NO CASE SHALL SIDEWALK CROSS SLOPES EXCEED 2.0 PERCENT. IN NO CASE SHALL LONGITUDINAL SIDEWALK SLOPES EXCEED 5.0 PERCENT. CONTRACTOR SHALL CONTACT ENGINEER PRIOR TO PAVING IF ANY EXCESSIVE SLOPES ARE ENCOUNTERED. NO CONTRACTOR CHANGE ORDERS WILL BE ACCEPTED FOR ADA COMPLIANCE ISSUES.
- ALL ACCESSIBLE SPACES AND ACCESSIBLE ROUTES SHALL COMPLY WITH THE TEXAS ACCESSIBILITY STANDARDS (TAS) AND THE CITY REQUIREMENTS.
- PARKING SPACES AND ACCESS AISLES SHALL BE LEVEL WITH SURFACE SLOPES NOT EXCEEDING 1:50 (2%) IN ALL DIRECTIONS. CURB RAMPS COMPLYING WITH TAS SHALL BE PROVIDED AT ALL PASSENGER LOADING ZONES.
- EACH ACCESSIBLE PARKING SPACE SHALL BE DESIGNATED AS RESERVED BY A VERTICALLY MOUNTED OR SUSPENDED SIGN SHOWING THE SYMBOL OF ACCESSIBILITY PER TAS. SPACES COMPLYING WITH TAS SHALL HAVE AN ADDITIONAL SIGN "VAN ACCESSIBLE" MOUNTED BELOW THE SYMBOL OF ACCESSIBILITY WHEN REQUIRED.
- (A) CHARACTERS AND SYMBOLS ON SUCH SIGNS SHALL BE LOCATED 60" MINIMUM ABOVE THE GROUND, FLOOR, OR PAVING SURFACE SO THEY CANNOT BE OBSCURED BY A VEHICLE PARKED IN THE SPACE.
- (B) SIGNS LOCATED WITHIN AN ACCESSIBLE ROUTE SHALL COMPLY WITH TAS.
- (C) CHARACTERS AND SYMBOLS ON OVERHEAD SIGNS SHALL COMPLY WITH TAS.
- 5. SLOPES OF CURB RAMPS SHALL COMPLY WITH TAS. TRANSITIONS FROM RAMPS TO WALKS, GUTTERS, OR STREETS SHALL BE FLUSH AND FREE OF ABRUPT CHANGES. MAXIMUM SLOPES OF ADJOINING GUTTERS, ROAD SURFACE IMMEDIATELY ADJACENT TO THE CURB RAMP, OR ACCESSIBLE ROUTE SHALL NOT EXCEED 1:20.
- SURFACES OF CURB RAMPS SHALL COMPLY WITH TAS.
- (A) TEXTURES SHALL CONSIST OF EXPOSED CRUSHED STONE AGGREGATE, ROUGHENED CONCRETE, RUBBER, RAISED ABRASIVE STRIPS, OR GROOVES EXTENDING THE FULL WIDTH AND DEPTH OF THE CURB RAMP. SURFACES THAT ARE RAISED, ETCHED, OR GROOVED IN A WAY THAT WOULD ALLOW WATER TO ACCUMULATE ARE PROHIBITED.
- (B) FOR PURPOSES OF WARNING, THE FULL WIDTH AND DEPTH OF CURB RAMPS SHALL HAVE A LIGHT REFLECTIVE VALUE AND TEXTURE THAT SIGNIFICANTLY CONTRASTS WITH THAT OF ADJOINING PEDESTRIAN ROUTES.
- EVERY HANDICAP ACCESSIBLE PARKING SPACE SHALL BE IDENTIFIED BY A SIGN CENTERED 5 FEET ABOVE THE PARKING SURFACE, AT THE HEAD OF THE PARKING SPACE. THE SIGN MUST INCLUDE THE INTERNATIONAL SYMBOL OF ACCESSIBILITY. SUCH SIGNS SHALL NOT BE OBSCURED BY A VEHICLE PARKED THE SPACE AND SHALL MEET THE CRITERIA SET FORTH IN
- SLOPES ON ACCESSIBLE ROUTES MAY NOT EXCEED 1:20 UNLESS DESIGNED AS A RAMP
- THE MAXIMUM SLOPE OF A RAMP IN NEW CONSTRUCTION IS 1:12. THE MAXIMUM RISE FOR ANY RAMP RUN IS 30 IN.
- 10. ACCESSIBLE ROUTES MUST HAVE A CROSS-SLOPE NO GREATER THAN 1:30.
- 11. GROUND SURFACES ALONG ACCESSIBLE ROUTES MUST BE STABLE, FIRM, AND SLIP RESISTANT.

#### TRAFFIC CONTROL NOTES:

- 1. ALL SIGNS, PAVEMENT MARKINGS, AND OTHER TRAFFIC CONTROL DEVICES SHALL CONFORM TO THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES".
- 2. ALL FIRE DEPARTMENT ACCESS DRIVES/ROADS TO HAVE A MINIMUM 14' VERTICAL CLEARANCE.
- 3. ALL PARKING SPACES SHALL HAVE A MINIMUM 7'-0" VERTICAL CLEARANCE.
- ALL LANDSCAPED AREAS ARE TO BE PROTECTED BY SIX-INCH WHEEL CURBS, WHEELSTOPS, OR OTHER APPROVED BARRIERS AS PER ECM.
- ADEQUATE BARRIERS BETWEEN ALL VEHICULAR USE AREAS AND ADJACENT LANDSCAPE AREAS, SUCH AS A 6" CONCRETE CURB ARE REQUIRED. IF A STANDARD 6' CURB AND GUTTER ARE NOT PROVIDED FOR ALL VEHICULAR USE AREAS AND ADJACENT LANDSCAPE AREAS, COMPLY
- EACH COMPACT PARKING SPACE/AISLE WILL BE SIGNED "SMALL CAR ONLY".
- 7. PRIOR TO PERFORMING ANY WORK IN OR ON THE RIGHT OF WAY OF ANY CITY OR STATE ROADWAY, THE CONTRACTOR SHALL NOTIFY THE CITY/STATE TRAFFIC ENGINEER'S OFFICE. THE CONTRACTOR SHALL ERECT WARNING SIGNS AND BARRICADES TO PROTECT THE TRAVELING PUBLIC. THE SIGNING AND BARRICADING SHALL CONFORM TO THE APPROPRIATE APPLICATIONS OUTLINED IN THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES OR AS OTHERWISE DIRECTED BY THE CITY/STATE TRAFFIC ENGINEER. IF PERMITS ARE REQUIRED TO CONDUCT THE WORK, THE CONTRACTOR SHALL SECURE THE PERMITS AND SUPPLY THEM TO THE OWNER AT NO ADDITIONAL COST. ALL FULL WIDTH LANE CLOSURES, PARTIAL LANE CLOSURES, OR CONSTRUCTION ADJACENT TO PAVEMENT, SHALL BE IDENTIFIED, SIGNED, AND BARRICADES ERECTED IN CONFORMANCE WITH THE APPLICABLE ARTICLES OF THE STANDARD SPECIFICATIONS AND THE MUNICIPALITY'S REQUIREMENTS. ALL TRAFFIC PROTECTION, BOTH ONSITE AND OFFSITE SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.

#### REVISION RECORD

#### **EARTHWORK NOTES AND REQUIREMENTS:**


- CONTRACTOR IS RESPONSIBLE FOR ALL MATERIALS TESTING AND CERTIFICATION, UNLESS SPECIFIED OTHERWISE BY OWNER. ALL MATERIALS TESTING SHALL BE COORDINATED WITH THE APPROPRIATE CITY INSPECTOR AND COMPLY WITH CITY STANDARD SPECIFICATIONS AND GEOTECHNICAL REPORT. TESTING SHALL BE PERFORMED BY AN APPROVED INDEPENDENT AGENCY FOR TESTING MATERIALS. OWNER SHALL APPROVE THE AGENCY NOMINATED BY THE CONTRACTOR FOR MATERIALS TESTING.
- ALL COPIES OF MATERIALS TEST RESULTS SHALL BE SENT TO THE OWNER. ENGINEER AND ARCHITECT DIRECTLY FROM THE TESTING AGENCY.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO SHOW, BY THE STANDARD TESTING PROCEDURES OF THE MATERIALS, THAT THE WORK CONSTRUCTED MEETS THE PROJECT REQUIREMENTS AND CITY SPECIFICATIONS.
- DUE TO THE POTENTIAL FOR DIFFERENTIAL SOIL MOVEMENT ADJACENT TO THE BUILDING, THE CONTRACTOR SHALL ADHERE TO THE GEOTECHNICAL REPORT'S RECOMMENDATION FOR SUBGRADE PREPARATION SPECIFIC TO FLATWORK ADJACENT TO THE BUILDING. THE OWNER AND CONTRACTOR ARE ADVISED TO OBTAIN A GEOTECHNICAL ENGINEER RECOMMENDATION SPECIFIC TO FLATWORK ADJACENT TO THE BUILDING, IF NONE IS CURRENTLY EXISTING.
- THE CONTRACTOR SHALL COMPLY WITH ALL LOCAL, STATE, AND FEDERAL EROSION CONTROL AND WATER QUALITY REQUIREMENTS.
- A RETAINING WALL OVER 4 FEET IN HEIGHT MEASURED FROM THE BOTTOM OF THE FOOTING TO THE TOP OF THE WALL SHALL BE ENGINEERED AND REQUIRE A SEPARATE BUILDING PERMIT.
- 7. CONTRACTOR SHALL REMOVE EARTHEN MATERIAL, EXISTING SURFACES, AND STRUCTURES AS REQUIRED. ALL WASTE MATERIAL SHALL BE PROPERLY DISPOSED OFF-SITE AND SHALL BE INCIDENTAL TO THE CONTRACT.
- ALL AGGREGATE BASE COURSE SHALL BE COMPACTED TO 95% STANDARD PROCTOR DENSITY MAXIMUM DRY DENSITY WITHIN 2 PERCENT OF OPTIMUM MOISTURE CONTENT.

#### **TRENCH EXCAVATION NOTES:**

- 1. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING AND SUBMITTING A TRENCH SAFETY PLAN, PREPARED BY A PROFESSIONAL ENGINEER IN THE STATE OF TEXAS, TO THE CITY PRIOR TO CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING TRENCH SAFETY REQUIREMENTS IN ACCORDANCE WITH CITY, STATE, AND FEDERAL REQUIREMENTS, INCLUDING OSHA, FOR ALL TRENCHES. THE CONTRACTOR SHALL KEEP TRENCHES FREE FROM WATER.
- CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN / GEOTECHNICAL / SAFETY / EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS, AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS, AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.
- BRACING OF UTILITY POLES MAY BE REQUIRED WHEN TRENCHING OR EXCAVATING IN CLOSE PROXIMITY TO THE POLES AND IS THE RESPONSIBILITY OF THE CONTRACTOR.
- ALL TRENCH BACKFILL SHALL BE IMPORTED GRANULAR MATERIAL UNLESS EXISTING GRANULAR MATERIALS ARE SPECIFICALLY APPROVED BY THE OWNER'S REPRESENTATIVE.

#### INDEMNIFICATION

THE CONTRACTOR SHALL INDEMNIFY AND HOLD HARMLESS THE OWNER, THE CITY, AND SANDLIN SERVICES, LLC. FROM AND AGAINST ALL CLAIMS, DAMAGES, LOSSES AND EXPENSES INCLUDING ATTORNEY'S FEES ARISING OUT OF OR RESULTING FROM THE PERFORMANCE OF THE CONTRACTOR'S WORK. IN ANY AND ALL CLAIMS AGAINST THE OWNER OR SANDLIN SERVICES, LLC. BY ANY EMPLOYEE OF THE CONTRACTOR OR ANYONE DIRECTLY OR INDIRECTLY EMPLOYED BY THE CONTRACTOR OR ANYONE FOR WHOSE ACTS THE CONTRACTOR MAY LIABLE, THE INDEMNIFICATION OBLIGATION SHALL NOT BE LIMITED IN ANY WAY BY ANY LIMITATION ON THE AMOUNT OF DAMAGES, COMPENSATION. OR BENEFITS PAYABLE BY OR FOR THE CONTRACTOR UNDER WORKER'S COMPENSATION ACTS. DISABILITY BENEFIT ACTS OR OTHER EMPLOYEE BENEFIT ACTS.



GENERAL NOTES (3 OF 4)

SHEET 4 OF 10

P.E.C. LIBERTY HILL EAPP


**EXCELL FUELING SYSTEMS** 



### **BUILDING COORDINATION & CONSTRUCTION NOTES:**

- 1. THE SCOPE OF WORK FOR THE CIVIL IMPROVEMENTS SHOWN ON THESE PLANS TERMINATES 5—FEET FROM THE BUILDING. REFERENCE THE BUILDING PLANS (E.G. ARCHITECTURAL, STRUCTURAL, MEP) FOR AREAS WITH 5—FEET OF THE BUILDING AND WITHIN THE BUILDING FOOTPRINT
- 2. REFER TO ARCHITECTURAL AND STRUCTURAL PLANS FOR ALL FINAL BUILDING DIMENSIONS.
- 3. THE PROPOSED BUILDING FOOTPRINT(S) SHOWN IN THESE PLANS WAS PROVIDED TO SANDLIN SERVICES, LLC. BY THE PROJECT ARCHITECT AT THE TIME THESE PLANS WERE PREPARED. IT MAY NOT BE THE FINAL CORRECT VERSION BECAUSE THE BUILDING DESIGN ONGOING. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR CONFIRMING THE FINAL CORRECT VERSION OF THE BUILDING FOOTPRINT WITH THE ARCHITECT AND STRUCTURAL ENGINEER PRIOR TO LAYOUT. DIMENSIONS AND/OR COORDINATES SHOWN ON THESE PLANS WERE BASED ON THE ABOVE STATED ARCHITECTURAL FOOTPRINT, AND ARE THEREFORE A PRELIMINARY LOCATION OF THE BUILDING. THE CONTRACTOR IS SOLELY RESPONSIBLE TO VERIFY WHAT PART OF THE BUILDING THE ARCHITECT'S FOOTPRINT REPRESENTS (E.G. SLAB, OUTSIDE WALL, MASONRY LEDGE, ETC....) AND TO CONFIRM ITS FINAL POSITION ON THE SITE BASED ON THE FINAL ARCHITECTURAL FOOTPRINT, CIVIL DIMENSION CONTROL PLAN, SURVEY BOUNDARY AND/OR PLAT. ANY DIFFERENCES FOUND SHALL BE REPORTED TO SANDLIN SERVICES, LLC. IMMEDIATELY.
- 4. ALL CONSTRUCTION AND MATERIALS SHALL BE IN ACCORDANCE WITH THESE PLANS, LOCAL JURISDICTION STANDARD DETAILS AND SPECIFICATIONS, THE FINAL GEOTECHNICAL REPORT, AND ALL ISSUED ADDENDA, AND COMMONLY ACCEPTED CONSTRUCTION STANDARDS. THE CITY SPECIFICATIONS SHALL GOVERN WHERE OTHER SPECIFICATIONS DO NOT EXIST. IN CASE OF CONFLICTING SPECIFICATIONS OR DETAILS, THE MORE SPECIFICATION AND DETAILS SHALL BE FOLLOWED.
- 5. THE CONTRACTOR SHALL FURNISH ALL MATERIAL AND LABOR TO CONSTRUCT THE FACILITY AS SHOWN AND DESCRIBED IN THE CONSTRUCTION DOCUMENTS IN ACCORDANCE WITH ALL APPROPRIATE AUTHORITIES' SPECIFICATIONS AND REQUIREMENTS.
- 6. THE EXISTING CONDITIONS SHOWN ON THESE PLANS WERE PROVIDED BY THE TOPOGRAPHIC SURVEY PREPARED BY THE PROJECT SURVEYOR, AND ARE BASED ON THE BENCHMARKS SHOWN. THE CONTRACTOR SHALL REFERENCE THE SAME BENCHMARKS. THE CONTRACTOR SHALL REVIEW AND VERIFY THE EXISTING TOPOGRAPHIC SURVEY SHOWN ON THE PLANS REPRESENTS THE EXISTING FIELD CONDITIONS PRIOR TO CONSTRUCTION, AND SHALL REPORT ANY DISCREPANCIES FOUND TO THE OWNER AND ENGINEER IMMEDIATELY.
- 7. ALL CONSTRUCTION SURVEYING AND STAKING SHALL BE PROVIDED BY THE GENERAL CONTRACTOR.
- 8. CONTRACTOR SHALL VERIFY HORIZONTAL AND VERTICAL CONTROL, INCLUDING BENCHMARKS, PRIOR TO COMMENCING CONSTRUCTION OR STAKING OF IMPROVEMENTS.
- 9. PRIOR TO COMMENCEMENT OF CONSTRUCTION, THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS AFFECTING THEIR WORK WITH THE ACTUAL CONDITION AT THE PROJECT SITE. IN ADDITION, THE CONTRACTOR MUST VERIFY THE ENGINEER'S LINE AND GRADE STAKES. IF THERE ARE ANY DISCREPANCIES FROM WHAT IS SHOWN ON THE CONSTRUCTION PLANS, THE CONTRACTOR MUST IMMEDIATELY PROVIDE THE INFORMATION TO THE ENGINEER BEFORE DOING ANY WORK, OTHERWISE, THE CONTRACTOR ASSUMES FULL RESPONSIBILITY. IN THE EVENT OF A DISAGREEMENT BETWEEN THE CONSTRUCTION PLANS, STANDARD SPECIFICATIONS, AND/OR DETAILS. THE CONTRACTOR SHALL SECURE WRITTEN INSTRUCTIONS FROM THE ENGINEER PRIOR TO PROCEEDING WITH ANY PART OF THE WORK AFFECTED BY OMISSIONS OR DISCREPANCIES. IF THE CONTRACTOR FAILS TO SECURE WRITTEN INSTRUCTIONS FROM THE ENGINEER, THE CONTRACTOR WILL BE CONSIDERED TO HAVE PROCEEDED AT THEIR OWN RISK AND EXPENSE. IN THE EVENT OF ANY DOUBT OR QUESTION ARISING WITH RESPECT TO SPECIFICATIONS, THE DECISION OF THE ENGINEER SHALL BE FINAL.
- 10. THE CONTRACTOR SHALL REVIEW ALL DIMENSIONS, ELEVATIONS, AND FIELD CONDITIONS THAT MAY AFFECT CONSTRUCTION. ANY DISCREPANCIES ON THE DRAWINGS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT AND ENGINEER IMMEDIATELY.
- 11. NO FIELD CHANGES OR DEVIATION FROM DESIGN ARE TO BE MADE WITHOUT PRIOR APPROVAL OF THE ARCHITECT, ENGINEER, OWNER, AND IF APPLICABLE THE CITY,
- 12. THE CONTRACTOR SHALL THOROUGHLY CHECK COORDINATION OF CIVIL, LANDSCAPE, MEP, ARCHITECTURAL, AND OTHER PLANS, PRIOR TO COMMENCING CONSTRUCTION AND NOTIFY OWNER/ENGINEER OF ANY DISCREPANCY PRIOR TO COMMENCING WITH CONSTRUCTION.
- 13. THE CONTRACTOR SHALL BE RESPONSIBLE TO OBTAIN ALL REQUIRED CONSTRUCTION PERMITS, APPROVALS, AND BONDS PRIOR TO CONSTRUCTION.
- 14. THE CONTRACTOR SHALL HAVE AVAILABLE AT THE JOB SITE AT ALL TIMES A COPY OF THE CONTRACT DOCUMENTS INCLUDING PLANS, GEOTECHNICAL REPORT AND ADDENDA, PROJECT AND CITY SPECIFICATIONS, AND SPECIAL CONDITIONS, COPIES OF ANY REQUIRED CONSTRUCTION PERMITS, EROSION CONTROL PLANS, SWPPP, AND INSPECTION REPORTS.
- 15. THE CONTRACTOR SHALL KEEP A NEAT AND ACCURATE RECORD OF CONSTRUCTION, INCLUDING ANY DEVIATIONS OR VARIANCES FROM THE PLANS.
- 16. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING AS-BUILT PLANS TO THE ENGINEER AND CITY IDENTIFYING ALL DEVIATIONS AND VARIATIONS FROM THESE PLANS MADE DURING CONSTRUCTION.
- 17. THE CONTRACTOR TO COORDINATE WITH PROJECT ARBORIST TO TRIM TREES TO ENSURE VISIBILITY NEAR PARKING AREAS.
- 18. ALL DIMENSIONS ARE TO FACE OF CURB UNLESS OTHERWISE NOTED.
- 19. ALL RADII TO BE 2' UNLESS OTHERWISE NOTED.
- 20. ALL ON-SITE UTILITIES SHALL BE LOCATED UNDERGROUND UNLESS REQUIRED BY THE UTILITY TO BE OTHERWISE LOCATED.
- 21. SIDEWALKS CITY PARK ROAD ARE REQUIRED TO BE CONSTRUCTED BY THE PROPERTY OWNER AFTER THE ABUTTING ROADWAY IS IMPROVED AND CONCRETE CURBS ARE IN PLACE.
- 22. WHEN CONCRETE IS PLACED ABUTTING STRUCTURES, FOUNDATIONS OR EXISTING SIDEWALKS, A BOND BREAKER CONSISTING OF 1" PJF AND ELASTOMERIC SEALANT SHALL BE USED FULL DEPTH UNTIL OTHERWISE NOTED.
- 23. SIDEWALK RAMPS FOR ADA SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.
- 24. CONSTRUCTION STAKING, LAYOUT, AND GRADING SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR USING THE BASIC TOPOGRAPHIC SURVEY CONTROLS. CONTRACTOR SHALL VERIFY SURVEY CONTROLS PRIOR TO BEGINNING CONSTRUCTION. ANY DISCREPANCIES IN THE SURVEY CONTROLS SHALL BE REPORTED TO THE OWNER AND ENGINEER PRIOR TO CONSTRUCTION. ANY ADDITIONAL SURVEY CONTROLS REQUIRED FOR CONSTRUCTION SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 25. ANY SIDEWALKS, FENCES, AND OTHER ITEMS NOT SHOWN TO BE REMOVED, BUT DAMAGED DURING CONSTRUCTION, SHALL BE REPAIRED BY THE CONTRACTOR AT NO COST TO THE OWNER.

REVISION RECORD




GENERAL NOTES (4 OF 4)

SHEET 5 OF 10

P.E.C. LIBERTY HILL EAPP

EXCELL FUELING SYSTEMS





NICHOLAS R. SANDLIN 124404 Vicensed

FINAL PLAT (1 OF 2)

SHEET 6 OF 10

P.E.C. LIBERTY HILL EAPP

EXCELL FUELING SYSTEMS

SANDLIN SERVICES, LLC

TBPELS FIRM #21356 9111 JOLLVILLE RD., STE. 212 AUSTIN, TX 78759

BEING 10.22 cores of land, situated in the Nooh Smithwick Survey, Abstract No. 590, in williams on Courty, Texas, soid load being that certain tract of land, collect No. 590, in Weiliams or Courty, Texas, soid load being that certain tract of land, collect of 10.22 cores, as conveyed to IDM Supply by deed recorded as Document No. \*\*ROSZ-94-97-25-\*\* of the Official Records of Williamson County, Texas. Surveyed on the ground in the month of July, 2002, under the supervision of Don H. Büzzlei, Registered Professional Land Surveyor, and being more conflicted described on follows:

BEGINNING at an iron pin found on the south line of State Highway No. 29, marking the

Debuthintor at an early pin loand on the south line of state Highway No. 29, marking the Nartheast corner of the above-referenced 10.22 acrs IDM Supply tract, being the Northwest corner that certain tract of land, called 10.00 acrs, as conveyed to Cano Pasta by deed recorded as Document No. 2000033370 of the Official Records of Williamson County, Texas for the Northrest corner hereof, from said point the Southwest corner of the Nooh Smithwick Survey, Abstract No. 590 bears approximately SI 2: 10° E. 3625 feet, more or less: THEMCE, along the east line of the said 10.22 acre IDM Supply tract, being the west line of the said Clana Pasts tract, as follows; 5 19: 53: 30" w, 190.93 feet to an iron pin found; 5 82" 36" 30" w, 158.13 feet to an iron pin found and 5 7" 23" E, 673.30 feet to an iron pin found on the north line of County Road No. 255, marking the Southeast corner of the said 10.22 once IDM Supply tract, being the Southwest corner of the said 10.22 once iDM supply tract, being the Southwest corner of the said Class Pasts tract, for the Southeast corner hereof;

DHENCE, along the soid north line of County Road No. 259, as follows; S 87° 56° W, 95.82 feet to an iron pin found; S 88° 07° W, 222.78 feet to an iron pin found and S 68° 58° W, 80.90 feet to an iron pin found for the Southwest corner of the soid 10.22 ages IDM Supply fract, being the Southwest corner of the semainder of that certain fact of land, called 25.38 acres, as conveyed to Ching Ruth Hsu Chang and Francis P. Lot, Custodian for Nancy N. Lot, a Minor under the Texas Uniform Cities to Minors Act by deed recorded as Document No. 9725003 of the Official Records of Williamson County, Texas, for the Southwest corner hereof;

THENCE, N 7" 23" W, 1,148.44 feet to an iron pin found on the said south line of State Highway No. 29, for the Northwest comer of the soid 10,22 are IDM Supply trad, being the Northeast corner of the said remainder of the 25-38 are topd, for the Northeast corner break corner break.

THENCE, along the said south line of State Highway No. 29, 5 70° 05' E, 700 00 feet to the Place of BEGINNING and contribining 10.22 cores of land.

STATE OF TEXAS KNOW ALL MEN BY THESE PRESENTS COUNTY OF WILLIAMSON

b) Bon H. Bizzell, Registered Professional Land Sarveyor, in the State of Texas, do hereby certify that this plot is true and correctly made from an actual survey on the ground of the property legalty described hereon, and that there are no apporent discrepancies, conflicts, overlapping of improvements, visible utility lines or roads in place, except as shown on the accompanying plots and that the perimeter field notes hereon have a mathematical closure in compliance with standards as set out in the "Manual of Practice" of the Texas Society of Professional Surveyors, to the best of my knowledge and belief.

TO CERTIFY WHICH, WITNESS my Aind and soul of Georgetown, Williamson County, Texas, this the 20th day of Hugust , 2002, A.D.



Based upon the above representations of the engineer or surveyor whose seal is affixed hereto, and after a review of the plat as represented by the said engineer or surveyor, I find that this plat complies with the requirements of Edwards Aquiter Regulations for Williamson County, the Williamson County Flood Plain Regulations and Williamson County for Site Sewerage Fatchty Regulations. It is certification is made solely upon such representations and should not be relied upon for verification of the facts alleged. The Williamson County & Cities Health Destrict and Williamson County disclaims any responsibility to any member of the public for independent verification of the representation, factual or otherwise, contained in this plat and the documents.

as Paulo Pinto Director of Environmental Services

City of Liberty Hill, Texas Planning and Zoning Commission

This plat has been presented to like Planning and Zoning Commission of the City of Liberty Hill, Texas for review, and has been approved.

Elizabeth Stubble Gerd Chairperson

City of Liberty Hill, Texas

This plot has been presented to the City Council of the City of Liberty Hill, Texas, for review, and has been approved.

Bot W. Eachern

10/11/02

16/17/02

SLIDE # 319 STATE OF TEXAS KNOW ALL MEN BY THESE PRESENTS COUNTY OF WILLIAMSON

I, Don H. Bizzell, Registered Professional Engineer, do hereby certify that this subdivision is not the Edwards Aquifer Recharge Zone. An approved Water Poliution Abatement Plan is not required by the Texas Natural Resource Conservation Commission. No lot within this subdivision is encroached by any Special Flood Hazard Areas inundated by 1909-Year Flood as identified by the U.S. Federal Emergency Management Agency Flood Insurance Rate Map Map No. 4849/COURC C. effective date September 27, 1991.

The engineering work for the roads and drainage (including driveway drain pipes) within the auditivation have been completed in compliance with the Williamson County Subdivision Regulations (including the Engineering Guidelines incorporated as Appendix B) and all generally accepted engineering standards.

TO CERTIFY WHICH WITNESS my hold and segl at Georgetown, Williamson County, Texas, this the 2672 day of 2, A.D.

Professional Engineer, Md 88700N H, BIZZELL B, Bizzell State of Texas CENSE

STATE OF TEXAS KNOW ALL MEN BY THESE PRESENTS; COUNTY OF WILLIAMSON

That I, David S. Morgan, Fresident of IDM Supply, owner of the certain tracks of land shown hereon and described in a deed recorded as Decument No. 2002.066.135. of the Official Records of Williamson County, Isras, do hereby join, approve, and consent to all deficiations and plat note requirements shown hereon. I do hereby approve the recordation of this subdivision plat and dedicate to the public use forever only resements and reads that are shown hereon. This subdivision is to be known as "Seward Junction Commercial Park"

This subdivision is to be known as "Several Junction Commercial Pipes".

I haveby acknowledge that I am the subdiviner of this property and do increby state that there are no lienholders or any unpaid debt for which this property represents collateral on any loan. It is also understood that it is the responsibility of the owner, not the County, to assure compliance with the provisions of all applicable state, federal, and local Jaw's and regulations relating to the environment, including, but not limited to the Endangered Species Act Styte Aquiter Regulations, and Municipal Watershed Ordinances.

10-10-02

Date

IDM Supply David S. Morgan, President 350 CR 250 Liberty Hill, Texas 78642

Before me, the undersigned authority, on this day personally appeared to the David S. Morgan, known by me to be the person whose name is subscribed to the toregoing restrument. At hos been acknowledged, to me that he she executed the foregoing instrument as the senar of the property described herean.



Date Natory Commission Expires

Road name and address assistment verified this the # day of September 2005.

Williamson County Address Coordinates

STATE OF TEXAS §
KNOW ALL MEN BY THESE PRESENTS

In approving this plot by the Commissioners' Court of Williamson County. Texas, lit is understood that the building of all street, roads, and other public thoroughforce and any bridges or curverts necessary to be constructed or placed is the responsibility of the owners of the tract of load ownered by this plot in accordance with the place and specifications prescribed by the Commissioners' Court of Milliamson County, Texas. Solid Commissioners' Court assumes no obligation to build any of the streets, roads, or other public thoroughforce shown on this plot or of construction of any of the bridges or drainage improvements in connection therewith. The County will assume no responsibility for drainage ways or accements in the subdivision, other finan those draining or protecting the road systems and streets.

The County assumes no responsibility for the accuracy of representations by other parties in this plat. Flood plain data, in particular, may change depending an subsequent development. It is further understood that the owners of the tract of land covered by this plat must install at their own excess all traffic control devices and signage that may be required before the streets in the subdivision have linally been accepted for maintenance.

4, John C. Doerfier, County Judge of Williamson County, Texas, do hereby certify that this map or plot, with field notes hereon, that a subdivision having been fully presented to the Commissioners' Court of Williamson County, Texas, and by the said Court duly considered, were on this day opproved and plot to authorized to be registered and recorded in the proper records of the County Clerk of Williamson County, Texas.

C Davids 11-6-02 sylin C. Boertler, Grunky Judge Marmach County, Feves

10-29-61

GENERAL NOTES:

- 2. Number of lots: 33. Number of blocks: 1
- 4. Area of smallest lot: 2.00 Acres
- 5. Proposed use: Commercial business park
- 6. In order to promote drainage away from a structure, the slab elevation should be built at least one foot above the surrounding ground, and the ground should be gooded away from the structure at a slope at 1/2° per foot for a distance of a least 10 feet.
- Each lat will be served by an an-site eastewater system. Water will be provided by Chisholm Trail Water Supply Corporation.
- S. This tract is not located in the Edwards Aquifer Recharge Zone.
- No structure or land on this plat shall hereafter be located or altered without first submitting a CERTIFICATE OF COMPLIANCE Application Form, to the Williamson
- 10.All dwellings, trailers, or mobile homes placed on subdivision lots or ranchettes must be connected to septic tanks or disposal facilities meeting the specifications and conditions of the state Department of Health and the private sewage facility regulations applicable to Williamson County as of the date of applications.

11. DWNER: IDM Supply David S. Morgan 350 CR 250 Liberty Hill, Texas 78642 512-515-5573

12.ENSINEER/SURVEYOR: Don H. Bizzell, P.S. R.P.L.S. Steger & Bizzell, Engineering, Inc. 1978, S. Austin Awange Georgetown, Texas 78626 512-930-9412

15. Bloth of may easements for widening roadways or improving drainage shall be mointained by the loadware until a road or drainage improvements are octually constructed on the property. The County has the right of any time to take passession of any road widening easement for the construction, improvement or maintenance of the adjacent road. The kindowner assumes all risks associated with improvements located in the right—of—

why of road widening easements. By placing anything in the night-of-way or road widening eosements, the landware indemnifies and holds the County, its officers, and employees homiless from any liability away to properly defects or negligence not attributable to their and acknowledges that the improvements may be removed by the County and that the sener of the improvement will be responsible for the relocation.

14.All public readways and easements as shown on this slot are free of liens

15. There are no new roadways proposed for this subdivision.

16.All lots shall use a culvert pipe, with a minimum opening size of 18". Positive Drainage occurs throughout the entire tract, improvements will be made if drainage problems become opporent.

18. TELET Will approve driveways on Hwy 29.

STATE OF TEXAS & RNOW ALL MEN BY THESE PRESENTS COUNTY OF WILLIAMSON \$

l, Nancy Rister, Clark of the County Court of solid County, do hereby certify that the foregoing instrument in writing, with its certificate of authentication was filed for record in my citize on the day of 12 November, 200 A.D., at 3:00 o'clack, P.M., and duly recorded this the /3 day of November 200 2 A.D., at /0.75 o'clock, A M., in the Flat Records of said County in Cobinet U , Side 3/8, 3/9 TO CERTIFY WHICH, WITNESS my band and seal at the County Court of said County, at my office in Georgetown, Texas, the date last shown above written

Nancy Rister, Slerk County Court of Williamson County, Texas



#### SEWARD JUNCTION COMMERCIAL PARK

A 10.22 Acre Subdivision situated in the Noah Smithwick Survey, Abstract No. 590 Williamson County, Texas



Steger & Bizzell Engineering, Inc.

Jeb No. 20071

20071-plat.dwg

Sheet 2 of 2

Telephone: Spcsmie: (512)930-9412 (512)930-9416

NICHOLAS R. SANDLIN

124404 CENSED WELL


SHEET 7 OF 10


P.E.C. LIBERTY HILL EAPP

REVISION RECORD

FINAL PLAT (2 OF 2)

**SANDLIN** 





IF DRAWING BAR DOES NOT MEASURE 2" THIS PRINT IS NOT TO SCALE

1. THIS PROJECT IS SUBMITTED WITHOUT PHASING. 2.ALL EXISTING IMPERVIOUS COVER AND DRAINAGE PATTERNS WILL REMAIN UNCHANGED POST-DEVELOPMENT.

3.CONTRACTOR TO CUT AND REMOVE CONCRETE AS NECESSARY TO REMOVE ALL EXISTING PIPING. REFER TO PLANS BY OTHERS FOR EXACT LOCATION OF DISPENSERS AND PIPING.

4.ALL REQUIRED NOTICES AND PERMITS MUST BE PLACED IN A HIGHLY VISIBLE LOCATION ONSITE BEFORE THE COMMENCEMENT OF

5.ALL EROSION AND SEDIMENTATION CONTROLS (ESC) MUST BE INSTALLED PRIOR TO ANY DISTURBANCE TO THE PROJECT SITE.

6.ALL ESC USED ONSITE MUST BE REGULARLY MONITORED AND MAINTAINED AS NEEDED.

7.THE STABILIZED CONSTRUCTION ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT PREVENTS TRACKING ONTO THE PUBLIC ROADWAY ON AN ONGOING/REGULAR BASIS. MUD AND OR DIRT TRACKÉD INTO THE ROADWAY MUST BE IMMEDIATELY REMOVED UPON DISCOVERY.

8.INLET PROTECTION SHALL BE INSTALLED IMMEDIATELY UPON INLET INSTALLATION.

9.INITIATE TEMPORARY STABILIZATION WHEN CONSTRUCTION CEASES IN A DISTURBED AREA

10. INITIATE PERMANENT STABILIZATION IMMEDIATELY ONCE WORK HAS CEASED AND FINAL GRADE HAS BEEN ACHIEVED.

11. ALL DISTURBED/BARE AREAS WILL REQUIRE PERMANENT STABILIZATION BEFORE FINAL ACCEPTANCE CAN BE ACHIEVED. AVOID DISTURBING AREAS OF THE PROJECT THAT ARE NOT NECESSARY FOR CONSTRUCTION.


12. TEMPORARY ESC'S SHALL REMAIN IN PLACE IN ALL DISTURBED AREAS UNTIL ADEQUATE STABILIZATION HAS BEEN ACHIEVED.

13. THE TECHNICAL SPECS OF ESC DEVICES AND BEST MANAGEMENT PRACTICES (BMP) MEET OR EXCEED THE CITY OF AUSTIN ENVIRONMENTAL

14. PER PLANS BY OTHERS, EXISTING WATER QUALITY AND DETENTION POND HAS CAPACITY FOR AND WILL TREAT RUNOFF DURING CONSTRUCTION AND IN THE PROPOSED

15.NO INCREASED RUNOFF OR TSS WILL RESULT FROM THIS FUEL ISLAND AND TANK

16. IMPERVIOUS COVER PERCENTAGE ON-SITE WILL NOT INCREASE POST-DEVELOPMENT.




### LEGEND

PROPOSED PROPERTY/ PROJECT BOUNDARY LINE EXISTING R.O.W./PROPERTY LINE EXISTING EASEMENT LINE PROPOSED CURB & GUTTER —LOC—LOC—LOC— LIMITS OF CONSTRUCTION .00000000 FIBER ROLL (MULCH) STAGING & TEMPORARY SPOILS AREA STABILIZED CONSTRUCTION **ENTRANCE** 



CONCRETE WASHOUT

NOTE: ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED BY INSPECTOR AT TIME OF CONSTRUCTION.





EROSION CONTROL AND DRAINAGE PLAN


SHEET 8 OF 10


P.E.C. LIBERTY HILL EAPP

**EXCELL FUELING SYSTEMS** 


TBPELS FIRM #21356 9111 JOLLVILLE RD., STE. 212 AUSTIN, TX 78759

SANDLIN






### PROPERTY KEY MAP



IF DRAWING BAR DOES NOT MEASURE 2" THIS PRINT IS NOT TO SCALE




AST TANK LAYOUT PLAN SHEET 9 OF 10

P.E.C. LIBERTY HILL EAPP

**EXCELL FUELING SYSTEMS** 

**SANDLIN** 

TBPELS FIRM #21356 9111 JOLLVILLE RD., STE. 212 AUSTIN, TX 78759



- STONE SIZE: 75-125 mm (3-5") OPEN GRADED ROCK.
- LENGTH: AS EFFECTIVE BUT NOT LESS THAN 15 m (50').
- THICKNESS: NOT LESS THAN 200 mm (8").
- WIDTH: NOT LESS THAN FULL WIDTH OF ALL POINTS OF INGRESS/EGRESS WASHING: WHEN NECESSARY, VEHICLE WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC ROADWAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE AND DRAINS INTO AN APPROVEI TRAP OR SEDIMENT BASIN. ALL SEDIMENT SHALL BE PREVENTED FROM ENTERING ANY STORM DRAIN, DITCH OR WATERCOURSE USING APPROVED METHODS.
- SIORM DRAIN, BICH OF WALER-COURSE USING APPROVED METHODS.

  MAINTENANCE: THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC ROADWAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND, AS WELL AS REPAIR AND CLEAN OUT OF ANY MEASURE DEVICES USED TO TRAP SEDIMENT. ALL SEDIMENTS THAT IS SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC ROADWAY MUST BE REMOVED IMMEDIATELY.
- DRAINAGE: ENTRANCE MUST BE PROPERLY GRADED OR INCORPORATE A DRAINAGE

			À MANNER THAT WILL NOT	CONTR	
CITY OF AUSTIN WATERSHED PROTECTION DEPARTMENT		STABILIZED CONSTRUCTI		CITY OF AUS' WATERSHED PROTECTION DEF	,
RECORD COPY SIGNED BY J. PATRICK MURPHY	5/23/00	THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE	standard nd. : 6415-1	RECORD COPY SIGNED BY MORGAN BYARS	09/01/
	ADOPTED	OF THIS STANDARD.	0,10 1		ADDP

-STEEL OR WOOD FENCE POSTS MAX. 2.4 m (8') SPACING SILT FENCE FABRIC 2" x 4" WELDED WIRE BACKING SUPPORT FOR FABRIC (12.5 GA. WIRE) 600 mm FLOW FABRIC TOE-IN TRENCH (BACKFILLED) STANDARD SYMBOL FOR SILT FENCE (SF) TRENCH CROSS SECTION L=

1. STEEL OR WOOD POSTS WHICH SUPPORT THE SILT FENCE SHALL BE INSTALLED ON A SLIGHT ANGLE TOWARD THE ANTICIPATED RUNOFF SOURCE. POST MUST BE EMBEDDED A MINIMUM OF 300 mm (12 INCHES). IF WOOD POSTS CANNOT ACHIEVE

2. THE TOE OF THE SILT FENCE SHALL BE TRENCHED IN WITH A SPADE OR MECHANICAL TRENCHER, SO THAT THE DOWNSLOPE FACE OF THE TRENCH IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW.

inches) WIDE TO ALLOW FOR THE SILT FENCE FABRIC TO BE LAID IN THE GROUND AND BACKFILLED WITH COMPACTED MATERIAL.

4. SILT FENCE FABRIC SHOULD BE SECURELY FASTENED TO EACH STEEL OR WOOD SUPPORT POST OR TO WOVEN WIRE , WHICH IS IN TURN ATTACHED TO THE STEEL OR

5. INSPECTION SHALL BE MADE WEEKLY OR AFTER EACH RAINFALL EVENT AND REPAIR OR REPLACEMENT SHALL BE MADE PROMPTY AS NEEDED.

6. SILT FENCE SHALL BE REMOVED WHEN THE SITE IS COMPLETELY STABILIZED SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.

ACCUMULATED SILT SHALL BE REMOVED WHEN IT REACHES A DEPTH OF 150 mm (6 inches). THE SILT SHALL BE DISPOSED OF ON AN APPROVED SITE AND IN SUCH MANNER THAT WILL NOT CONTRIBUTE TO ADDITIONAL SILTATION.

> 09/01/201 ADOPTED


SILT FENCE


THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE 642S-1

POSTS POSTS  POSTS  A FT SPACING (BOTH SIDES)	ANCHOR PLACE ADDITIONAL POSTS OR MULCH MATERIAL TO FILL SEAM BETWEEN THE SOCK AND THE GROUND  MIN. 24*  MULCH SOCK MATERIAL
MULCH SOCK  MULCH SOCK	USE UNTREATED WOOD CHIPS PRODUCED FROM A 3 (THREE) INCH MINUS SCREENING PROCESS (EQUIVALENT TO TXDOT ITEM 161, COMPOST, SECTION 1.6.2.B, WOOD CHIP REQUIREMENTS).
O O O O MINIMUM 12" (300 mm) OVERLAP DO NOT STACK MULCH SOCKS	MULCH CONSISTS PRIMARILY OF ORGANIC MATERIAL, SEPARATED AT THE POINT OF GENERATION, AND MAY INCLUDE: SHREDDED BARK, STUMP GRINDINGS, OR COMPOSTED BARK.
	LARGE PORTIONS OF SILT, CLAYS, OR FINE SANDS ARE NOT ACCEPTABLE IN THE MULCH.

- STEEL OR WOOD POSTS WHICH SUPPORT THE MULCH SOCK SHALL BE INSTALLED ON A SLIGHT ANGLE TOWARD THE ANTICIPATED RUNOFF SOURCE. POST MUST BE EMBEDDED A MINIMUM OF 600mm (24 inches). IF WOOD POSTS CANNOT ACHIEVE 600mm (24 inches) DEPTH, USE STEEL POSTS. EARTH
- 2. THE TOE OF THE MULCH SOCK SHALL BE PLACED SO THAT THE MULCH SOCK IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW. IN ORDER TO PREVENT WATER FROM FLOWING BETWEEN THE JOINTS OF ADJACENT ENDS OFMULCH SOCKS, LAP THE ENDS OF ADJACENT MULCH SOCKS A MINIMUM
- MULCH MATERIAL MUST BE FREE OF REFUSE, PHYSICAL CONTAMINANTS, AND MATERIAL TOXIC TO PLANT GROWTH; IT IS NOT ACCEPTABLE FOR THE MULCH MATERIAL TO CONTAIN GROUND CONSTRUCTION DEBRIS, BIOSOLIDS, OR MANURE.
- SOCK MATERIAL WILL BE 100% BIODEGRADABLE, PHOTODEGRADABLE, OR RECYCLABLE SUCH AS BURLAP, TWINE, UV PHOTOBIODEGRADABLE PLASTIC, POLYESTER, OR ANY OTHER ACCEPTABLE
- MULCH SOCKS SHOULD BE USED AT THE BASE OF SLOPES NO STEEPER THAN 2:1 AND SHOULD NOT EXCEED THE MAXIMUM SPACING CRITERIA PROVIDED IN CITY OF AUSTIN ENVIRONMENTAL CRITERIA MANUAL TABLE 1.4.5.F.1 FOR A GIVEN SLOPE CATEGORY
- ACCUMULATED SILT SHALL BE REMOVED WHEN IT REACHES A DEPTH OF 150mm (6 inches). THE SILT SHALL BE DISPOSED OF ON AN APPROVED SITE AND IN SUCH A MANNER THAT WILL NOT CONTRIBUTE TO ADDITIONAL SILTATION.


CITY OF AUSTIN WATERSHED PROTECTION DEPARTMENT	MULCH SOCK	
RECURD CUPY SIGNED BY 08/24/2010 ADDPTED	THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE $6485-1$	





EXCAVATED WASHOUT STRUCTURE

### ONSITE CONCRETE WASHOUT STRUCTURE OR APPROVED EQUAL




CAN BE TWO STACKED BALES OR PARTIALLY EXCAVATED TO REACH 3

WASHOUT STRUCTURE WITH STRAW BALES

### CONSTRUCTION SPECIFICATIONS

- 1. LOCATE WASHOUT STRUCTURE A MINIMUM OF 50 FFFT AWAY FROM OPEN CHANNELS, STORM DRAIN INLETS, SENSITIVE AREAS, WETLANDS, BUFFERS AND WATER COURSES AND AWAY FROM CONSTRUCTION
- SIZE WASHOUT STRUCTURE FOR VOLUME NECESSARY TO CONTAIN WASH WATER AND SOLIDS AND MAINTAIN AT LEAST 4 INCHES OF FREEBOARD. TYPICAL DIMENSIONS ARE 10 FEET X 10 FEET X 3
- 3. PREPARE SOIL BASE FREE OF ROCKS OR OTHER DEBRIS THAT MAY CAUSE TEARS OR HOLES IN THE LINER, FOR LINER, USE 10 MIL OR THICKER UV RESISTANT, IMPERMEABLE SHEETING, FREE OF HOLES AND TEARS OR OTHER DEFECTS THAT COMPROMISE IMPERMEABILITY OF THE MATERIAL.
- 4. PROVIDE A SIGN FOR THE WASHOUT IN CLOSE PROXIMITY TO THE FACILITY.
- 5. KEEP CONCRETE WASHOUT STRUCTURE WATER TIGHT. REPLACE IMPERMEABLE LINER IF DAMAGED (E.G., RIPPED OR PUNCTURED). EMPTY OR REPLACE WASHOUT STRUCTURE THAT IS 75 PERCENT FULL, AND DISPOSE OF ACCUMULATED MATERIAL PROPERLY. DO NOT REUSE PLASTIC LINER. WET-VACUUM STORED LIQUIDS THAT HAVE NOT EVAPORATED AND DISPOSE OF IN AN APPROVED MANNER. PRIOR TO FORECASTED RAINSTORMS, REMOVE LIQUIDS OR COVER STRUCTURE TO PREVENT OVERFLOWS. REMOVE HARDENED SOLIDS, WHOLE OR BROKEN UP, FOR DISPOSAL OR RECYCLING. MAINTAIN RUNOFF DIVERSION AROUND EXCAVATED WASHOUT STRUCTURE UNTIL STRUCTURE IS REMOVED.



WASHOUT STRUCTURE WITH WOOD PLANKS

**EROSION CONTROL DETAILS** SHEET 10 OF 10 P.E.C. LIBERTY HILL EAPP **EXCELL FUELING SYSTEMS** 

SANDLIN TBPELS FIRM #21356 9111 JOLLVILLE RD., STE. 212 AUSTIN, TX 78759

REVISION RECORD



### Attachment N: Inspection, Maintenance, Repair and Retrofit Plan **NOT APPLICABLE**

As no additional IC is proposed for the site, the existing and approved BMP inspection, maintenance, repair and retrofit plan is still in effect (CZP EAPP 11-08030503 dated April 16, 2008, and CZP Modification EAPP 11001078 dated May 23, 2018). No changes are needed.



### Attachment O:

Pilot-Scale Field Testing Plan, if BMPs not based on complying with Edwards Aquifer Rules: Technical Guidance for BMPs (NOT APPLICABLE)

A pilot-scale field testing plan is not applicable. All BMP design and calculations are based on and comply with Edwards Aquifer Technical Guidance for Edwards Aquifer Rules (RG-348, revised July 2005).



### Attachment P: Measures for Minimizing Surface Stream Contamination

No surface streams flow across the property. The property drains southwest to an unnamed tributary that trains directly to the South fork San Gabriel River, approximately two (2) miles south of the project site. The existing sand filter basin BMP will continue to address onsite water quality and stormwater drainage to mitigate and minimize offsite surface stream contamination.



### **Temporary Stormwater Section** (TCEQ-0602)

### **Temporary Stormwater Section**

**Texas Commission on Environmental Quality** 

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

### Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Nick Sandlin, P.E. (Sandlin Services, LLC)

Date: 3/20/2024
Signature of Customer/Agent:

Nice State Sta

### **Project Information**

### **Potential Sources of Contamination**

Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.

l be used during
the site:
city of less than 250

	<ul> <li>Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.</li> <li>Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.</li> </ul>
	igstyle igstyle Fuels and hazardous substances will not be stored on the site.
2.	Attachment A - Spill Response Actions. A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
3.	Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
4.	Attachment B - Potential Sources of Contamination. A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.
S	equence of Construction
5.	Attachment C - Sequence of Major Activities. A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.
	<ul> <li>For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.</li> <li>For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.</li> </ul>
6.	Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: South Fork San Gabriel River

### Temporary Best Management Practices (TBMPs)

Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.

7. Attachment D – Temporary Best Management Practices and Measures. TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.
A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.
A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
Attachment E - Request to Temporarily Seal a Feature. A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.
There will be no temporary sealing of naturally-occurring sensitive features on the site.
<b>Attachment F - Structural Practices</b> . A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
 <b>Attachment G - Drainage Area Map</b> . A drainage area map supporting the following requirements is attached:
For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.
For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.
There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.

[	There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.
5 t -	Attachment H - Temporary Sediment Pond(s) Plans and Calculations. Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.
	N/A
t 1 1	Attachment I - Inspection and Maintenance for BMPs. A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
i (	All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
r f	If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
	Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
ı	Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).
Soil S	Stabilization Practices
-	es: establishment of temporary vegetation, establishment of permanent vegetation, og, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or

preservation of mature vegetation.

17.  $\boxtimes$  Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices. A schedule of the interim and permanent soil stabilization practices for the site is attached.

- 18. Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 19. Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

### Administrative Information

- 20. All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
- 21. If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
- 22. Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.



# Temporary Stormwater Section (TCEQ-0602)

### Attachment A: Spill Response Actions

Spill Response Actions

In the event of an accidental spill, immediate action shall be undertaken by the General Contractor to contain and remove the spilled material. All hazardous materials, including contaminated soil and liquid concrete waste (if applicable), shall be disposed of by the Contractor in the manner specified by Federal, State and Local regulations and by the manufacturer of such products. As soon as possible, the spill shall be reported to the appropriate agencies. As required under the provisions of the Clean Water Act, any spill or discharge entering waters of the United States shall be properly reported. The General Contractor shall prepare a written record of any spill and associated clean-up activities of petroleum products or hazardous materials in excess of 1 gallon or reportable quantities, whichever is less. The General Contractor shall provide notice to the Owner immediately upon identification of a reportable spill.

All spills of petroleum products or hazardous materials in excess of Reportable Quantities as defined by EPA or the State or Local agency regulations, shall be immediately reported within 24 hours to the EPA National Response Center (1-800-424-8802), TCEQ (1-800-832-8224), and local Fire Department (911).

The reportable quantity for hazardous materials can be found in 40 CFR 302:

Reportable Quantities			
Material	Media Released to	Reportable Quantities	
Engine Oil, Fuel, Hydraulic & Brake Fluid	Land	25 gallons	
Engine Oil, Fuel, Hydraulic & Brake Fluid	Water	Visible sheen	
Antifreeze	Land	100 lbs (13 gal.)	
Battery Acid	Land, Water	100 lbs	
Refrigerant	Air	1 lb	
Gasoline	Air, Land, Water	100 lbs	
Engine Degreasers	Air, Land, Water	100 lbs	

For more information, please visit https://www.tceq.texas.gov/response/spills/spill\_rq.html

In order to minimize the potential for a spill of petroleum product or hazardous materials to come in contact with stormwater, the following steps shall be implemented.

1) All materials with hazardous properties (such as pesticides, petroleum products, fertilizers, detergents, construction chemicals, acids paints, paint solvents, additives for soil stabilization,

#### PEC Liberty Hill CONTRIBUTING ZONE PLAN MODIFICATION



concrete curing compounds and additives, etc.) shall be stored in a secure location, under cover and in appropriate, tightly sealed containers when not in use.

- 2) The minimum practical quantity of all such materials shall be kept on the job site and scheduled for delivery as close to the time of use as practical. Post Material Safety Data Sheets (MSDS), as well as proper storage, cleanup, and spill reporting instructions for hazardous materials stored or used on the project site in an open, conspicuous, and accessible location.
- 3) A spill control and containment kit (containing for example: absorbent material such as kitty litter or sawdust, acid neutralizing agent, brooms, dust pans, mops, rags, gloves, goggles, plastic and metal trash containers, etc.) shall be provided on the construction site and construction employees shall be trained in when and how to use spill containment materials.
- 4) The contractor personnel will immediately clean up any oil, fuel or hydraulic fluid if observed being released from equipment or vehicles. Vehicles or equipment will cease operation until required repairs are made to the equipment.
- 5) All of the product in a container shall be used before the container is disposed of. All such containers shall be triple rinsed with water prior to disposal. The rinse water used in these containers shall be disposed of in a manner in compliance with State and Federal regulations and shall not be allowed to mix with stormwater discharges.
- 6) All products shall be stored in and used from the original container with the original product label.
- 7) All products shall be used in strict compliance with instructions on the product label.
- 8) The disposal of the excess or used products shall be in strict compliance with instructions on the product's label.

#### Spill Prevention and Control

#### Education

- 1) Be aware that different materials pollute in different amounts. Make sure that each employee knows what a "significant spill" is for each material they use, and what is the appropriate response for "significant" and "insignificant" spills. Employees should also be aware of when a spill must be reported to the TCEQ. Information is available in 30 TAC 327.4 and 40 CFR 302.4.
- 2) Educate employees and subcontractors on potential dangers to humans and the environment from spills and leaks.
- Hold regular meetings to discuss and reinforce appropriate disposal procedures (incorporate into regular safety meetings).
- 4) Establish a continuing education program to indoctrinate new employees.
- 5) Have contractor's superintendent or representative oversee and enforce proper spill prevention and control measures.



#### General Measures

- To the extent that the work can be accomplished safely, spills of oil, petroleum products, substances listed under 40 CFR parts 110, 117, and 302, and sanitary and septic wastes should be contained and cleaned up immediately.
- Store hazardous materials and wastes in covered containers and protect from vandalism.
- Place a stockpile of spill cleanup materials where it will be readily accessible.
- Train employees in spill prevention and cleanup.
- Designate responsible individuals to oversee and enforce control measures.
- Spills should be covered and protected from stormwater run-on during rainfall to the extent that it doesn't compromise cleanup activities.
- Do not bury or wash spills with water.
- Store and dispose of used clean up materials, contaminated materials, and recovered spill material that is no longer suitable for the intended purpose in conformance with the provisions in applicable BMPs.
- Do not allow water used for leaning and decontamination to enter storm drains or watercourses. Collect and dispose of contaminated water in accordance with applicable regulations.
- 10) Contain water overflow or minor water spillage and do not allow it to discharge into drainage facilities or watercourses.
- 11) Place Material Safety Data Sheets (MSDS), as well as proper storage, cleanup, and spill reporting instructions for hazardous materials stored or used on the project site in an open, conspicuous, and accessible location.
- 12) Keep waste storage areas clean, well-organized, and equipped with ample cleanup supplies as appropriate for the materials being stored. Perimeter controls, containment structures, covers, and liners should be repaired or replaced as needed to maintain proper function.

#### Cleanup

- 1) Clean up leaks and spills immediately.
- Use a rag for small spills on paved surfaces, a damp mop for general cleanup, and absorbent material for larger spills. If the spilled material is hazardous, then the used cleanup materials are also hazardous and must be disposed of as hazardous waste.
- Never hose down or bury dry material spills. Clean up as much of the material as possible and dispose of it properly. See the waste management BMPs in this section for specific information.

#### Minor Spills

- 1) Minor spills typically involve small quantities of oil, gasoline, paint, etc. which can be controlled by the first responder at the discovery of the spill.
- Use absorbent materials on small spills rather than hosing down or burying the spill.
- Absorbent materials should be promptly removed and disposed of properly.



- 4) Follow the practice below for a minor spill:
- Contain the spread of the spill.
- Recover spilled materials.
- Clean the contaminated area and properly dispose of contaminated materials.

### Semi-Significant Spills

Semi-significant spills still can be controlled by the first responder along with the aid of other personnel such as laborers and the foreman, etc. This response may require the cessation of all other activities. Spills should be cleaned up immediately.

- 1) Contain spread of the spill.
- 2) Notify the project foreman immediately.
- 3) If the spill occurs on paved or impermeable surfaces, clean up using "dry" methods (absorbent materials, cat litter and/or rags). Contain the spill by encircling with absorbent materials and do not let the spill spread widely.
- 4) If the spill occurs in dirt areas, immediately contain the spill by constructing an earthen dike. Dig up and properly dispose of contaminated soil.
- If the spill occurs during rain, cover the spill with tarps or other material to prevent contaminating runoff.

### Significant/Hazardous Spills

For significant or hazardous spills that are in reportable quantities:

- 1) Notify the TCEQ by telephone as soon as possible and within 24 hours at 512-339-2929 (Austin) or 210-490-3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224. It is the contractor's responsibility to have all emergency phone numbers at the construction site.
- 2) For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110,009, and 302, the contractor should notify the National Response Center at (800)424-8802.
- 3) Notification should first be made by telephone and followed up with a written report.
- The services of a spill's contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staff have arrived at the job site.
- Other agencies which may need to be consulted include, but are not limited to, the City Police Department, County sheriff Office, Fire Departments, etc.

More information on spill rules and appropriate responses is available on the TCEQ website at: https://www.tceq.texas.gov/downloads/compliance/investigations/spills/spill-poster-x.pdf

#### Vehicle and Equipment Maintenance

If maintenance must occur onsite, use a designated area and a secondary containment, located away from drainage course, to prevent the runon of stormwater and the runoff of spills.



- 2) Regularly inspect onsite vehicles and equipment for leaks and repair immediately.
- Check incoming vehicles and equipment (including delivery trucks, and employee and subcontractor vehicles) for leaking oil and fluids. Do not allow leaking vehicles or equipment onsite.
- Always use secondary containment, such as a drain pan or drop cloth, to catch spills or leaks when removing or changing fluids.
- Place drip pans or absorbent materials under paving equipment when not in use.
- Use absorbent materials on small spills rather than hosing down or burying the spill. Remove the absorbent materials promptly and dispose of them properly.
- Promptly transfer used fluids to the proper waste or recycling drums. Don't leave full drip pans or other open containers lying around.
- Oil filters disposed of in trashcans or dumpsters can leak oil and pollute stormwater. Place the oil filter in a funnel over a waste oil-recycling drum to drain excess oil before disposal. Oil filters can also be recycled. Ask the oil supplier or recycler about recycling oil filters.
- Store cracked batteries in a non-leaking secondary container. Do this with all cracked batteries even if you think all the acid has drained out. If you drop a battery, treat it as if it is cracked. Put it into the containment area until you are sure it is not leaking.

#### Vehicle and Equipment Fueling

- 1) If fueling must occur on site, use designated areas, located away from drainage courses, to prevent the runon of stormwater and the runoff of spills.
- Discourage 'topping off' of fuel tanks.

Always use secondary containment, such as a drain pan, when fueling to catch spills/leaks.

#### SPILL REPORT FORM

#### Notes to General Contractor:

- Control and contain the spill.
- Contact the appropriate regulatory agencies if the spill exceeds the applicable reportable quantity.
- Clean up the spill and dispose of waste according to federal, state and local regulations.
- Complete the Spill Report Form in full for each spill that exceeds the applicable reportable quantity and submit to the Owner.
- Call the Owner.
- Resolve as appropriate and as required by regulatory authorities.



### SPILL REPORT FORM

PROJECT: PROJECT ADDRESS:		
Spill Reported By:		
Date / Time of Spill:		
Describe spill location and events leading to spill:		
Material Spilled:		
Source of Spill:		
Amount Spilled:		
Amount Spilled to Waterway (Name Waterway):		
Containment or Clean up Action:		
Approximate depth (yards) of soil excavation:		
List injuries or Personal Contamination:		
Action to be taken to prevent future spills:		
Agencies notified of spill:		
Contractor Signature and Printed Name	 Date	

AFTER NOTIFYING GOVERNING AUTHORITIES, IMMEDIATELY COMPLETE THIS FORM AND CONTACT THE OWNER IF THE SPILL EXCEEDS THE REPORTABLE QUANTITY FOR THE GOVERNING AGENCY



### **Temporary Stormwater Section** (TCEQ-0602)

### Attachment B: **Potential Sources of Contamination**

Potential Sources of Contamination and Preventive Measures:

Potential Source: Concrete and concrete products used on-site during construction.

Preventive Measures: Concrete washout structure will be used if necessary.

Potential Source: Oil, grease, fuel, and hydraulic fluid contamination from construction equipment and vehicle

Preventative Measures: Vehicle maintenance will be performed at a local maintenance shop.

Potential Source: Miscellaneous trash and litter from construction workers and material wrappings.

Preventative Measures: Trash containers will be placed throughout the site to encourage proper disposal of trash.

Potential Source: Silt leaving the site

Preventative Measures: Contractor will install all temporary best management practices prior to start of construction

including the stabilized construction entrance to prevent tracking onto adjoining streets.

Potential Source: Construction debris

Preventative Measures: Construction debris will be monitored daily by contractor. Debris will be collected weekly and placed in disposal bins. Situations requiring immediate attention will be addressed on a case by case basis.

Potential Source: Soil and mud from construction vehicle tires as they leave the site.

Preventative Measures: a stabilized construction exit shall be utilized as vehicles leave the site. And soil, mud, etc. carried from the project onto public roads shall be cleaned up within 24 hours.

Potential Source: Sediment from soil, sand, gravel, and excavated materials stockpiled on site.

Preventative Measures: Silt fence shall be installed on the down gradient side of the stockpiled materials. Reinforced rock berms shall be installed at all downstream discharge locations.

Potential Source: Portable toilet spill

Preventative Measures: Toilets on the site will be emptied on a regular basis by the contracted toilet company.



# Temporary Stormwater Section (TCEQ-0602)

### Attachment C: Sequence of Major Activities

The installation of erosion and sedimentation controls shall occur prior to any excavation of materials or major disturbances on the site. The sequence of major construction activities will be as follows. Approximate acreage (AC)to be disturbed is listed in parentheses next to each activity.

Intended Schedule or Sequence of Major Activities:

- 1. Submit written notice of construction to TCEQ regional office at least 48 hours prior to the start of any regulated activities.
- 2. A pre-construction conference prior to commencement of construction. All contractors conducting regulated activities associated with this project must be provided with complete copies of the approved Contributing Zone Plan (CZP) and the TCEQ letter indicating the specific conditions of its approval. During the course of these regulated activities, the contractors are required to keep on-site copies of the approved plan and approval letter.
- 3. Contractors must follow requirements as outlined in TCEQ General Construction Notes for the Contributing Zone Plan (CZP). CZP Construction Notes are listed in the Construction Plans (Attachment M of the Contributing Zone Plan Application section).
- 4. Prior to beginning any construction activity, all temporary erosion and sedimentation BMPs and control measures must be properly installed and maintained in accordance with the approved plans and manufacturers specifications (0.15 Acres).
- 5. Evaluate temporary erosion control installation. If inspections indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations. These controls must remain in place until the disturbed areas have been permanently stabilized.
- 6. Review construction schedule and the Contributing Zone Plan (CZP) requirements.
- 7. Install the AST (0.15 Acres).
- 8. Piping and ancillary equipment installation.
- 9. Install tank fittings and other associated equipment.
- 10. Site cleanup and removal of temporary erosion/sedimentation BMP controls. (0.15 Acres)



### **Temporary Stormwater Section** (TCEQ-0602)

### Attachment D: Temporary Best Management Practices and Measures

- 1. There is approximately 0.0 AC of storm water that originates up gradient from the site and flows through the existing onsite BMP.
- Temporary BMPs will be installed prior to soil disturbing construction activity. Silt fencing will be placed along the down-gradient sides of the property and limits of construction to prevent silt from escaping the construction area during permanent BMP construction.
- A concrete washout pit may be used to collect all excess concrete during construction, if needed.
- 4. Temporary BMPs for this project will protect surface water or groundwater from turbid water, phosphorus, sediment, oil and other contaminants, which may mobilize in stormwater flows by slowing the flow of runoff to allow sediment and suspended solids to settle out of the runoff.
- Practices may also be implemented on site for interim and permanent stabilization. Stabilization practices may include but are not limited to establishment of temporary vegetation; establishment of permanent vegetation; mulching; geotextiles; sod stabilization; vegetative buffer strips; protection of existing trees and vegetation; and other similar measures.
- There are no sensitive features or surface streams within the boundaries of the project that would require temporary BMPs. The temporary onsite BMPs will be used to treat stormwater runoff before it leaves the project and prevent pollutants from entering surface streams or any sensitive features down gradient of the site.



## **Temporary Stormwater Section** (TCEQ-0602)

Attachment E: Request to Temporarily Seal a Feature (NOT APPLICABLE)



# Temporary Stormwater Section (TCEQ-0602)

# Attachment F: Structural Practices

Structural BMPs will be used to limit runoff discharge of pollutants from exposed areas of the site. BMPs will be installed prior to soil disturbing construction activity. Silt fencing will be placed along the down-gradient sides of the property to prevent silt from escaping the construction area. A temporary construction entrance will be placed at the site entry/exit point to reduce tracking onto adjoining streets. A construction staging area will be used onsite to perform all vehicle maintenance and for equipment and material storage. A concrete truck washout pit will be placed on site to provide containment and easier cleanup of waste from concrete operations. The location of all structural temporary BMPs are shown within the Site Plans.

Description of Temporary BMPs

### Fiber Roll:

The purpose of a fiber roll is to intercept and detain water-borne sediment from unprotected areas of a limited extent. Fiber rolls are used during the period of construction near the perimeter of a disturbed area to intercept sediment, reduce flow velocity, and release runoff as sheet flow. If concentrated flow occurs after installation, corrective action must be taken such as placing a rock berm in the areas of concentrated flow.

#### Triangular Sediment Filter Dikes

Triangular sediment filter dikes (18"x18"x18" filter material with 6" square folded wire mesh frame) will be installed downgradient of the AST construction area with filter cloth placed over any existing stormwater collection drains. The dike and filter cloth will be held in place with cloth sandbags. The facility existing topography will not change as the AST will be placed on existing crushed rock.

### Concrete Washout Area

The purpose of concrete washout areas is to prevent or reduce the discharge of pollutants to stormwater from concrete waste by conducting washout offsite, performing onsite washout in a designated area, and training employees and subcontractors.

The following steps will help reduce stormwater pollution from concrete wastes:

- Incorporate requirements for concrete waste management into material supplier and subcontractor agreements.
- Avoid mixing excess amounts of fresh concrete.
- Perform washout of concrete trucks in designated areas only.
- Do not wash out concrete trucks into storm drains, open ditches, streets, or streams.
- Do not allow excess concrete to be dumped onsite, except in designated areas.
- For onsite washout:







- Locate washout area at least 50 feet from sensitive features, storm drains, open ditches, or water bodies. Do not allow runoff from this area by constructing a temporary pit or bermed area large enough for liquid and solid waste.
- Wash out wastes into the temporary pit where the concrete can set, be broken up, and then disposed properly.



# Temporary Stormwater Section (TCEQ-0602)

Attachment G: Drainage Area Map





IF DRAWING BAR DOES NOT MEASURE 2" THIS PRINT IS NOT TO SCALE

1. THIS PROJECT IS SUBMITTED WITHOUT PHASING. 2.ALL EXISTING IMPERVIOUS COVER AND DRAINAGE PATTERNS WILL REMAIN UNCHANGED POST-DEVELOPMENT.

3.CONTRACTOR TO CUT AND REMOVE CONCRETE AS NECESSARY TO REMOVE ALL EXISTING PIPING. REFER TO PLANS BY OTHERS FOR EXACT LOCATION OF DISPENSERS AND PIPING.

4.ALL REQUIRED NOTICES AND PERMITS MUST BE PLACED IN A HIGHLY VISIBLE LOCATION ONSITE BEFORE THE COMMENCEMENT OF

5.ALL EROSION AND SEDIMENTATION CONTROLS (ESC) MUST BE INSTALLED PRIOR TO ANY DISTURBANCE TO THE PROJECT SITE.

6.ALL ESC USED ONSITE MUST BE REGULARLY MONITORED AND MAINTAINED AS NEEDED.

7.THE STABILIZED CONSTRUCTION ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT PREVENTS TRACKING ONTO THE PUBLIC ROADWAY ON AN ONGOING/REGULAR BASIS. MUD AND OR DIRT TRACKÉD INTO THE ROADWAY MUST BE IMMEDIATELY REMOVED UPON DISCOVERY.

8.INLET PROTECTION SHALL BE INSTALLED IMMEDIATELY UPON INLET INSTALLATION.

9.INITIATE TEMPORARY STABILIZATION WHEN CONSTRUCTION CEASES IN A DISTURBED AREA

10. INITIATE PERMANENT STABILIZATION IMMEDIATELY ONCE WORK HAS CEASED AND FINAL GRADE HAS BEEN ACHIEVED.

11. ALL DISTURBED/BARE AREAS WILL REQUIRE PERMANENT STABILIZATION BEFORE FINAL ACCEPTANCE CAN BE ACHIEVED. AVOID DISTURBING AREAS OF THE PROJECT THAT ARE NOT NECESSARY FOR CONSTRUCTION.


12. TEMPORARY ESC'S SHALL REMAIN IN PLACE IN ALL DISTURBED AREAS UNTIL ADEQUATE STABILIZATION HAS BEEN ACHIEVED.

13. THE TECHNICAL SPECS OF ESC DEVICES AND BEST MANAGEMENT PRACTICES (BMP) MEET OR EXCEED THE CITY OF AUSTIN ENVIRONMENTAL

14. PER PLANS BY OTHERS, EXISTING WATER QUALITY AND DETENTION POND HAS CAPACITY FOR AND WILL TREAT RUNOFF DURING CONSTRUCTION AND IN THE PROPOSED

15.NO INCREASED RUNOFF OR TSS WILL RESULT FROM THIS FUEL ISLAND AND TANK

16. IMPERVIOUS COVER PERCENTAGE ON-SITE WILL NOT INCREASE POST-DEVELOPMENT.




### LEGEND

PROPOSED PROPERTY/ PROJECT BOUNDARY LINE EXISTING R.O.W./PROPERTY LINE EXISTING EASEMENT LINE PROPOSED CURB & GUTTER —LOC—LOC—LOC— LIMITS OF CONSTRUCTION .00000000 FIBER ROLL (MULCH) STAGING & TEMPORARY SPOILS AREA STABILIZED CONSTRUCTION **ENTRANCE** 



CONCRETE WASHOUT

NOTE: ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED BY INSPECTOR AT TIME OF CONSTRUCTION.





EROSION CONTROL AND DRAINAGE PLAN

SHEET 8 OF 10

P.E.C. LIBERTY HILL EAPP

**EXCELL FUELING SYSTEMS** 

TBPELS FIRM #21356 9111 JOLLVILLE RD., STE. 212 AUSTIN, TX 78759

SANDLIN



## **Temporary Stormwater Section** (TCEQ-0602)

## Attachment H: Temporary Sediment Pond(s) Plans and Calculations (NOT APPLICABLE)



# Temporary Stormwater Section (TCEQ-0602)

# Attachment I: Inspection and Maintenance for BMPs

Inspection and Maintenance Guidelines for Construction BMPs

#### Fiber Rolls – Section 1.4.14

- (1) Inspect and verify that activity based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly to verify continued BMP implementation.
- (2) Inspect BMPs subject to non-stormwater discharges daily while non-stormwater discharges occur.
- (3) Unit-specific maintenance requirements are included with the description of each technology.
- (4) Sediment removed during the maintenance of a dewatering device may be either spread onsite and stabilized or disposed of at a disposal site.
- (5) Sediment that is commingled with other pollutants must be disposed of in accordance with all applicable laws and regulations.

### Personnel Responsible for Inspections

The agent that performs the inspections should be knowledgeable of this general permit, familiar with the construction site, and knowledgeable of the SWPPP for the site. Documentation of the inspector's qualifications is to be included in the attached Inspector Qualifications Log.

### Inspection Schedule

The primary operator is required to choose one of the two inspections listed below.

□ Option 1	<b>l:</b> Once ever	y seven ca	alendar da	ays. If this altern	native schedu	ale is develop	ed, then the
inspection inspection.		egardless	of wheth	er or not there l	nas been a ra	infall event s	ince the previous
	• 0						_

□ **Option 2:** Once every 14 calendar days and within 24 hours of the end of a storm event of two inches or greater.

The inspections may occur on either schedule provided that documentation reflects the current schedule and that any changes to the schedule are conducted in accordance with the following provisions: the schedule may be changed a maximum of one time each month, the schedule change must be implemented at the beginning of a calendar month, and the reason for the schedule change must be documented (e.g., end of "dry" season and beginning of "wet" season).



If option 2 is the chosen frequency of inspections a rain gauge must be properly maintained on site or the storm event information from a weather station that is representative of the site location. For any day of rainfall during normal business hours that measures 0.25 inches or greater, proper documentation of the total rainfall measured for that day must be recorded.

Personnel provided by the permittee must inspect:

- disturbed areas of the construction site that have not been finally stabilized
- areas used for storage of materials that are exposed to precipitation
- structural controls (for evidence of, or the potential for, pollutants entering the drainage system)
- sediment and erosion control measures identified in the SWP3 (to ensure they are operating correctly), and
- locations where vehicles enter or exit the site (for evidence of off-site sediment tracking)

### Reductions in Inspection Frequency

Where sites have been finally or temporarily stabilized or where runoff is unlikely due to winter conditions (e.g., site is covered with snow, ice, or frozen ground exists), inspections must be conducted at least once every month. In arid, semi-arid, or drought-stricken areas, inspections must be conducted at least once every month and within 24 hours after the end of a storm event of 0.5 inches or greater. A record of the total rainfall measured, as well as the approximate beginning and ending dates of winter or drought conditions resulting in monthly frequency of inspections in the attached Rain Gauge Log.

In the event of flooding or other uncontrollable situations which prohibit access to the inspection sites, inspections must be conducted as soon as access is practicable.

### <u>Inspection Report Forms</u>

Use the Inspection Report Forms given as a checklist to ensure that all required areas of the construction site are addressed. There is space to document the inspector's name as well as when the inspections regularly take place. The tables will document that the required area was inspected. (If there were any areas of concern, briefly describe them in this space with a more detailed description in the narrative section. Use the last table to document any discharges found during the inspections).

Describe how effective the installed BMPs are performing. Describe any BMP failures that were noted during the investigation and describe any maintenance required due to the failure. If new BMPs are needed as the construction site changes, the inspector can use the space at the bottom of the section to list BMPs to be implemented before the next inspection.

Describe the inspector's qualifications, how the inspection was conducted, and describe any areas of non-compliance in detail. If an inspection report does not identify any incidents of non-compliance, then it must contain a certifying signature stating that the facility or site is in compliance. The report must be signed by a person and in a manner required by 30 TAC 305.128. There is space at the end of the form to allow for this certifying signature.

Whenever an inspection shows that BMP modifications are needed to better control pollutants in runoff, the changes must be completed within seven calendar days following the inspection. If existing BMPs are





modified or if additional BMPs are needed, you must describe your implementation schedule, and wherever possible, make the required BMP changes before the next storm event.

The Inspection Report Form functions as the required report and must be signed in accordance with TCEQ rules at 30 TAC 305.128.

Corrective Action

#### Personnel Responsible for Corrective Actions

Both Primary and Secondary Operators are responsible for maintaining all necessary Corrective Actions. If an individual is specifically identified as the responsible party for modifying the contact information for that individual should be documented in the attached Inspector Qualifications Log.

### Corrective Action Forms

The Temporary BMPs must be modified based on the results of inspections, as necessary, to better control pollutants in runoff. Revisions must be completed within seven (7) calendar days following the inspection. If existing BMPs are modified or if additional BMPs are necessary, an implementation schedule must be described in the attached forms and wherever possible those changes implemented before the next storm event. If implementation before the next anticipated storm event is impracticable, these changes must be implemented as soon as practicable. Actions taken as a result of inspections must be properly documented by completing the corrective action forms given.



### Inspector Qualifications Log\*

Inspector Name:
Qualifications (Check as appropriate and provide description):
☐ Training Course
□ Supervised Experience
□ Other
Inspector Name:
☐ Training Course
□ Supervised Experience
□ Other
Inspector Name:
Qualifications (Check as appropriate and provide description):
☐ Training Course
□ Supervised Experience
□ Other
Inspector Name:
Qualifications (Check as appropriate and provide description):
☐ Training Course
□ Supervised Experience
□ Other
Inspector Name:
Qualifications (Check as appropriate and provide description):
☐ Training Course
□ Supervised Experience
□ Other
Inspector Name
Inspector Name:
☐ Training Course
□ Supervised Experience
□ Other

\*The agent that performs the inspections should be knowledgeable of this general permit, familiar with the construction site, and knowledgeable of the SWPPP for the site. The contractor is to provide an inspector with a CPESC, CESSWI, or CISEC certification.



# Amendment Log

No.	Description of the Amendment	Date of Amendment	Amendment Prepared by [Name(s) and Title]

# Construction Activity Sequence Log\*

Name of Operator	Projected Dates Month/Year	Activity Disturbing Soil clearing, excavation, etc.	Location on-site where activity will be conducted	Acreage being disturbed

<sup>\*</sup>Construction activity sequences for linear projects may be conducted on a rolling basis. As a result, construction activities may be at different stages at different locations in the project area. The Contractor is required to complete and update the schedule and adjust as necessary.

# Stormwater Control Installation and Removal Log

Stormwater Control	Location On-Site	Installation Date	Removal Date

### Stabilization Activities Log\*

Date Activity Initiated	Description of Activity	Description of Stabilization Measure and Location	Date Activity Ceased (Indicate Temporary or Permanent)	Date When Stabilization Measures Initiated

<sup>\*</sup>Stabilization and erosion control practices may include, but are not limited to, establishing temporary or permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, and protecting existing trees and vegetation. List practices used where they are located, when they will be implemented, and whether they are temporary (interim) or permanent.

# **Inspection Frequency Log**

Date	Frequency



# Rain Gauge Log

Date	Location of Rain Gauge	Gauge Reading

General Information							
Name of Project		Tracking Number		Inspection Date			
Inspector Name, Title & Contact				·			
Information							
Present Phase of Construction							
Inspection Location (if multiple							
inspections are required, specify location							
where this inspection is being conducted)							
Inspection Frequency	_						
Standard Frequency:   Weel	kly $\Box$ Every 14 days and within 2	24 hours of a 0.25" rain					
	ry 7 days and within 24 hours of a	0.25" rain					
Reduced Frequency:							
☐ Once per month (for s	stabilized areas)						
☐ Once per month and v	within 24 hours of a 0.25" rain (for	arid, semi-arid, or drou	ght-stricken areas during	seasonally dry periods or during			
drought)	`		9	, , ,			
☐ Once per month (for t	frozen conditions where earth-dist	urbing activities are bein	g conducted)				
Was this inspection triggered by a 0.25"		O	/				
If yes, how did you determine whether a		?					
	er station representative of site. Spe		rce				
I Rain gauge on site I weather	if stadon representative of site. ope	cerry weather station sou	icc.				
Total rainfall amount that trigge	ered the inspection (in inches):						
Unsafe Conditions for Inspection							
_		· · · · · · · · · · · · · · · · · · ·					
Did you determine that any por	tion of your site was unsafe for	inspection?   Yes	□No				
If "yes," complete the following							
	;· :hat prevented you from conductin	or the inspection in this l	ocation:				
o Describe the conditions t	that prevented you from conducting	ig the mspeedon in this i	ocation.				
o Location(s) where conditi	ions were found:						



Condition and Effectiveness of Erosion and Sediment (E&S) Controls						
Type / Location of E&S Control	Repairs or Other Maintenance Needed?	Corrective Action Required?	Date on Which Maintenance of Corrective Action First Identified?	Notes		
1.	□ Yes □ No	□ Yes □ No				
2.	□ Yes □ No	□ Yes □ No				
3.	□ Yes □ No	□ Yes □ No				
4.	□ Yes □ No	□ Yes □ No				
5.	□ Yes □ No	□ Yes □ No				
6.	□ Yes □ No	□ Yes □ No				
7.	□ Yes □ No	□ Yes □ No				
8.	□ Yes □ No	□ Yes □ No				
9.	□ Yes □ No	□ Yes □ No				



Condition and Effectiveness of Pollution Prevention (P2) Practices							
Type / Location of P <sub>2</sub> Practices	Repairs or Other Maintenance Needed?	Corrective Action Required?	Identification Date	Notes			
1.	□ Yes □ No	□ Yes □ No					
2.	☐ Yes ☐ No	□ Yes □ No					
3.	□ Yes □ No	□ Yes □ No					
4.	□ Yes □ No	□ Yes □ No					
5.	□ Yes □ No	□ Yes □ No					
6.	□ Yes □ No	□ Yes □ No					
7.	□ Yes □ No	□ Yes □ No					
8.	☐ Yes ☐ No	□ Yes □ No					
9.	□ Yes □ No	□ Yes □ No					



Stabilization of Exposed Soil							
Stabilization Area	Stabilization Method	Have you Initiated Stabilization?	Notes				
1.		☐ YES ☐ NO If yes, provide date:					
2.		☐ YES ☐ NO If yes, provide date:					
3.		☐ YES ☐ NO If yes, provide date:					
4.		☐ YES ☐ NO If yes, provide date:					
	Description	of Discharges					
	rge or other discharge occurring from any part of yo owing information for each point of discharge:	our site at the time of the inspection? $\Box$ Y	ES 🗆 NO				
Discharge Locations	Observations						
1.	Describe the discharge:  At points of discharge and the channels and banks of surface waters in the immediate vicinity, are there any visible signs of erosion and / or sediment accumulation that can be attributed to your discharge?   YES.   NO  If yes, describe what you see, specify the location(s) where these conditions were found, and indicate whether modification, maintenance, or corrective action is needed to resolve the issue:						
2.	Describe the discharge:  At points of discharge and the channels and banks of surface waters in the immediate vicinity, are there any visible signs of erosion and / or sediment accumulation that can be attributed to your discharge?   YES.   NO  If yes, describe what you see, specify the location(s) where these conditions were found, and indicate whether modification, maintenance, or corrective action is needed to resolve the issue:						
3.	Describe the discharge:  At points of discharge and the channels and banks of or sediment accumulation that can be attributed to yo If yes, describe what you see, specify the location(s) wor corrective action is needed to resolve the issue:	ur discharge? □ YES. □ NO					



# Contractor or Subcontractor Certification and Signature

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in a that qualified personnel properly gathered and evaluated the information, submitted. Based on my inquiry of the person or persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment	persons who manage the system, or those belief, true, accurate, and complete. I am,	
Signature of Contractor or Subcontractor:	_ Date:	
Printed Name and Affiliation:		
Certification and Signature by Permittee		
"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in a that qualified personnel properly gathered and evaluated the information, submitted. Based on my inquiry of the person or persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment	persons who manage the system, or those belief, true, accurate, and complete. I am,	
Signature of Permittee or "Duly Authorized Representative":	Date:	
Printed Name and Affiliation:		



Section A – Initial Report				
(Complete this section within 24 hours of discovering the condition that triggered corrective action.)				
Name of Project:		Tracking Nu		Today's Date
Date Problem First Discovered:			m First Discovered:	
Name of Individual Completing this Form:		Contact Info	ormation:	
What site conditions triggered the requirement to conduct corrective act				
☐ A required stormwater control was never installed, was installed inco	orrectly, or not in acco	ordance with the requirem	ents in Part 2 and/or	Part 3
☐ The stormwater controls that have been installed and maintained are	not effective enough	n for the discharge to meet	t applicable water qual	ity standards
☐ A prohibited discharge has occurred or is occurring				
Provide a description of the problem:				
Deadline for completing corrective action (Enter date that is either: (1)	no more than 7 calen	dar days after the date you	discovered the proble	em, or (2) if it is infeasible to complete work
within the first 7 days, enter the date that is as soon as practicable follow	ving the 7th day):			
	· (4) 1 1 1		1 .11	1.00
If your estimated date of completion falls after the 7-day deadline, expla			te work within / days,	and (2) why the date you have established
for making the new or modified stormwater control operational is the so	oonest practicable tin	nerrame:		
Continu D. Competing Asting Day areas				
Section B – Corrective Action Progress				against agreement in a section
(Complete this section no later than 7 calendar days after discovering the condition that triggered corrective action.)				
Section B.1 – Why the Problem Occurred Cause(s) of Problem (Add an additional sheet if necessary)		How This Was Determi	and and the Date Voy	Determined the Course
			ned and the Date You	Determined the Cause
1.		1.		
2.		2.		
2.		۷.		
Section B.2 – Stormwater Control Modifications to be Implemented to Correct the Problem				
List of Stormwater control Modification(s) Needed to Correct	Completion Date	SWPPP Update	Notes	
Problem (Add an additional sheet if necessary)	Completion Bate	Necessary?	TVOICS	
1.		☐ Yes ☐ No		
		Date:		
2.				
		☐ Yes ☐ No Date:		
	<u> </u>	Date:		



Section A – Initial Report  (Complete this section within 24 hours of discovering the condition that triggered corrective action.)				
Name of Project:		Tracking Nu		Today's Date
Date Problem First Discovered:		Time Proble	m First Discovered:	
Name of Individual Completing this Form:		Contact Info	ormation:	
What site conditions triggered the requirement to conduct corrective act	ion:	<u>.</u>		
☐ A required stormwater control was never installed, was installed incompared in the control was never installed.	rectly, or not in acco	rdance with the requirem	ents in Part 2 and/or I	Part 3
☐ The stormwater controls that have been installed and maintained are				
☐ A prohibited discharge has occurred or is occurring	Q	O	11	•
Provide a description of the problem:  Deadline for completing corrective action (Enter date that is either: (1) r within the first 7 days, enter the date that is as soon as practicable follow.  If your estimated date of completion falls after the 7-day deadline, explain for making the new or modified stormwater control operational is the so	ring the 7th day): in (1) why you believe conest practicable time  Section B -	e it is infeasible to complete frame:  - Corrective Action P	ete work within 7 days,	and (2) why the date you have established
(Complete this section no late	r than 7 calendar d	ays after discovering th	e condition that trig	gered corrective action.)
Section B.1 – Why the Problem Occurred		Harry This Was Data was		Determined the Court
Cause(s) of Problem (Add an additional sheet if necessary)		How This Was Determine 1.	ned and the Date You	Determined the Cause
1.		1.		
2.		2.		
Section B.2 – Stormwater Control Modifications to be Imple	emented to Correc	t the Problem		
List of Stormwater control Modification(s) Needed to Correct	Completion Date	SWPPP Update	Notes	
Problem (Add an additional sheet if necessary)		Necessary?		
1.		☐ Yes ☐ No Date:		
2.		☐ Yes ☐ No		
		Date:		
			·	

Contractor or Subcontractor Certification and Signature



"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information, submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am, aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."		
Signature of Contractor or Subcontractor:	Date:	
Printed Name and Affiliation:		
Certification and Signature by Permittee		
"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information, submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am, aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."		
Signature of Permittee or "Duly Authorized Representative":  Printed Name and Affiliation:	Date:	



# Temporary Stormwater Section TCEQ-0602)

### Attachment J: Schedule of Interim and Permanent Soil Stabilization Practices

Interim Vegetative Stabilization

Interim soil stabilization will not be required.

Permanent Vegetative Stabilization

Construction practices shall disturb the minimal amount of existing ground cover as required for land clearing, grading, and construction activity for the shortest amount of time possible to minimize the potential of erosion and sedimentation from the site. Existing vegetation shall be maintained and left in place until it is necessary to disturb construction activity. For this project, the following stabilization practices will be implemented:

- 1. Hydraulic Mulch and Seeding: Disturbed areas subject to erosion shall be stabilized with hydraulic mulch and/or seeded and watered to provide interim stabilization.
- 2. Sodding and Wood Mulch: As per the project landscaping plan, sodding and wood mulch will be applied to landscaped areas to provide permanent stabilization prior to project completion.

Records of the following shall be maintained:

- 1. The dates when major grading activities occur,
- 2. The dates when construction activities temporarily or permanently cease on a portion of the site,
- 3. The dates when stabilization measures are initiated.

Stabilization measures must be initiated as soon as practical in portions of the site where construction activities have temporarily or permanently ceased, and except as provided in the following, must be initiated no more than fourteen (14) days after the construction activity in that portion of the site has temporarily or permanently ceased:

Where the initiation of stabilization measures by the 14<sup>th</sup> day after construction activity temporarily or permanently ceased is precluded by snow cover or frozen ground conditions, stabilization measures must be initiated as soon as practical.





Where construction activity on a portion of the site is temporarily ceased and earth disturbing activities will be resumed within twenty-one (21) days, temporary stabilization measures do not have to be initiated on that portion of the site.

In arid areas (areas with an average rainfall of 0-10 inches), semiarid areas (areas with an average annual rainfall of 10 to 20 inches), and areas experiencing droughts where the initiation of stabilization measures by the 14<sup>th</sup> day after construction activity has temporarily or permanently ceased is precluded by seasonably arid conditions, stabilization measures must be initiated as soon as practical.



# Copy of Notice of Intent (NOI)



## **Agent Authorization Form** (TCEQ-0599)

### **Agent Authorization Form**

For Required Signature
Edwards Aquifer Protection Program
Relating to 30 TAC Chapter 213
Effective June 1, 1999

	Bud Collora	
	Print Name	
	PEC Project Manager	
	Title - Owner/President/Other	
of	Pedernales Electric Cooperative, Inc. (PEC)	
	Corporation/Partnership/Entity Name	
have authorized	Nick Sandlin, P.E.	
	Print Name of Agent/Engineer	
of	Sandlin Services, LLC	
· · · · · · · · · · · · · · · · · · ·	Print Name of Firm	

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

#### I also understand that:

- 1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
- 2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
- 3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
- 4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
- 5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

### SIGNATURE PAGE:

Applicant's Signature

Bul Blara 3-26-2024 Date

THE STATE OF Texas §

County of Blacco §

BEFORE ME, the undersigned authority, on this day personally appeared <u>Bud Colloca</u> known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 26 day of March ,2024.

CHRISTINA GONZALES
Notary Public, State of Texas
Notary ID# 13339029-4
My Commission Expires
OCTOBER 22, 2025

NOTARY PUBLIC J
Christina Gonzales
Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 10/22/2025



# **Application Fee Form** (TCEQ-0574)

## **Application Fee Form**

### **Texas Commission on Environmental Quality** Name of Proposed Regulated Entity: PEC Liberty Hill Regulated Entity Location: 10625 W SH 29, Liberty Hill, TX 78642 Name of Customer: Pedernales Electric Cooperative, Inc. Contact Person: Bud Collora Phone: <u>830-868-6056</u> Customer Reference Number (if issued):CN 601327927 Regulated Entity Reference Number (if issued):RN <u>105473979</u> **Austin Regional Office (3373)** Hays Travis X Williamson San Antonio Regional Office (3362) Medina Uvalde Bexar Comal Kinney Application fees must be paid by check, certified check, or money order, payable to the Texas Commission on Environmental Quality. Your canceled check will serve as your receipt. This form must be submitted with your fee payment. This payment is being submitted to: Austin Regional Office San Antonio Regional Office Mailed to: TCEQ - Cashier Overnight Delivery to: TCEQ - Cashier **Revenues Section** 12100 Park 35 Circle Mail Code 214 Building A, 3rd Floor P.O. Box 13088 Austin, TX 78753 Austin, TX 78711-3088 (512)239-0357 Site Location (Check All That Apply): Contributing Zone Recharge Zone **Transition Zone**

Type of Plan	Size	Fee Due
Water Pollution Abatement Plan, Contributing Zone		
Plan: One Single Family Residential Dwelling	Acres	\$
Water Pollution Abatement Plan, Contributing Zone		
Plan: Multiple Single Family Residential and Parks	Acres	\$
Water Pollution Abatement Plan, Contributing Zone		
Plan: Non-residential	6.22 Acres	\$ 5,000
Sewage Collection System	L.F.	\$
Lift Stations without sewer lines	Acres	\$
Underground or Aboveground Storage Tank Facility	Tanks	\$
Piping System(s)(only)	Each	\$
Exception	Each	\$
Extension of Time	Each	\$

Signature:	Nive Soft

Date: 3/20/2024

### **Application Fee Schedule**

**Texas Commission on Environmental Quality** 

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

### Water Pollution Abatement Plans and Modifications

Contributing Zone Plans and Modifications

	Project Area in	
Project	Acres	Fee
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial,	< 1	\$3,000
institutional, multi-family residential, schools, and	1 < 5	\$4,000
other sites where regulated activities will occur)	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

Organized Sewage Collection Systems and Modifications

Project	Cost per Linear Foot	Minimum Fee- Maximum Fee
Sewage Collection Systems	\$0.50	\$650 - \$6,500

# Underground and Aboveground Storage Tank System Facility Plans and Modifications

Project	Cost per Tank or Piping System	Minimum Fee- Maximum Fee
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

**Exception Requests** 

Project	Fee
Exception Request	\$500

Extension of Time Requests

Project	Fee
Extension of Time Request	\$150



## Check Payable to the "Texas Commission on Environmental Quality"



# Core Data Form (TCEQ-10400)



# **TCEQ Core Data Form**

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

### **SECTION I: General Information**

1. Reason for	Submissi	<b>on</b> (If other is checked	please descri	be in space pr	ovided.)							
☐ New Pern	nit, Registra	ation or Authorization	(Core Data Foi	rm should be s	submitted w	ith the prog	gram application.)					
Renewal (Core Data Form should be submitted with the renewal form)							Other					
2. Customer Reference Number (if issued)  Follow this lin						<u>-</u>	gulated Entity Re	ference	Number (if i	issued)		
CN 601327927					N numbers in Registry**		105473979					
SECTIO	N II:	Customer	Inforr	mation	<u>1</u>							
4. General Customer Information 5. Effective Date for Customer Information							nation Updates (mm/dd/yyyy)					
New Custor	New Customer											
☐Change in L	egal Name	(Verifiable with the Te	kas Secretary o	of State or Tex	as Comptro	ller of Publi	c Accounts)					
The Custome	r Name su	ıbmitted here may l	be updated o	automatical	ly based o	n what is o	current and active	with th	ne Texas Seci	retary of State		
(SOS) or Texa	s Comptro	oller of Public Accou	ints (CPA).									
6. Customer	Legal Nam	ne (If an individual, pri	nt last name fi	irst: eg: Doe, J	lohn)		If new Customer,	enter pre	evious Custom	er below:		
PEDERNALES ELECTRIC COOPERATIVE INC												
7. TX SOS/CP	A Filing N	umber	8. TX State	<b>Tax ID</b> (11 d	ligits)		9. Federal Tax ID 10. DUNS Number (if			Number (if		
0007336401			1740828412	27			(9 digits)		applicable)			
	000/330 101						, ,					
11. Type of C	ustomer:		tion			☐ Indivi	Individual Partnership: G			neral 🔲 Limited		
Government: City County Federal Local State Other							Sole Proprietorship					
12. Number of Employees 13. Independently Owned and Operated?												
□ 0-20 □ 21-100 □ 101-250 □ 251-500 □ 501 and higher □ <b>Yes</b> □ <b>No</b>												
14. Customer	r <b>Role</b> (Pro	posed or Actual) – as i	t relates to the	e Regulated Ei	ntity listed o	n this form.	Please check one o	f the follo	owing			
Owner		Operator	⊠ o	wner & Opera	ator							
Occupational Licensee Responsible Party VCP/BSA Applicant Other:												
P.O. BOX 1  15. Mailing												
Address:	City	Johnson City		State	TX	ZIP	78636		ZIP + 4			
16. Country I	 Mailing Inf	 formation (if outside	USA)		17	'. E-Mail A	ddress (if applicab	le)				
18 Telenhon	e Number			19 Fytensio	on or Code		20 Fay N	lumher	(if annlicable)			

TCEQ-10400 (11/22) Page 1 of 3

SECTION III: I	Regul	ated En	tity I	nform	atior	<u>1</u>						
21. General Regulated En	tity Inform	nation (If 'New Re	gulated Ent	ity" is select	ted, a new p	permit applica	tion is also r	equired.)				
☐ New Regulated Entity ☐ Update to Regulated Entity Name ☐ Update to Regulated Entity Information												
The Regulated Entity Nan as Inc, LP, or LLC).	ne submitt	ed may be updo	ated, in ord	der to mee	t TCEQ Co	re Data Star	ndards (rer	noval of or	ganization	al endings such		
22. Regulated Entity Nam	<b>e</b> (Enter nai	me of the site whe	ere the regu	lated action	is taking pl	ace.)						
PEC Liberty Hill												
23. Street Address of the Regulated Entity:	10625 W SH 29											
(No PO Boxes)					T	1	1	1		1		
<u>inter e penesj</u>	City	y Liberty Hill		te	TX	ZIP	78642		ZIP + 4			
24. County	Williamso	n										
If no Street Address is provided, fields 25-28 are required.												
25. Description to												
Physical Location:	Physical Location:											
26. Nearest City State Nearest ZIP Code												
Latitude/Longitude are re used to supply coordinate	-	-	-			Data Standa	rds. (Geoc	oding of th	e Physical	Address may be		
<b>27. Latitude (N) In Decimal:</b> 30.649222 <b>28. Longitude (W) In Decimal:</b> -97.863481								81				
Degrees	Minutes		Seconds		Degrees		Mi	nutes		Seconds		
30		38	!	57.20	-97			51		48.53		
29. Primary SIC Code		31. Primary NAICS Code 32. Secondary NAICS Code					CS Code					
(4 digits) (5 or 6 digits) (5 or 6 digits)												
4911 221122												
33. What is the Primary B	usiness of	this entity? ([	Do not reped	nt the SIC or	NAICS desc	ription.)		ı				
PEC Operations Center												
	P.O. Box	1										
34. Mailing												
Address:	City	Johnson City		State	тх	ZIP	78636		ZIP + 4			
35. E-Mail Address:					<u> </u>							

**39. TCEQ Programs and ID Numbers** Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.

37. Extension or Code

36. Telephone Number

) -

TCEQ-10400 (11/22) Page 2 of 3

38. Fax Number (if applicable)

) -

☐ Dam Safety	Districts	Edwards Aquifer		Emissions inventory Ai	ir Industriai Hazardous waste			
		11-08030503 (4/16/2	008)					
		11001078 (Mod 5/23)	/2018)					
Municipal Solid Waste	e New Source Review Air	OSSF		Petroleum Storage Tan	nk PWS			
Sludge	Storm Water	☐ Title V Air		☐ Tires	Used Oil			
☐ Voluntary Cleanup	☐ Wastewater	☐ Wastewater Agric	ulture	☐ Water Rights	Other:			
SECTION IV: Preparer Information								
40. Name: Nick Sandlin, P.E. (Sandlin Services, LLC)		C)	41. Title:	Principal / Profession	al Engineer			
42. Telephone Number	43. Ext./Code	44. Fax Number	45. E-Ma	il Address				
(806) 679-7303		( ) -	nick@san	dlinservices.com				
			L					

### **SECTION V: Authorized Signature**

**46.** By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	Sandlin Services, LLC	Professional Engineer			
Name (In Print):	Nick Sandlin, P.E.	Phone:	( 806 ) 679- <b>7303</b>		
Signature:	Nive Sort			Date:	3/20/2024

TCEQ-10400 (11/22) Page 3 of 3